

Save Energy for Benefit of Self and Nation



PR NO	327116
RFQ NO	44802

## Tender Notice No.13/2017-18

TO,  
M/s \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Name of Work Open Tender for LABOUR CHARE FOR U/G LAYING OF 11KV XLPE CABLE for approved work at CHHAPI S/DN Under SIDHPUR DO for N D Scheme . Part-1  
Tender Notice No

Estimate cost.	<b>Rs. 499544.00</b>
Earnest Money.	Rs. 5000.00
Security Deposit.	5% of order value.
Last date of receipt of tender/EMD at	Date: 06-10-2017 On 15.00 Hrs. (By RPAD)
Date of opening the tender at	Date: 07-10-2017 On 15.00 Hrs. (If Possible )
Type of tender	Item Rate.
Tender Fee	Rs. 500.00+GST Applicable
Time Limit	12 Month

Earnest money deposit will be accepted in cash or by demand draft on any schedule bank at SIDHPUR in favor of UTTAR GUJARAT VIJ COMPANY LIMITED, cheques or Bank guarantee will not be accepted. The tender without Earnest Money deposit will not be accepted. The date of D.D of EMD should be within 10 days from the date of receipt of tender.

Tender received through RPAD will be accepted.

SUPDT.ACCTT.  
UGVCL, DO, SIDHPUR.

EXECUTIVE ENGINEER  
UGVCL, DO, SIDHPUR.

---

Division Office: Highway Near Madhav Hotel, Sidhpur (North Gujarat)  
Telephone: (02767) 225090 Website: www.ugvcl.com  
e-mail: eesiddo@ugvcl.com

**SCHEDULE-B**

**Name of works:** - Labour charges for underground work for laying 11 kV XLPE cable of approved work At Chhapi S/Dn Under SIDHPUR Division.(As & When Required)

SR NO	ITEAM DESCRIPTION	UNIT	QTY	Supply RATE	Labour RATE	AMOUNT
1	Labour charges for Horizontal: State / NH/ TAR Road crossing by push through method at a depth of minimum 4 feet from Ground level & using G.I pipe of size 100/150 mm. <b>The rates are Excluding pipe.</b> Onlycable will be supplied by UGVCL. 990600001	MTR	2	0	824	1650
2	Laying of underground cable-HT/LT cable including digging of pit (4FT), Laying of cable with providing cable trench with bricks/half round PCC slab and refilling the trench. <b>9911000013</b>	MTR	650	0	305	198250
3	Laying of XLPE - HT/ LT cable open to air ground to Gentry including carting990600001	MTR	100	0	175	17500
4	Supply of medium grade GI pipe of size 4" dia (Including clamping the cable with pole) . 990600001	MTR	25	945	0	23625
5	Supply of HDPE pipe for laying 11KV XLPE cable 140mm diameter & 6mm thickness as per IS:4985. 990600001	MTR	100	500	0	50000
6	Supply of route marker of 150mm x 150mm concrete stone UGVCL marked embedded in earth at, at least 300mm below the ground level and 450mm above ground level at distance of approx. 30 meters along the length of cable. The route marker should be paintedwith UGVCL's blue colour The rate is inclusive of cost of paint. <b>9915020010</b>	Each	30	130	165	8850
7	Supply of HT push on/heat shrink type straight joint preferably 3m(m-seal) or Raychem make or equivalent for 3 core 185 Sq mm 11 KV XLPE aluminium conductor armoured cable as specified with connection of leads including cutting stripping of cable insulations providing compression type terminals crimping of lugs with suitable crimping tool <b>9915020015</b>	Each	5	7000	1041	40205
8	Providing & fixing Earthing of cable using G I Pipe, good quality and as per specification.	Each	30	1800	400	66000
9	Supply of HT push on/heat shrink type Outdoor cable kit preferably 3m(m-seal) or Raychem make or equivalent for 3 core 185 Sq mm 11 KV XLPE aluminium conductor armoured cable as per	No	14	535	1041	

Division Office: Highway Near Madhav Hotel,Sidhpur (North Gujarat)  
 Telephone: (02767) 225090 Website: www.ugvcl.com  
 e-mail:eesiddo@ugvcl.com

specified.						93464
<b>Total RS.</b>						<b>499544.00</b>

The rates quote rate \_\_\_\_\_% above/bellow to the scheduled rates as shown in S C H E D U L E -B above.

**Executive Engineer  
SIDHPUR**

**Contractor's Signature.**

1. Each And Every Size Of Nut Bolts Provided By UGVCL, If company not provided, Rs. 65/Kg paid after submission of bill by Contractor.

2.

**-Income Tax at prevailing rate will be deducted as per Income Tax Act.  
Period of contract. CST/GST will be applicable as per Govt notification**

As per GST Act,UGVCL is in the process of amending various Commercial Terms & conditions of Tender. The following Terms & conditions to be amended are given below:-

Name of Terms & conditions	To be added/amended
Tender fee	Plus applicable GST
Prices	Replace Excise duty,VAT/Sales Tax by GST
Excise duty	Replace Excise duty,VAT/Sales Tax by GST
Sales/VAT (Value Added Tax)	Replace Excise duty,VAT/Sales Tax by GST
Octroi	To be deleted

The present tender is floated with Pre-GST regime. The Modification in line with GST Act will be bound to all the bidders

**Executive Engineer  
Sidhpur**

**Contractor's Signature.**

The present tender is floated with Pre-GST regime. The Modification in line with GST Act will be bound to all the bidders

(i) UGVCL VENDOR REGISTRATION SHOULD BE ATTACHED WITH TECH. BID.

Sr.No.	Class of Vendor Regis.	Minimum Experience in years	Under ground work of 11 KV XLPE cable in the area of <b>SIDHPUR DO</b>
1	CLASS-A	5 YEARS	Can participate in tender of the erection work of HT/LT/TC line for any amount tender invited through limited/open/n-code by division/circle.Vendor registration mandatory.
2	CLASS-B	3 YEARS	Can participate in tender of the erection work of HT/LT/TC line for any amount up to Rs. 10 lacs, tender invited through limited/open/n-code by division/circle.Vendor registration mandatory.
3	CLASS-C	1 YEARS	Can participate in tender of the erection work of HT/LT/TC line for any amount up to Rs. 5 lacs. tender invited through limited/open/n-code by division/circle.Vendor registration mandatory.

Division Office: Highway Near Madhav Hotel,Sidhpur (North Gujarat)  
Telephone: (02767) 225090 Website: www.ugvcl.com  
e-mail:eesiddo@ugvcl.com

Executive Engineer  
Sidhpur

\_\_\_\_\_  
Contractor's Signature.

*Save Energy for Benefit of Self and Nation*



#### SPECIFICATIONS

**For erection work of 11 KV Transmission lines.LT distribution lines and transformer sub-stations.  
ERECTION OF HT AND LT LINES.:**

**(a) Site** clearing and tree cutting which come in the way of line will be done by the contractor at his cost. Any claim for compensation in above respect will have to be borne by the contractor.

**(b) Fixing** : Pole position :The position of pole structures guys and earthings will be fixed by the department and shown to the contractor. He shall adhere to these locations in all circumstances unless. Directed by the department to make any change.

**(c) Pole setting** :

Where poles are set in good solid ground the depth of pit shall be 1/6 the height of the pole and for grounds of any other nature depth of the pit shall be decided by the department. The poles and guys must not be set at the edge of cut/at shore/ embankments where soil is liable to be washed or eroded out such setting should be avoided while back filling, the each must be packed tight and in no case must earth be dumped to greater depth than four inches without being rammed hard before the next layer is thrown in extra earth should be packed around the poles and rammed. The cost of damage done to the pole during the erection will be recovered from the contractor. No pole which is out of plumb or out of alignment shall be accepted. The contractor will keep the poles and other materials in his safe custody in erected and he is liable to compensate to the Company the full cost of same along with supervision charges, if the pole is broken during the erection or stolen from him custody. He should be able to render full account of

the poles entrusted to him whenever the supervising officer demands to scrutinizes the same.

#### **1. Erection of Complete Single Pole Structure.**

Erection of single pole structure comprises of shifting of pole from the place in the village to the site of actual work in that village excavation of pit erection in position (with base place where required) of 26' to

Division Office: Highway Near Madhav Hotel, Sidhpur (North Gujarat)

Telephone: (02767) 225090 Website: www.ugvcl.com

e-mail: eesiddo@ugvcl.com

33' PSC poles 60 lbs/Yds. 30' to 42' long rail or suitable size girder or any other suitable pole fitting up clamps and cross arms and fabricated materials etc. Complete as per drawing inclusive of numbering fixing of caution Company and anticlimbing device. All size of Bolts and Nuts required should be used by the contractor at his cost. All the fabricated materials such as cross arms clamps turn buckles etc. fitted on the PSC poles of RCC poles should be painted first coat with red lead paint and then two coats of aluminum paint. The tendered has to use all the paints at his cost and should get approved by the Engineer-in-charge before use.-Do- same as item No.1 (a and also including painting of steel poles)

## **2. Special two poles structures.**

Special two poles structures such as for HT line tapping Railway crossing any other HT, LT or telephone line crossing, terminal structure comprises of excavation of suitable pits and refilling of earth, erection in position of two numbers 26' to 33' PSC poles 60 lbs/Yds 30' to 42' long rails or any other suitable poles fitting of clamps and cross arms. Cross bracing etc. as per drawing inclusive of mounting H.G.Fuses (or A B Switch or HT metering equipments etc. numbering, fixing of caution Board and anticlimbing device. The D.P. must be properly aligned and must be special structure if included will be erected as per drawing supplied. A size of bolts and nuts required for fitting the fabrication should be used by the at his cost including painting as per item No.1.

## **3. Stringing of Conductors.**

This includes stringing of standard and solid bare conductors with fitting has necessary HT/LT pin and strain insulators, binding on insulators, jumpering jointing, The jointing in HT line will be done by twisting sleeve joints as per standard practice, Care must be taken in handling the conductor must not be drawn over tough or rocky ground, where it is liable to be damaged Aluminium and ACSR conductors must be drawn on wooden or aluminium pulleys only the conductor or coil must not be dropped Westage and cutting should be avoided as far as possible, Not more than 5% scrap will be accepted in the material account drawing to the proper tension. The sag and spans will be maintained as per drawing and design. The cross arms and insulators must be so fixed that neither tilts or bends in any position. The rate quoted should be per conductor route kilometer. The span and sag. However may vary according to sizes of poles available but these dimensions will be specified by the field Engineer before commencement of work.. The sagging should be uniform for all conductors and uneven sagging will not be allowed.

## **4. Stringing of Continue cuss Earth Wire.**

Where required the stringing of G.I. Wire No. 1 or S.W.G. is to be carried out for continuous earth wire and sag should be kept appropriate as per the conductor and continuous earth wire should be fixed on cross arm by using "011" size bolts nuts and washers. The required bolts nuts and washers should be used by the contractor at his cost. All the fabricated cross arms sited on the pole should be connected to the earth wire by G.I.Wire.

### **4.(a) Guarding.**

The guarding will have to be provided between crossing of HT and LT lines below the entire railway crossing. At the crossing at the crossing to telephone or telegraphs line (Licensee's HT and LT lines are passing below Company's HT line) road crossing and such other places as indicated by the department. The work comprises of fixing of guard cross-arms, eye bolts guard cradle as per design. Binding cross arms must be used where the HT line crosses the road. A clearance of 20 ft. must be available for all road crossing. The poles for road crossing must be concreted. The work has to be carried out as per drawings specially prepared for the purpose Guarding for railways crossing is to be carried out as per instructions of the Engineer-in-charge.

## **5. Erection of Stay set.**

The erection of stay comprises of excavation of pit of 2'x2'x4' depth burying stay rods anchor plate, fixing of turn buckle binding of GI Stay wire. The stay insulators must be inserted in the stay wire on all stays as per drawing. The wrapping of the Guy wire strands at both ends at the stay insulator must be even and must present neat appearance and good workmanship. No stay should be left loose but should be tight and straight to withstand any cyclone or stand storm. The item includes refilling of earth and painting paint should be used by the contractor at his cost. If the guys are not required to be concreted, a per-casted cement concrete block will be supplied by the department at his divisional store at SIDHPUR which the contractor will have to transport at his cost to the site of work and will have to use for fixing the

guy road rate includes transportation and using the same in place of cement concreting of the guy. If the block is damaged during transport the cost of same will be recovered from the contractor.

**6.** Cement concreting for rail of R.S.J. pole or stay rod should be carried out in preparation 1:3:6 i.e. one part of cement three part of washed river sand and six part of well burnt brick-bat of 1x 1FF" size metals. The mixture should be prepared on the GI sheets and should be free from the dust the river sand, cement and the metal or brickbat should be used by the contractor at his cost.

**7.** Concreting for muffing of poles or stay rods should be as per item No. 6 above and size of the boxing provided should be Dia. Of 1.5 feet X height 3 feet and 1.5 feet should remain below the ground level and 1.5 feet should remain above the ground level.

#### **8. Earthing**

A pit of 2'x2'x6' is to be dug about 3' away from the pole on which earthing is required to be carried out. The earthing pipe supplied should be erected in the pit and should be hammered in the ground as far as possible and G.I.Wire for earthing should be bolted with the pipe and should be connected with earth wire of the pole by means of bolt 10 kg. of common salt and coal-dust should be provided per earthing by the contractor at his cost. Bolts nuts and washers should be used by the contractor at his cost.

#### **9. Erection of Pole Mounted Transformer Center.**

This work includes erection of special two pole structure as per item No.2 and fixing of all fabricated materials for support of line, L.A.H.G. fuses. A.B. switches transformer L.T. Dist. Box etc. The work includes of transportation and hoisting of transformer fixing of H.G. fuses A.B. switch L. As Distribution Box bilding numbering and V.I.R. or P.V.C. wiring and prodding two earthings as per the specifications and the instructions of the Engineer-in-charge including painting.

(a) Up to and including 100 KVA

(b) –do- as above but transformer above 100 KVA capacities.

#### **10. (A) Painting of Transformer Structure & Febrication of New erected pole for new lines :**

All the galvanized fabricated materials to be used on the structure for transformer & new erected pole for new line will be provided by UGVCL.

**(B)** The Fabrication to be used for augmentation, renovation and modernization of existing line and sub station should be painted first with on coat of red oxide and then with two coats of good quality of alluminium paint should be applied by the contractor at his cost. The paint should be

got approved by the Engineer in charge before use.

#### **11. Testing of Material provided by contractor**

The materials supplied by the contractor as per the schedule-B must be tested & approved by recognized inspector of UGVCL.

12. While work Execution contactor's can not take any help from applicant/beneficiary.

**Signature of Contractor**

**Executive Engineer**  
Sidhpur.

#### **SIGHT EXECUTION TERMS & CONDITIONS**

1. The Contractor shall consider the site conditions of underground cable laying work before quoting the offer.
2. Contractor shall have to strictly follow all the instructions, terms and conditions and concerns by the respective Government authorities. The necessary approval/NOC's etc. is to be obtained by the Contractor from concern R & B/NHAI/STATE HIGHWAY & etc. Govt Authority.
3. (Liasoning Work)
4. All materials used shall be of approved/good quality and as per directions and instructions of Engineer- in- Charge.

Division Office: Highway Near Madhav Hotel, Sidhpur (North Gujarat)  
Telephone: (02767) 225090 Website: www.ugvcl.com  
e-mail: eesiddo@ugvcl.com

5. Work under normal land and at DP structure to be carried out as per instructions by Engineer in charge of UGVCL.
6. Looping of cable is to be done in the ground below DP structure by excavating earth and approximately 06 meters of looping to be laid in the excavated earth on both sides. After which the same shall be filled with sand and warning bricks shall be provided on cable for which no extra payment will be made.
7. Cable removing from drums shall be done with proper care as no damage to the power cable normally 11 KV XLPE 3 core cable of size 150 mm<sup>2</sup> to 240 mm<sup>2</sup> ( any one size) according to availability will be supplied by UGVCL for laying underground work.
8. Where the cable rise from ground to DP structure the each power cable to be taken separately in 4" (100 mm dia) G.I. pipe for mechanical protection of the XLPE cable GI may be kept approximately 4 meters.
9. The Length, quantity and distance mentioned in Schedule is approximate. It can be increased or decreased. The payment will be made as per actual quantity executed.
10. The Contractor will have to provide cable markers made from 3 mm thick MS plate (400 mm x 260 mm) along with the MS angle of 50 mm x 50 mm size at least 1700 mm long and the same shall be painted in Red & White colour with all the necessary instructions written in English, Gujarati & Hindi language clearly painted on it after which the same shall be concreted with the help of cement, sand, aggregate stone and water as per approved drawings of Railway and as per the direction of Railway authorities.
11. Contractors have to observe the standard norms/rules and regulations of the Railway while lying of cable work under Railway areas, failing which to do so are the responsibility of the Contractor.
12. Empty cable drum to be returned after completion of work, however the site Engineer will issue the required 11 KV XLPE cable for the above work.
13. The Contractor has to ensure that the work would be run smoothly throughout the period of the contract and work should be completed in time.
14. UGVCL, SIDHPUR will not be responsible for any loss, damages etc. as a result of the Contract.
15. Any damages to any of the Government / private property during the execution of work shall be on your account and you shall make good the same. Claims arising out of the damages shall have to be borne and settled by you.
16. All the power cable routes shall be carefully measured and the required cable shall be cut to the required length for laying sufficient length, for the final connection of the cable to the terminal of the equipment. Undue wastage shall be avoided.
17. The company shall not be responsible for any kind of accident during the execution of the work by the contractor. The contractor shall have to hold the responsibilities of any accident that occurs during the execution of the work. The contractor shall settle any issue arising out of any occurrence that takes place during execution of the work; on his own.
18. Contractor has to submit feeder map with signature and stamp mentioning the U/G cable work carried out along with location of straight joint and outdoor/indoor kit location to S/dn and one copy to Division Office. Also, the name of the contractor to be written by marker pen on straight joint and outdoor/indoor kit.
19. Work to be carried out in other sub Division under jurisdiction of SIDHPUR Division in case of emergency.

**Executive Engineer  
SIDHPUR**

**: GENERAL INSTRUCTION TO TENDERERS :-**

Division Office: Highway Near Madhav Hotel, Sidhpur (North Gujarat)  
Telephone: (02767) 225090 Website: www.ugvcl.com  
e-mail: eesiddo@ugvcl.com

**1.0** Tender are invited for the work of **erection of HT/LT line, T/C & U/G** Cable at CHHAPI S/Dn office under division office Sidhpur from the contractors/firms who have executed works of similar nature and magnitude successfully and who are registered under class B under UGVCL

**2.0 Tender documents are in two bids system i.e. “Technical Bid” and “Price Bid”.**

**2.1** Bidder has to submit tender in one Envelop and in this two different covers should be put. One cover mentioning **Technical bid** on it & another cover mentioning **Commercial Bid** on it. If we receive envelop that do not have two separate sealed covers than those bids are liable to be rejected. Technical bid should be submitted with documents as under, failing which tender is liable for rejection.

- (i) Solvency certificate issued from any Nationalized Bank amounting to sum equivalent of estimated cost .
- (ii) At least Rs. 10.00 Lacs turn over in Bank Statement For the Year 2016-17
- (iii) Separate EPF code No. allotted by RPFC & Last Six month of current year EPF Challan Bank paid copy is required.
- (iii) The Vender Registration certificate in appropriate class as contractor in UGVCL require. The vender registration fees paid challan /receipt attached by bidder will not be acceptable.
- (iv) Latest income tax clearance certificate Year of 2016-17. With PAN card.
- (v) Labour license certificate.
- (vi) Experience :-Contractor should produce evidence of executing similar nature & magnitude of work i.e. **Erection of HT-LT line ,Tc**. The Experience certificate of minimum 3 Yr. and satisfactory completion of work ; issued by Executive Engineer of respective division is require.
- (vii) For contractors should have carried out Underground cable laying work, he has to produce certificate from concern division, stating that they have carried out work satisfactory that not less than 2 KMs. Experience certificate as per requirement for above work by authorized Officer – NOT BELLOW THE RANK OF EXECUTIVE ENGINEER - of Distribution Company of DISCOM.
- (viii) Group Insurance A copy of the insurance policy of the insured laborer’s under W.C. Act.
- (ix) Details of equipments available with the tendered & Tools & tackle Certificate
- (x) Turn over details year wise on CA Letterhead At least 3 years.
- (xi) Copy of the last three year work orders of erection of HT/LT line & T/C and under ground cable work of any Distribution Company is required.
- (xii) GST registration no must be submitted with tender .
- (xiii) Govt. license to electrical contractor issued by Govt. of Gujarat is required.

The above documents should be submitted in form of attested true copies along with technical bid. If any documents are not submitted by bidder than do not consider those bidder proposal & do not open price bid of those bidder, and this tender is liable to rejection.



- 2.2** Both “Technical” & ” Commercial” bid should be submitted in one common envelope super scribing the name of the work and tender opening date etc.
- 3.1** Technical bid shall be opened on date ..... at **11.00** hrs. (If possible) in the presence of the bidders, who remains present at that time.

**4.0** Earnest money deposit of 1% of Tender amount should be deposited in form of DD of Nationalized Bank in favor of UTTAR GUJARAT VIJ COMPANY LIMITED drawn on any scheduled Bank, payable at SIDHPUR. No any tender accepted without EMD. The date of D.D of EMD should be in between 10 days from the last date of receipt of tender.

**5.0** Bidders should complete the tender documents in all respects and they are to be signed with Company’s seal on all pages.

**6.0** The bidders shall submit their offer without any deviations in general terms and conditions of the contract or in Technical specification/items. Tenders of such departing, may also be rejected. Incomplete and conditional tenders shall not be considered. Any Tender found with overwriting /correction on the rate will not be accepted.

**7.0** UTTAR GUJARAT VIJ COM.LTD. reserves the right to split up the work covered in the scope of this contract amongst more than one contractor.

**8.0** Intending bidders should submit their tenders after studying all tenders documents carefully and visiting the site for satisfying themselves of actual site conditions, location and accessibility of site and nature, extent of the work involved etc.

Submission of tenders implies that bidders have obtained all necessary information and other data required for executing the work. No claim for extra charges on account of any misunderstanding or otherwise will be allowed.

**10.0** All approaches to the site shall be in the scope of bidders.

**11.0** Bidders will not be allowed to give sub-contract of the works awarded to in for any, reasons what so ever without permission of the Engineer-in charge.

**12.0** In the experience certificate, contractor has to furnish the details of similar works executed by him along with the list of equipments, tools and tackles and manpower available with him along with the details of the same, which he intends to deploy on site of the work.

**13.0** After opening of “Technical bid” no revised price bid from any bidders will be accepted.

**14.0** Price quoted shall be firm, till overall completion of the work, under contract and there will not be any price escalation.

**15.0** Date of opening of “Price Bid” will be intimated later on to those Bidders who are qualified in technical bid. “Price bid” of only qualifying bidders on the basis of Technical bid shall only be opened. Price of bidders, who are not qualified technically as per requirement of technical bid shall not be opened.

***Save Energy for Benefit of Self and Nation***



Division Office: Highway Near Madhav Hotel, Sidhpur (North Gujarat)  
Telephone: (02767) 225090 Website: www.ugvcl.com  
e-mail: eesiddo@ugvcl.com

**16.0** Offers shall be valid for the period of 120 days from the date of opening of price bid. Tenders shall not withdraw tenders during the validity period, failing which their EMD shall be forfeited during the said period of 120 days.

**17.0** All the works shall be carried out as per specifications attached with the tender and relevant Indian Standard issued by Bureau Indian Standards. All materials procured should be confirming to relevant Indian Standard issued by Bureau of Indian Standard.

**18.0** Tenders, which do not fulfill all or any of the conditions of the tender of in complete in any respect, are liable to rejection.

**19.0** UTTAR GUJARAT VIJ COMPANY LTD, reserves the right to reject any or all tenders without assigning any reason thereof.

**20.0** Income Tax at prevailing rate will be deducted as per income Tax Act.

**21.0** The rates are inclusive of PF and all other State/Central Government taxes. All type of Excise duty tax, sales/VAT tax, Service replaced by GST.

## **22.0 Taxes and Duties:**

The price ara excluding GST and CESS as applicable which will be paid extra on a given taxable goods and/or service within the original contractual delivery period. The amount and % of GST and CESS as applicable should clearly be indicated saperately. (GST/CESS means all applicable TAX/CESS under GST Laws. GST Laws means IGST Act, GST ( Compensation to the Stae for Loss of Revenue) Act, CGST Act, UGST Act and SGST Act -2017 and all related ancilliary legislation).

Supplies/Contractor should charge GST in invoice at the rate as agreed to /mentioned in acceptance of Tender only and any deviation in the same shall not be accepted . Further any additional liability of GST (later on due to wrongmentioning of GST rate, mis interpretation of HSN/SAC code, etc.) over and above as charged in the invoice shall be borne by the Supplier/ Contractor. However , any refund received by the supplier / contractor on account og GST charged from the company , such refund shall have to be passed on to the company , along with interest if any. Such refund along with interest needs to be passed on suo-moto by the supplier/ Contractor.

Further the company has a right to recover the amount of GST along with penal interest at the rate of 15% per annum if GST charged is not paid /short paid to the government or fail to upload the details or uploads inaccurate particulars on GSTIN portal by the Supplier/ Contractor within the stipulated time limit.

In case , Govt. revises the rate of GST rate / Code during the tenure of the contract , the provision of UGVCL's statutory variation clause shall apply.

## **22.1 STATUTORY VARIATION:**

Any statutory increase or decrease in the taxes and duties including GST and Cess as applicable or in the event of introduction of new tax/cess or cessation of existing tax/cess subsequent to contractors offer if it takes place within the original contractual delivery date will be to COMPANY's account subject to the claim being supported by documentary evidence . However , if any decrease takes place after the contractual delivery date, the advantage will have to be passed on to COMPANY.

## **22.2 PENALTY FOR LATE DELIVERY:**

Penalty shall be @ 0.5% per Week or part thereof plus GST as applicable on delayed portion subject to maximum 10% plus GST as applicable of the delayed portion Order Value ( End Cost with GST and Cess as applicable ) in case of supply only, whereas in case of Project, the ceiling shall be with reference to total contract value with GST and Cess as applicable of the project (Supply +Erection+Civil ) . For calculating the delayed portion, date of actual receipt of material at store shall be considered

Division Office: Highway Near Madhav Hotel, Sidhpur (North Gujarat)  
Telephone: (02767) 225090 Website: www.ugvcl.com  
e-mail: eesiddo@ugvcl.com

**23.0** If any work will not be executed by contractor fully / partly due to non providing of materials by UGVCL ,than the amount at appropriate rate will be deducted from the contractors bill , as the amount of non execution of works is already included in the rate of order.

**24.0** Terms & condition & other relevant documents is required .

**25.0** D.D. for EMD should be kept with “technical bid” only .

**26.0** Tender without payment of tender fee will not be accepted.

**30.0** Delay /late receipt of tender will be rejected.

**27.0** Successful bidder should have to pay security Deposit should be paid through D.D of any Nationalized/ Schedule Bank in favor of Utter Gujarat Vij Company Ltd.” payable at Sidhpur.

**28.0 Right to reject any or all tenders without assigning any reason there of is reserved by the undersigned.**

**Signature of Contractor**  
**Name Seal, Details address**  
**With phone/fax.**

**Executive Engineer**  
**Sidhpur**

*Save Energy for Benefit of Self and Nation*

