



REF. No.	PART NAME	No. REQ	SIZE	MATERIAL	REMARKS
10	GI Strip	1	50 x 6 MM	GI	-
9	OPERATING HOOK	6	-	ALUMINIUM	-
8	11 KV POST INSULATOR	6	254mm HEIGHT	POLYMERIC	Min. 320mm CD
7	OUT GOING TERMINAL	3	-	E C COPPER	TIN PLATED
6	INCOMING TERMINAL	3	-	E C COPPER	TIN PLATED
5	FEMALE CONTACT	6	-	E C COPPER	TIN PLATED
4	MALE CONTACT	3	-	E C COPPER	TIN PLATED
3	MOUNTING HOLE	4	Ø18X55 SLOT	-	-
2	EARTHING TERMINAL	3	M10 BOLT	-	HOTDIP GALV.
1	MOUNTING CHANNEL	3	C 75X40	F.R.P	F.R.P

- ALL DIMENSIONS ARE TO BE READ AND NOT TO BE MEASURED.
 - IN CASE OF ANY DISCREPANCY BETWEEN GPRD CELL-GUVNL, GOG DRGS. AND OTHER DRGS. DISCREPANCY SHOULD BE BROUGHT TO THE NOTICE OF THE GPRD BEFORE COMMENCEMENT OF THE WORK.
 - IN CASE OF ANY AMBIGUITIES ON SITE, THE GPRD SHOULD BE INFORMED.
 - IT IS MUST TO INFORM AND TO HAVE PRIOR PERMISSION OF GPRD BEFORE MAKING ANY CHANGES ON SITE.
 - REFER THE LATEST REVISED DRAWING.

POTISION - 1

POTISION - 2

POTISION - 3

SIDE VIEW

TOP VIEW

Research Proj. No: RP 014
 Date: 10.01.2018
 Drawing. No: 12

Drawing Prepared By: *Abhishek Borsliagar*
 Checked By: *A R Vaikhatya*
 Approved By: *P B Patel*

Project Name:
 11 KV ABEB Switch
 Title:
 11KV 600A DISCONNECTOR
 EARTH SWITCH