UGVCL
Uttar Gujarat Vij Company Ltd.
Corporate Office: Visnagar Road, Mehsana-384001, Gujarat
Phone: (02762) 222080-81 Fax: (02762) 223574 E-mail : corporate@ugvcl.com
CIN NO:U40102GJ2003SGC042906

PURCHASE REQUISITION 370743

Description	**Construction of Kanodar Sub Division Office Building at 66 KV S/S Kanodar**				
Requisition Type	**----**	**Finally Approved Date**	**:**		
Requisition for Repeat PO	**----**	**Approver Note**	**:**		
				Mr. NARENDRAKUMAR RAMESHCHANDRA	
Tender Type	**----**	**Preparer**	**:**	**PATEL**	
Creation Date	**12-NOV-18**	**Current_Approver**	**:**	**Mr. AMRABHAI SUJABHAI DAMOR**	
		Final Approver	**:**	**----**	

Requisition Lines

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
1	9501040002	Excavation for foundation upto 1.5 M. depth including sorting out and stacking of useful materials and disposing off excavated stuff up to 50M. lead.(b) Dense or hard soil	95.00	Cubmic Meter	550	85.9	47245	0	47245		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
2	9501040007	Excavation for foundation for depth from 1.5 Mt to 3 Mt. including sorting out and stacking of useful materials and disposing off the excavated stuff up to 50 Mt. lead.(b) Dense or hard soil	95.00	Cubmic Meter	115	93.2	10718	0	10718		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
3	9501050004	Providing and laying C.C. 1:4:8 and curing complete excl. cost of from work in : Foundation and plinth	95.00	Cubmic Meter	220	2231	490820	0	490820		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
4	9501060005	Brick work using common Brunt clay building bricks having crushing strength not less than 35 Kg./Sqcm. In foundation and plinth in cement mortar 1:6: Conventional	95.00	Cubmic Meter	105	2879	302295	0	302295		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
5	9501040026	Filling available excavated earth (excluding rock) in trenches, plinth, sides of	95.00	Cubmic	600	76.5	45900	0	45900		Mr. NARENDRAKUMAR

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		foundations etc. in layers not exceeding 20 cm. In depth consolidating EA deposited layer by ramming and watering.		Meter							RAMESHCHANDRA PATEL Palanpur Circle
6	9501040028	Filling in foundation and plinth with murrum or selected soil in layers of 20 cm. Thickness including watering ramming and consolidating etc. comp.	95.00	Cubmic Meter	500	266	133000	0	133000		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
7	9501040040	Earthwork in cutting in all sorts of soil and soft murrum including conveying and filling/spreading the stuff in 200 mm layers as and where directed from the end of the cutting with all required lead & lift etc.complete.	95.00	Cubmic Meter	75	80.3	6022.5	0	6022.5		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
8	9501040027	Filling in plinth with sand under floors including watering ramming, consolidating and dressing etc. comp.	95.00	Cubmic Meter	85	416	35360	0	35360		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
9	9501050100	Providing and laying M-200 and finshing smooth curing etc complete incl.the cost of form work but excluding the cost of reinforcement for R.C.c. work in Slabs having more than 10cm and up to 13 cm thickness up to two floor level.	95.00	Cubmic Meter	63	5124.48	322842.24	0	322842.24		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
10	9501050108	Providing and laying M-200 and finshing smooth curing etc complete incl.the cost of form work but excluding the cost of reinforcement for R.C.C. work in beam having cross sectional area more than 0.12 sqm & up to 0.18sqm. up to floor two level.	95.00	Cubmic Meter	30	5074.48	152234.4	0	152234.4		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
11	9501050108	Providing and laying M-200 and finshing	95.00	Cubmi	53	5074.4	268947	0	268947.44		Mr.

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		smooth curing etc complete incl.the cost of form work but excluding the cost of reinforcement for R.C.C. work in beam having cross sectional area more than 0.12 sqm & up to 0.18sqm. up to floor two level.		c Meter		8	.44				NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
12	9501050107	Providing and laying M-200 and finshing smooth curing etc complete incl.the cost of form work but excluding the cost of reinforcement for R.C.C. work in beam having cross sectional area more than 0.08 sqm & up to 0.12sqm. up to floor two level.	95.00	Cubmic Meter	7	5619.48	39336.36	0	39336.36		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
13	9501050106	Providing and laying M-200 and finshing smooth curing etc complete incl.the cost of form work but excluding the cost of reinforcement for R.C.C. work in beam having cross sectional area more than 0.05 sqm & up to 0.08sqm. up to floor two level.	95.00	Cubmic Meter	1.5	6084.48	9126.72	0	9126.72		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
14	9501050061	Providing and laying ordinary cement concrete 1:2:4 (1cement : 2coarse sand : 4 graded stone aggregate 20 mm. nominal size) and finishing smooth with during etc. complete including the cost of work but excluding the cost of reinforcement for R.C.C. work in :(a) BEAMS :(1) Having cross sectional area 0.05 to 0.08 Sq.M.	95.00	Cubmic Meter	17	5704	96968	0	96968		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
15	9501050121	Providing and laying M-200 and finshing smooth curing etc complete incl.the cost of form work but excluding the cost of reinforcement for R.C.C. work in coloumn having cross sectional area more than 0.12sqm. up to floor two level.	95.00	Cubmic Meter	43	5786.48	248818.64	0	248818.64		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
16	9501050065	Providing and laying ordinary cement	95.00	Cubmi	22	6246	137412	0	137412		Mr.

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		concrete 1:2:4 (1cement : 2coarse sand : 4 graded stone aggregate 20 mm. nominal size) and finishing smooth with during etc. complete including the cost of work but excluding the cost of reinforcement for R.C.C. work in :(b) COLUMNS : :(2) Having cross sectional area more than 0.08 Sq. M. and up to 0.12 Sq. M.		c Meter							NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
17	9501050115	Providing and laying M-200 and finshing smooth curing etc complete incl.the cost of form work but excluding the cost of reinforcement for R.C.C. for Lintel/Coping/staircase up to floor two level.	95.00	Cubmic Meter	6	6439.48	38636.88	0	38636.88		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
18	9501050115	Providing and laying M-200 and finshing smooth curing etc complete incl.the cost of form work but excluding the cost of reinforcement for R.C.C. for Lintel/Coping/staircase up to floor two level.	95.00	Cubmic Meter	7	4003.88	28027.16	0	28027.16		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
19	9501050118	Providing and laying M-200 for reinforced concrete chajjahs not exceeding 10cm thickness incl finishing the exposed surfacewith cement mortar (1:3) to give a smooth surface centering and form workbut excluding the cost of reinforcement up to floor two level	95.00	Cubmic Meter	8	5510.48	44083.84	0	44083.84		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
20	9501050034	Providing and laying controlled cement concrete M-200 and curing complete excluding the cost of form work and reinforcement for reinforced concrete work in :(a) Foundation footings, Base of columns and Mass concrete	95.00	Cubmic Meter	34	3773.28	128291.52	0	128291.52		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
21	9501050012	Providing and laying cement concrete 1:2:4	95.00	Meter	35	3392.8	118748	0	118748		Mr.

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		(1cement : 2coarse sand : 4 graded stone aggregates 20 mm. Nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in :(a) Foundation footing base of columns and mass concrete									NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
22	9501050020	Providing T M T. bar reinforcement for R.C.C. work including bending binding and placing in position complete up to floor two level.	95.00	KiloGram	34000	44.3	1506200	0	1506200		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
23	9501060029	Brick work using common Brunt clay building bricks having crushing strength not less than 35 Kg./Sqcm. In superstucture above plinth level up to two floor leveland plinth in cement mortar 1:6 (1cement : 6 fine sand) (b) Conventional	95.00	Cubmic Meter	200	3040	608000	0	608000		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
24	9501060059	(1) Half brick masonry in common brunt clay building bricks having crushing strength not less than 35 Kg./Sqcm. In cement mortar 1:4 (1cement : 4 coarse sand) in fsuperstrucure above plinth level up to two floor level.(b) Conventional	95.00	Square Meter	155	426.1	66045.5	0	66045.5		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
25	9501110019	Providing fitting & fixing fully glazed/ partly glazed double leaf anodised aluminium entrance door using extruded section fabricated by standard manufactures with framing 10.15cm x4.45cm rectangular section & door shutter made from 10.15 cm x 4.45cm aluminium bottom section top & vertical section 6.35x3.80cm size using 5.5mm thick "Triveni"or HB4 plain glass	95.00	Square Meter	10	3190	31900	0	31900		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		with glazing deep rubber gasket with locking arrangement(Godrej type) with all fixtures & fastenings of anodised section with aluminium bedding floor spring mounted door closer with all labours & materials etc. Complete as per drawing and as directed by E.I.C..(coloured powder coating to be done)									
26	9501110020	Providing fitting & fixing fully glazed/ partly glazed double leaf anodised aluminium entrance door using extruded section fabricated by standard manufactures with framing 10.15cm x4.45cm rectangular section & door shutter made from 10.15 cm x 4.45cm aluminium bottom section top & vertical section 6.35x3.80cm size using 5.5mm thick "Triveni"or HB4 plain glass with glazing deep rubber gasket with locking arrangement(Godrej type) with all fixtures & fastenings of anodised section with aluminium bedding floor spring mounted door closer with all labours & materials etc. Complete as per drawing and as directed by E.I.C..(instead of floor spring provide hydrulic door closer and coloured powder coating to be done)	95.00	Square Meter	10	2970	29700	0	29700		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
27	9501220013	Providing and fixing PVC door frame of size 48X40X1.80MM thick for PVC door with inserting country wood in hollow part with approved size of corner, necessary hole fast & grouting in wall etc. complete as directed. (Measurement will be paid for width outto out without horns and height	95.00	Square Meter	11	690	7590	0	7590		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		from floor top surface to top of frame. Item to be used for W/C and bath only.)									
28	9501220014	Providing and fixing diir shutter in single or double leaf of 20mm thick with shutter outer frame top bottom and style of size 54 X 24 X 1.80mm thick and locking rail ara of size 100 X 24 X 1.80mm thick panels are made from PVC section 200 X 20 X 1mm thick including fixing & joints with providing 3 Nos. of 100 mm long hinges on EA flap of door including fixing with frame. The material is f approved ISI brand colour & tint as per drawing & instruction of E.I.C. (To be used for bath & W/C only. Measurementshall be paid for clear size of shutter only.)	95.00	Square Meter	11	1350	14850	0	14850		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
29	9501100005	Providing and fixing 35 mm. Thick shutters for doors, windows and clearstory windows including wood frame 12x7cm size anodizes aluminum butt hinges with necessary screws.(A) Indian teak wood (II) Fully Panelled	95.00	Square Meter	5	4635	23175	0	23175		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
30	9501110005	Providing & fixing in position collapsible steel shutters with vertical channels 20 x 10 x 2 mm. Braced with flat iron diagonals 20 x 5 mm. Size with top and bottom rails of T-Iron 40 x 40 x 6 mm. With 38 mm. Dia steel pulleys, complete with bolts, nuts, locking arangements, stoppers, handles including applying a priming coat of Red lead paint	95.00	Square Meter	12	3664	43968	0	43968		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
31	9501110021	Providing and fixing aluminium anodised	95.00	Square	24	2022	48528	0	48528		Mr.

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		sliding windows having standard section using extruded section fabricated by standard. Manufacturers with 15/20 Microns silver colour anodising as per drawing windows shall be of 4 mm thick. Triveni 'HB4' smoke glass glazing rubber gasket and necessary hardware, handles cum locking arrangement etc. Complete Unit shall be fabricted from alluminium section conforming to HE9WB designated to IS?1285/1980 for its chemical and mechanical properties. Anodised shall be conforming to IS?1868/1968. All joints shall be mechanically joint having secured with specially design M.S. Zink plated heat arrangement. No welding process shall be allowed in the unit.(coloured powder coating to be done)		Meter							NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
32	9501100039	Providing & fixing M.S. grills of required pattern to wooden frames of windows etc. with M.S. flats at required spacing and frame all-round square or round bars with round headed bolts and nuts or by screws.(a) Plain grill	95.00	KiloGram	1400	63.6	89040	0	89040		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
33	9501170013	Providing 15 mm. Thick cement plaster in single coat on fair side Brick/concrete walls for interior plastering upto floor two level and finished even and smooth in :(I) Cement mortar 1:3 (1 cement : 3 sand) with a floating coat of neat cement slurry	95.00	Square Meter	1500	170	255000	0	255000		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
34	9501170025	20 mm. Thick sand faced cement plaster on walls upto height 10 meters above ground level consisting of 12 mm. Thick	95.00	Square Meter	1800	192	345600	0	345600		Mr. NARENDRAKUMAR RAMESHCHANDRA

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		backing coat of c.m. 1:3 (1 cement : 3 sand) and 8 mm. Thick finising coat of c.m. 1:1 (1 cement : 1 sand) etc. complete.									PATEL Palanpur Circle
35	9501140027	Providing and laying Kota stone slab flooring over 20 mm. (average thick base of cement mortar 1:6 (1 cement : 6 coarse sand) of L.M. 1:1.5 and laid over and jointed with grey cement slurry including rubbing and polishing complete.(A) 25 mm. Thick	95.00	Square Meter	65	610	39650	0	39650		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
36	9501140039	Providing and fixing fully vitrified flooring tiles of 8 mm thick of approved brand, colour and size laid on average 25mm. thick bed of cement mortor 1 : 6 (1 cement : 6 coarse sand) with cement slurry mixed with pigments to match the shade of the tiles between joints using ordinary cement.As/per sample approved by Engineer in charge.I) upto two floors	95.00	Square Meter	250	805	201250	0	201250		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
37	9501140029	Providing and laying Kota stone slab 25 mm. Thick in resiers of steps. Dado and pillars laid on 10 mm. Thick cement mortar 1:3 (1 cement : 3 coarse sand) and jointed with grey cement slurry including rubbing and polising etc. complete.	95.00	Square Meter	25	677	16925	0	16925		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
38	9501140047	Providing Fixing 25mm. thick POLISHED KOTAH STONE wall partitions 600mm. wide & required height & all sides polished, machine cut & of approved quality including fixing the same in wall in line & level etc., complete as directed by E.I.C.	95.00	Square Meter	53	610	32330	0	32330		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
39	9501140044	Providing & laying Granite flooring of	95.00	Square	25	2672	66800	0	66800		Mr.

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		approved quality in floor & dedo in (1:2) lime mortar bedding & setting the stone in cement slurry filling the joints with cement, curing, machine polishing etc., complete as directed by E.I.C. Rate is inclusiveof cement cost for fixing of stone.		Meter							NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
40	9501220046	Labour charges for making moulding edge to Granite , incl. all tools tackels,materials & labour etc. complete as directed.	95.00	Running Meter	115	85	9775	0	9775		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
41	9501220062	Labour charges for making moulding edge to kota stone , incl. all tools tackels,materials & labour etc. complete as directed.	95.00	Running Meter	75	51	3825	0	3825		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
42	9501140032	Providing and laying cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm. Nominal size) laid in one layer finished with a floating coat of neat cement.(A) 40 mm. Thick	95.00	Square Meter	35	179	6265	0	6265		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
43	9501140018	Providing and laying white glazed tiles 6 mm. Thick inflooring treads of steps and landings laid on a Bed of 12 mm. Thick cement mortar 1:3 (1 cement : 3 coarse sand) pointing in white ceand jointed with white cement slurry.	95.00	Square Meter	25	572	14300	0	14300		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
44	9501140021	Providing and laying white glazed tiles 6 mm. Thick in skirting risers of steps and dado on 10 mm. Thick cement plaster 1:3 (1 cement : 3 coarse sand) pointing in	95.00	Square Meter	110	891	98010	0	98010		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		white ceand jointed with white cement slurry.									Circle
45	9501230037	Providing and fixing wash basin with single hole for pillar tap with C.I. Or M.S. brackers painted white including cutting holes and making good the same but excluding fittings : (A) Vitreous china (i) Flat back wash basin 500mm x 400mm size in approved colour.	95.00	Each	4	914	3656	0	3656		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
46	9501230055	Providing and fixing Pillar Tap, capstan head, screw down high pressure with screws, shanks and backnuts (A) 15 mm. Dia.	95.00	Each	4	356	1424	0	1424		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
47	9501230040	Providing and fixing C.P. brass waste for wash basin or sink(B) 40mm dia	95.00	Each	4	101	404	0	404		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
48	9501230057	Providing and fixing brass screw down stop (A) 15 mm. Dia.	95.00	Each	7	239	1673	0	1673		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
49	9501230028	Providing and fixing water closet squatting pan (Indian type W.C.pan) size 580 mm. (A) Vitereous china (i) Long pattern in approved colour, with incl trap necessary C.I. piping with plug bends up to soil chamber for G.F & up to the sides of wall incl Porcelain foot rest etc complete in working condition & as directed by E.I.	95.00	Each	1	891.4	891.4	0	891.4		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		C.complete.									
50	9501230035	Providing & fixing G.I.inlet connection for flus pipe with W.C. pan	95.00	Each	1	41.3	41.3	0	41.3		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
51	9501230029	Providing and fixing wash down water closet (european type, W.C. Pan with integral 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1 (1 cement : 1fine sand) (seat and cover to be measured and paid for seperately) (A) Vitereous china pattern : in approved colour & make with connection for flushcocketc complete incl C.I. pipe connection up to man hole chamber for G.F & up to outside wall for other floors with bends etc complete.	95.00	Each	3	2348	7044	0	7044		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
52	9501230087	P / F jet spray for European w / c pan etc. complete.	95.00	Number	3	361	1083	0	1083		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
53	9501230045	Providing and fixing 600 mm. X 450 mm. Bevelled edge mirror of superior glass mounted on 6 mm. Thick A.C, sheet or plywood sheet and fixed to wooden plugs with C.P. brass screws and washers	95.00	Each	4	580	2320	0	2320		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
54	9501230069	Providing and fixing urinal approved quality connecting the urinal with integral longitudinal flush pipe (A) Squating plate pattern white earthern ware 550 mm. X 300	95.00	Each	2	2280	4560	0	4560		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		mm incl waste coupling bends & necessary outlets of 25mm dia G.I. pipe connection etc complete.									Circle
55	9501230069	Providing and fixing urinal approved quality connecting the urinal with integral longitudinal flush pipe (A) Squating plate pattern white earthern ware 550 mm. X 300 mm incl waste coupling bends & necessary outlets of 25mm dia G.I. pipe connection etc complete.	95.00	Each	1	976	976	0	976		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
56	9501280007	Providing and laying marble stone wall partition 600 mm wide & of required height incl. Fixing the same in wall in line & level etc.complete. (B) Marble slab 20 mm. thick	95.00	Square Meter	3	1337	4011	0	4011		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
57	9501230027	Providing and fixing cast iron (spun) Nahni trap of the following nominal diaM of seld cleaning design with C.I.screwed down or highd gratting including cost of cutting and making good the walls and floors 100 mm. Inlet and 50 mm. Outlet.	95.00	Each	11	439	4829	0	4829		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
58	9501240013	Providing and fixing S.W. Gully trap with C.I. Grating brick masonary chamber and water tight C.I. Cover with frame of 300 mm. X 300 size (inside) with standard weight (I) Square mouth trap (A) 100 mm. X 100 mm. Size p -- type	95.00	Each	8	1274	10192	0	10192		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
59	9501230066	Providing and fixing chromium plated brass half turn flush cock of approved quality including fixing in pipe line etc. complete. (II) 25 mm. Dia.	95.00	Each	1	308	308	0	308		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
60	9501230019	Providing and fixing to wall, ceiling and floor 6 Kg f/cm2 working pressure polythelene pipes of the following outside dia. Low density, complete with special flange compression type fittings wall clamps etc. including making good the wall, ceiling andfloor.(A) 75 mm. 10 Kg/cm2	95.00	Meter	24	251.4	6033.6	0	6033.6		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
61	9501230020	Providing and fixing to wall, ceiling and floor 6 Kg f/cm2 working pressure polythelene pipes of the following outside dia. Low density, complete with special flange compression type fittings wall clamps etc. including making good the wall, ceiling andfloor.(A) 110 mm. 10 Kg/cm2	95.00	Meter	25	319.42	7985.5	0	7985.5		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
62	9501240035	Constructing brick masonary road gully chamber 500 mm. X 450 mm x 600 mm. Including 500 mm x 450 mm. C.I. Horizontal grating with frame complete.	95.00	Each	5	2484	12420	0	12420		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
63	9501240038	Constructing brick masonary chamber for under ground C.I. Inspection chamber and bends with bricks having crushing strength not less than 35 Kg/cm2 in cm. 1:5 C.I. Cover with frame (light duty) 455 mm. X 610 mm. Internal dimensions, total weight of cover with frame to be not less than 38 Kgs. weight of cover 23 Kg. and wt. of frame 15 Kg) R.C.C. tiop slab with 1:2:4 mix(1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm. size) foundation concrete 1:5:10 inside plaster 15 mm. thickwith cementmortar 1:3 finished smooth with a floating coat of neat cement on walls	95.00	Each	3	2935	8805	0	8805		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		& abed concrete etc. complete. (I) inside dimensions, 455 mm. 610 mm. And 450 mm. Deep for single pipe line									
64	9501240001	Providing and laying (Two level or slopes) and jointing with stiff mixture or cement mortar in proportion 1:1, salt glazed stone ware pipes 100 mm dia. nominal intrnal diaM including testing of pipes and joints etc. complete.	95.00	Meter	40	136	5440	0	5440		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
65	9501240002	Providing and laying (Two level or slopes) and jointing with stiff mixture or cement mortar in proportion 1:1, salt glazed stone ware pipes of 150 mm dia. nominal intrnal diaM including testing of pipes and joints etc. complete.	95.00	Meter	30	196	5880	0	5880		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
66	9501240003	Providing and laying cement concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm. Nominal size) bending for stone- ware pipes of 100 mm dia.(112 mm Average bed thickness) internal diaMs with necessary form work and curring complete.	95.00	Running Meter	40	93.2	3728	0	3728		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
67	9501240004	Providing and laying cement concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm. Nominal size) bending for stone- ware pipes of 150 mm dia.(116 mm Average bed thickness) internal diaMs with necessary form work and curring complete.	95.00	Running Meter	30	156	4680	0	4680		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
68	9501230089	Providing and fixing to wall, ceiling and floor "U" PVC pipeof 15mm dia completewith special "U" PVC fitting wall	95.00	Running Meter	50	84.9	4245	0	4245		Mr. NARENDRAKUMAR RAMESHCHANDRA

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		clips etcincl making good the wall ceiling and floor. including making good the wall, ceiling and floor.									PATEL Palanpur Circle
69	9501230090	Providing and fixing to wall, ceiling and floor "U" PVC pipeof 20mm dia completewith special "U" PVC fitting wall clips etcincl making good the wall ceiling and floor. including making good the wall, ceiling and floor.	95.00	Running Meter	100	107	10700	0	10700		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
70	9501230091	Providing and fixing to wall, ceiling and floor "U" PVC pipeof 25mm dia completewith special "U" PVC fitting wall clips etcincl making good the wall ceiling and floor. including making good the wall, ceiling and floor.	95.00	Running Meter	25	139	3475	0	3475		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
71	9501230060	Providing and fixing gun metal check or nonreturn fullway wheel valve(A) 15 mm. Dia.	95.00	Number	2	197	394	0	394		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
72	9501230061	Providing and fixing gun metal check or nonreturn fullway wheel valve(B) 20 mm. Dia.	95.00	Number	2	485	970	0	970		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
73	9501230062	Providing and fixing gun metal check or nonreturn fullway wheel valve(C) 25 mm. Dia.	95.00	Number	3	368	1104	0	1104		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
74	9501230017	Providing and fixing to wall, ceiling and floor 6 Kg f/cm2 working pressure	95.00	Meter	10	105.21	1052.1	0	1052.1		Mr. NARENDRAKUMAR

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		polythelene pipes of the following outside dia. Low density, complete with special flange compression type fittings wall clamps etc. including making good the wall, ceiling andfloor.(A) 40 mm. 10 Kg/cm2									RAMESHCHANDRA PATEL Palanpur Circle
75	9501230018	Providing and fixing to wall, ceiling and floor 6 Kg f/cm2 working pressure polythelene pipes of the following outside dia. Low density, complete with special flange compression type fittings wall clamps etc. including making good the wall, ceiling andfloor.(A) 50 mm. 10 Kg/cm2	95.00	Meter	20	150.4	3008	0	3008		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
76	9501230051	Providing and fixing screw down bib taps of following size :(B) Brass chromium plated screw down bib tap.15 mm	95.00	Number	7	217	1519	0	1519		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
77	9501240046	Providing & Fixing FINOLEX brand or equivalent rigid P.V.C. Pipe for rain water including necessary fittings like bend shoe, cowl etc., & fixing the pipes to the wall in plumb by means of G.I. Clamps of 18 gauge sheet with 1 to 1.5 meter distance, complete as directed by E.I.C. 90mm. dia.	95.00	Running Meter	72	319.42	22998.24	0	22998.24		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
78	9501230080	Providing & Fixing readymade P.V.C. water tight storage tank made from linear low density polyethylene & low density polyethylene LDPF product confirming to I.S: 10146?1982 with cover including providing & fixing one 20mm.dia. float valve ball?cock ,one 20mm.dia. G.I. Waste pipe with plug one 25mm.dia.G.I.Over flow	95.00	Litre	1000	4.6	4600	0	4600		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		pipe of length up to 0.30Mt. including making all connection for inlet/outlet supply with necessary fittings for outlet/ inlet etc., complete as directed by E.I.C. 1000 litre capacity									
79	9501170035	Providing cement vata (10 cm x 10 cm size) quartar round in cement mortar 1:1 including neat cement finishing watering etc. complete.	95.00	Running Meter	80	17.9	1432	0	1432		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
80	9501280009	Providing & fixing 300x300mm size marble year plate with black boarder alaround and letters incl.fixing the same in cement mortar etc complete.	95.00	Number	1	700	700	0	700		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
81	9501110015	Providing and fixing M.S.fan clamps type 1 of 16 mm. Dia. M.S. bar bent to shpe with hooked ends to R.C.C. slabs during laying painting the exposed portion of the loops all as per standard design complete.	95.00	Number	20	80.9	1618	0	1618		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
82	9501230046	Providing and fixing C.P. brass towel rail complete with C.P. Brass brackets fixed to wooden plugs with C.P. Brass screws, (B) 600mm x 20 mm size	95.00	Number	4	477	1908	0	1908		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
83	9501180033	Providing & applying 2 coats of APEX or its equivalent AACRYLIC EXTERIOR paint on exiting plastered surface or approved makes & shade including finishing & thining as per manufacturers instruction. A gap of 6 hrs. should be given between 2 subsequent coats. The work should be	95.00	Square Meter	1800	65.6	118080	0	118080		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		carried out strictly as per manufacturers specifications and requirement etc., complete as directed by E.I.C.									
84	9501180020	Distempering (two coats) with oil bound distemper of approved brand & manufacturer & of required shade on wall surfaces to give an even shade, over & including a proming coat with a distemper primer of approved brand & manufacture after throughly brushingthe surface free from mortar droping & other foreign matter & also including preparing the surface even & sand papered smooth.	95.00	Square Meter	1350	45.2	61020	0	61020		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
85	9501180039	Applying two coats of Birla Or Asian acrylic lapi (putty) & two coats of primer approved brand and manufacture on new wall surface to give an even shade including throughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth	95.00	Square Meter	1350	47.4	63990	0	63990		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
86	9501220008	Carrying out plinth treatment to post construction/existing structure by spraying chemical solution for termite control treatment including labour and material consistent with I.S.I specification.	95.00	Square Meter	340	52	17680	0	17680		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
87	9501220056	Providing and fixing steel cupboard shutter of 18 gauge with steel frame and fixing the frame with brick masonary including locking arragement with 3 coats of oil painting etc. comp.	95.00	Square Meter	53	2595	137535	0	137535		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
88	9501100047	Providing & fixing built in wall, teakwood cup?board having 75X50mm. teakwood	95.00	Square Meter	25	3300	82500	0	82500		Mr. NARENDRAKUMAR

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		frame &19mm. thick block board shutter frame with 1mm thick laminated sheet on front side with T/W beading of 20x10mm size surrounding & front moulding of 40x15mm withfixtures and fastening& with 150mm. long. 3Nos of hinges on each flap of shutter etc., and 3 coats of oil paint etc., complete as per drawings etc., complete as directed by E.I.C.									RAMESHCHANDRA PATEL Palanpur Circle
89	9501240045	(B) Providing sock pit of 5.0 Cu.Mt volume including excavating and filling brick bats with dry masonary work at top for 45 cm. Height including covering the top with stone including providing vatas in cm 1:3 with finishing curing etc. complete as directed	95.00	Number	2	29955	59910	0	59910		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
90	9501050140	Providing & laying C.C.(1:2:4) / M-15 or C.C. (1:1.5:3) / M-20 for plain or R.C.C. work for structure foundation Road pavement using 12 mm to 20 mm size black trap machine crushed metal including necessary centring for all sides as required, mixing the concrete in mixer machine, ramming with vibrator, including keeping pockets for foundation bolts & finishing the exposed honey combed surface if any, curing, etc., complete as per drawing & specification, and as directed by E.I.C. Rate is inclusive of cement cost. (GROUTING OF THE POCKET TO BE DONE SEPERATELY AS DIRECTED BY ENGINEER-IN- CHARGE) (FINISHING BY PLASTER & REINFORCEMENT IF ANY WILL BE PAID SEPARATELY)	95.00	Cubmic Meter	120	3345	401400	0	401400		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
91	9501280006	Carring out cement concrete work for road pavement by trimix (vacume dewatering service) process by using vacume dewatering equipment / pump & floater disc surface vibrator etc incl. proper vibration / compaction & anti skid surface finish of concrete pavement incl. Making groove in it incl. all tools,tackels,materials, labour etc. complete as directed.	95.00	Square Meter	1200	49.4	59280	0	59280		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
92	9501220041	Providing & fixing china mosaic tiles flooring as water proofing treatment including (a) Applying cement slurry of cement admixed with water proofing compound after cleaning the surface properly. (b) Cracks in slab shall be open in ' V ' groove & all loose materials shall be removed & crack filling shall be done with special & approved type of expanding crack fillet material . (c) Depressions in slab if any be filled up with C.C.(1:2:4) I.P.S.flooring. (d) P / L 20 mm thick plaster layer in C.M. (1:4) with cement admixed with water proofing compound including rounding of junction of walls and slab by making cement vata. (e) Finishing the surface with china mosaic tiles (pieces) flooring incl.fixing the same in cement mortar (1:2) setting with ready made tile adhesive as recommended by manufacturer?s including fillings of joints mixed with pigmented white cement slurry of matching shade & finally finishing the surface with trowel with white cement slurry	95.00	Square Meter	380	471	178980	0	178980		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		etc., complete (f) After finishing, the whole terrace shall be flooded with water to check the performence of work.									
93	9501190002	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint, brushing interior to give an even shade including cleaning the surface of all dirt, dust and othr foreign matter.	95.00	Square Meter	130	76.7	9971	0	9971		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
94	9501220061	P & F submersible pump having 2.0 HP motor of ISI brand with all G.I.fittings for inlet & outlet connection etc complete as directed.	95.00	Number	1	8000	8000	0	8000		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
95	9501140045	P/L interlocking paver blocks of high density of 60mm thick M-35 grade grey/colour as per instruction for footpath etc as directed.Rate inclusive of excavation with compaction up to 30 cm and removal and carting of the samewith 25mm to 40mm sand beeding.The work of the paving blocks shall be executed in line & level. It should be laid in such a way so that cutting of paver block to be required.Paver block shall be completed and shall be relaid if necessary.	95.00	Square Meter	280	603	168840	0	168840		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
96	9501140046	Providing/Supplying & Fixing exposed finish precast C.C. Block (M-15) for walk way and parking edge having size of 75x150x250mm depth and as per design, carting it to site, jointing into CM(1:3) & racking out the joints including with necessary excavation of asphalt/ soil or	95.00	Running Meter	350	135	47250	0	47250		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		any type of materials, disposing of the unservicable materialwithin 5.0Km lead and Providing & laying 150mm thick bedding concrete in C.C. 1:3:6 etc complete as directed.									
97	9501220047	P/F Plaster of paris Decorative false ceilling in patten as selected & approved by E.I.C. with required seleton of G.I. Frame nuts bolts screws tie bar /suspenders etc in line level incl cost of all materials & labours incl inserting electr	95.00	Square Meter	16	511	8176	0	8176		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
98	9501220048	PROVIDING OF PLASTER OF PARIS DECORATIVE boarder/ cornice IN TWO DIFFERNT SETS & SELECTED MOULDINGS OF VERTICAL HEIGHT OF 6" INCL MAKING ITS DECORATIVE/finishing offests etc completed as directed by E.I.C.	95.00	Running Meter	30	80	2400	0	2400		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
99	9501240028	(I) Extra rate for constructing B.B. Masonry for every additional epth of 0.1 M.or part thereof over item 0024 for depth from 0.9 M. to 1.5 M.	95.00	Number	5	209	1045	0	1045		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
100	9501240028	(I) Extra rate for constructing B.B. Masonry for every additional epth of 0.1 M.or part thereof over item 0024 for depth from 0.9 M. to 1.5 M.	95.00	Number	3	228	684	0	684		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
101	9501150001	Providing corrugated G.I. Sheets roofing fixed with Galvanied iron 'J' or 'L' hooks bolts and nuts 8 m. diameter with bitumen and G.I.Limpet washers filled with white	95.00	Square Meter	40	600	24000	0	24000		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		lead complete excluding the cost of purlins, rafters and trusses. (I) 0.80 mm. Thick sheet									Circle
102	9501300001	Providing & fixing concaled point wiring with single PVC insulated flexible wire 2.5Sqmm for phase & neutral and 1.0sqmm for off wire 1100 volt grade copper stranded, (FR grade) ISI mark of approved quality; using 1.5 mm thick 1" dia sized ISI mark PVC pipe with shock proof ISI mark standard brand switch.The length of point wiring upto 5mtr in pair)Notes : Rates applicable per POINT i.e NOs.	95.00	Number	60	317	19020	0	19020		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
103	9501300035	Providing & fixing concaled point wiring with single PVC insulated flexible wire 1100 volt grade copper stranded, (FR grade) ISI mark of approved quality; using 1.5 mm thick 1" dia sized ISI mark PVC pipe with shock proof ISI mark standard brand switch.The length of point wiring upto 10mtrs in pair	95.00	Number	20	520	10400	0	10400		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
104	9501300036	Providing & fixing concaled point wiring with single PVC insulated flexible wire 1100 volt grade copper stranded, (FR grade) ISI mark of approved quality; using 1.5 mm thick 1" dia sized ISI mark PVC pipe with shock proof ISI mark standard brand switch.The length of point wiring upto 20mtrs in pair	95.00	Number	5	820	4100	0	4100		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
105	9501300002	Providing & fixing Two in One (2+3 Pin Plug Socket) 5Amp. 250 Volt ISI mark plug socket with switch on same switchboard	95.00	Number	60	123	7380	0	7380		Mr. NARENDRAKUMAR RAMESHCHANDRA

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		provided for item no.1 including necessary wiring & adequate earthing wire as per specification & instructions of E.I. C. Laying of Phase wire, (2+3 plug socket) 2-in-1 plug socket on the board, with the switch)									PATEL Palanpur Circle
106	9501300003	Providing & fixing 15Amp. 250 Volt ISI mark plug socket with switch on same switchboard provided for item no.1 including necessary wiring & adequate earthing wire as per specification & instructions of E.I.C. Laying of Phase wire, (2+3 Plug socket, 2-in-1 plug socket on the board, with the switch)	95.00	Number	40	364	14560	0	14560		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
107	9501300004	Providing & fixing concealed wiring for WAN line (internal) with 6 CAT ISI Computer cable with separate 1.5 mm thick 1/2" dia. PVC pipe including relevent materials as per drawing & specification & direction with I/O Socket with box RJ-45 & labour,wire & Pipe (Aprox length 8-10mtr) as per instruction of E.I.C etc. Note: Rates are applicable per POINT.	95.00	Number	20	1374	27480	0	27480		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
108	9501300038	Providing & fixing concealed wiring for WAN line (internal) with 4 pair ISI Computer cable CAT-6 grade with separate 1.5 mm 1/2" thick PVC pipe including relevant materials as per drawing & specification & direction with I/O Socket with box RJ-45 & labour, wire & Pipe. Length of service upto 10 to 20mts	95.00	Number	5	2329	11645	0	11645		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
109	9501230030	Providing and fixing 100 mm. Size 'P' or 'S' trap for water closet squatting pan including	95.00	Number	15	224	3360	0	3360		Mr. NARENDRAKUMAR

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		jointing the trap with the pan and soil pipe in cement mortar 1:1 (1 cement : 1fine sand) (A) Vitreous china									RAMESHCHANDRA PATEL Palanpur Circle
110	9501300039	Providing & fixing concealed wiring forTelephone line withTele cable with separate PVC pipe fitting including relevent materials as per drawing & specification & direction of EIC.Note : providing socket in the switch board. The length of the wire up to 10 to 20 mtrRates are applicable per POINT.	95.00	Number	5	368	1840	0	1840		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
111	9501300040	Providing & fixing concealed wiring forTelephone line withTele cable with separate PVC pipe fitting including relevent materials as per drawing & specification & direction of EIC.Note : providing socket in the switch board. The length of the wire up to 20 to 30 mtr and above.Rates are applicable per POINT.	95.00	Number	5	523	2615	0	2615		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
112	9501300007	Providing & laying External wiring (concealed 1 ph wiring Upto 2 KW Loading) from main switch /intermediate joint (wire) to Room by using standard PVC pipe with separate ,mains/neutral complete as directed by E.I.C. The cable should be of 2.5 sqmm standared copper with earth wire total 3 wires FR grade.	95.00	Meter	200	101	20200	0	20200		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
113	9501300009	Labour charges for fixing of Fans & fixtures (Ceiling & wall Mounted)	95.00	Number	20	30	600	0	600		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
114	9501300047	providing and fixing A/C wiring with 4.0sqmm wire with 2.5sqmm earth wire and electronic starter with O/L tripping facility. Length of wire up to 10mtrs	95.00	Number	2	2750	5500	0	5500		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
115	9501300008	Providing & Fixing of Fixtures for CFL/ Tubelight fixtures in POP as per instructiopn of the E-I-C.	95.00	Number	12	265	3180	0	3180		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
116	9501300011	Providing & Fixing of CFL fixtures in cone shape without CFL and cover glass : 35W/23/20/15W in POp with connection,	95.00	Number	20	265	5300	0	5300		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
117	9501300016	Providing & fixing 4 feetT-5 type complete tubelight (28 watts)	95.00	Number	25	443	11075	0	11075		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
118	9501300017	Providing & fixing hum free step dimmer for Fan.	95.00	Number	20	235	4700	0	4700		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
119	9501300031	Providing & fixing one door bell with plate as per instruction of E.I.C.	95.00	Number	4	189	756	0	756		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
120	9501300013	Providing of earthing with 1.3 mtr 3" dia CI pipe with Collars/ connection arrangement	95.00	Number	1	2200	2200	0	2200		Mr. NARENDRAKUMAR

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		for making rigid connection to external G.I. Flats. The Flat will be supplied by the company. The earthing will be done in a pit of 4.5 ft and making layers of charcoal, salt and sand till the ground level filling. Approximate 50 kg of charcoal and 50kg of salt will be utilised.									RAMESHCHANDRA PATEL Palanpur Circle
121	9501300028	Providing & fixing 3/4 pole MCB Box with 1 nos 3 phase MCB 63 AMP as per instruction of E.I.C	95.00	Number	1	2085	2085	0	2085		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
122	9501300029	Providing & fixing 3/4 pole MCB Box with 1 nos 3 phase MCB 100 AMP as per instruction of E.I.C	95.00	Number	1	2815	2815	0	2815		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
123	9501300030	Providing & fixing 3/4 pole MCB Box with 1 nos 3 phase MCB 200 AMP as per instruction of E.I.C	95.00	Number	1	4750	4750	0	4750		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
124	9501300015	Providing of ceiling fans : energy efficient 3 star and above of any standard ISI Mark like Crompton/ Philips/ Bajaj/Orient/Polar etc	95.00	Number	20	1550	31000	0	31000		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
125	9501300018	Supply laying & fixing of 16mm2 4-core Alluminium armoured cable ISI mark as per specification.	95.00	Meter	25	210	5250	0	5250		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
126	9501300023	Providing & fixing 63A TPN MCB Hagger Make	95.00	Number	2	1300	2600	0	2600		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
127	9501300024	Providing & fixing 32A DP MCB Hagger Make	95.00	Number	12	450	5400	0	5400		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
128	9501300025	Providing & fixing 20 SP MCB Hagger Make	95.00	Number	6	200	1200	0	1200		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
129	9501300026	Providing & fixing 16 SP MCB Hagger Make	95.00	Number	6	200	1200	0	1200		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
130	9501300027	Providing & fixing 10 SP MCB Hagger Make	95.00	Number	6	200	1200	0	1200		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
131	9501300046	Providing & fixing 1 pole MCB hagger / l&T/Siemens 16/32 Amp as per requirement.as per the instructions of the E-I- C	95.00	Number	1	185	185	0	185		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
132	9501300071	Supply and fixing of 100 A LT busbar with metal box	95.00	Number	1	3623	3623	0	3623		Mr. NARENDRAKUMAR

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
											RAMESHCHANDRA PATEL Palanpur Circle
133	9501300073	Cat-6	95.00	Running Meter	20	54.05	1081	0	1081		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
134	9501100082	Providing & fixing approved quality vertical strip venation blind curtain incl powder coated runner channel etc.	95.00	Square Meter	50	495	24750	0	24750		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
135	9501110022	Providing & Fixing hinged type square. M.S. Pipe gate as per drawing & design incl.erection of gate with necessary hinges supported to vertical girders, locking arrangement by providing & fixing aldrop on both sides, with 3 coats of oil painting of approved shade & make with one coat of red oxide primer etc., complete as directed by E.I.C. (COST DOES NOT INCLUDE THE COST OF COLUMNS, STEEL/JOISTS, CONCRETE, MASONRY ETC.)	95.00	Square Meter	14	1995	27930	0	27930		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
136	9501240020	Providing and laying (two level or slopes) and jointing reinforced concrete light duty, nonpressure pipes I.S> class NP/2 of the 600 MM diameter with collars and butt ends prepared for collar joints including testing of units complete.	95.00	Meter	16	1000	16000	0	16000		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
137	9501260027	Supplying of graded stone aggregate for	95.00	Cubmi	150	468.51	70276.	0	70276.5		Mr.

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		WBM (1) 63mm to 40mm.		c Meter			5				NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
138	9501260028	Spreading of stone aggregates for soiling and WBM including filling and the interstics forming the surface to required camber and gradient for 63 to 40mm.	95.00	Cubmic Meter	150	157	23550	0	23550		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
139	9501260026	Supplying of Murrum/ binding material.	95.00	Cubmic Meter	60	269.57	16174.2	0	16174.2		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
140	9501260030	Spreading blindage or road crust filling the gaps in metal and levelling to camber and gradient as directed.(I) Murrum	95.00	Cubmic Meter	60	92.7	5562	0	5562		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
141	9501260006	Rolling of Earth work in layers with power roller including filling in depressions which occur during the process.	95.00	Cubmic Meter	1200	16.9	20280	0	20280		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
142	9501170051	Providing & applying Dr.fixit(pidilite)LW+ OR equivalent, In RCC Work using 200ml per bag as directed & instructed by E.I.C	95.00	Litre	100	78	7800	0	7800		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
143	9501230085	Providing & fixing stainless steel sink with drain board of approved make & size of 1'-6" *1'-5" * 0'-7" incl. Waste couplin &	95.00	Number	1	1575	1575	0	1575		Mr. NARENDRAKUMAR RAMESHCHANDRA

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		waste pipe for water stand as directed.									PATEL Palanpur Circle
144	9501110001	Steel work reverted in built up sections,framed work including cutting, histing, fixing in position and applying a priming coat of red lead paint :-(A) In beams and joints channels angles, tees, flats with connecting cleats as in main and cross beems, hip and jack reffers, purlins connected to common raffers and the like.	95.00	Quintal	12	6011	72132	0	72132		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
145	9501300010	Making arrangement for fan hook in celling & providing Anchor pass Hook as per theinstruction of E-I-C.	95.00	Number	22	112	2464	0	2464		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
146	9501050115	Providing and laying M-200 and finshing smooth curing etc complete incl.the cost of form work but excluding the cost of reinforcement for R.C.C. for Lintel/Coping/staircase up to floor two level.	95.00	Cubmic Meter	12	3623.4	43480.8	0	43480.8		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
147	9501110026	Providing and fixing window having extruded alluminum colour powder coated section frame main outer size 63.5x38.10x1.95mm (of Jindal Section no4605,@ wt 1.094 Kg/Rmt), horizantal two track member size 61.85mmx31.75mmx1.20mm (of Jindal section no 8687 @ wt of 0.695kg/Rmt), vertical memberof size 61.85mmx31.75mmx1.30mm (of jindal section no 8758 @ wt of 0.0659kg/mt) with sliding shutter of horizantal member size	95.00	Square Meter	18	1880	33840	0	33840		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		40mmx18mmx1.29mm (of jindal section no 8949 @ wt of 0.456kg/Rmt), vertical member of size40mmx18mmx1.29mm (of jindal section of 8947 @ wt of 0.456kg/mt, section 8948 @ wt of 0.457kg/mt) with 5mm thick transparent bronze colour tinted float glass with powder coated alluminum fittings and fixtures and transparent silicon sealant glass fixing to frame as per details etc complete.									
148	9501110026	Providing and fixing window having extruded alluminum colour powder coated section frame main outer size 63.5x38.10x1.95mm (of Jindal Section no4605,@ wt 1.094 Kg/Rmt), horizantal two track member size 61.85mmx31.75mmx1.20mm (of Jindal section no 8687 @ wt of 0.695kg/Rmt), vertical memberof size 61.85mmx31.75mmx1.30mm (of jindal section no 8758 @ wt of 0.0659kg/mt) with sliding shutter of horizantal member size 40mmx18mmx1.29mm (of jindal section no 8949 @ wt of 0.456kg/Rmt), vertical member of size40mmx18mmx1.29mm (of jindal section of 8947 @ wt of 0.456kg/mt, section 8948 @ wt of 0.457kg/mt) with 5mm thick transparent bronze colour tinted float glass with powder coated alluminum fittings and fixtures and transparent silicon sealant glass fixing to frame as per details etc complete.	95.00	Square Meter	5	1386	6930	0	6930		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
149	9501300078	Providing & Fixing heavy duty electric	95.00	Numbe	4	2000	8000	0	8000		Mr.

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		exhaust Fan of sweep size of 300mm of ISI approvedmake as directed.		r							NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
150	9501200054	PROVIDING AND FIXING IN POSITION 72 +-3 SPIRAL TURNS IN EACH 9 MTR OF RECOMMENDED STRETCHED (LAID) LENGTH & 750 MM EFFCTIVE DIA (AFTER LAYING) HOT DEEP GALVANIZED CROSS SPIRE TYPE RAZOR TAPE CONCERTINA COIL WIRE USING A CENTRAL CORE WIRE HIGH CARBON SPRING STEEL (HIGH TENSILE WIRE) MADE UP OF 2.6 MM DIA AS PER IS: 4454, PART-1, GRADE-II HAVING MINIMUM GALVANIZING OF 230 - 250 GMS PER mm2. AROUND WHICH A TAPE OF RAZOR SHARP BARBS STRIP OF 0.5 MM THICK & 19 MM WIDTH CONFORMING TO IS: 513 DD QUALITY HAVING MINIMUM GALVANIZING COATING OF 12 MICRONS WITH SERIES OF BARBS PUNCHED ALONG THE LENGTH AT REGULAR INTERVAL.(APPROXIMATELY 160 BARBS PER RUNNING METER OF CONCERTINA COIL IS MACHINE CRIMPED WITH 4 TO 5 NO OF CLIPS PER EACH SPIRE MADE UP OF STEEL(SS304). INCLUDING FIXING OF CONCERTINA COIL ON 4 RUNS OF SUPPORT FIXED THROUGH OUT THE COMPOUND WALL WITH THE HELP OF	95.00	Running Meter	210	375	78750	0	78750		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		REQUIRED GI U-NAILS / SPLIT PIN, SCAFFOLDING ETC; COMPLETED AS PER DETAILD SPECIFICATION & AS DIRECTED BY ENGINEER IN CHARGE. 4 NOS OF RUNS OF SUPPORT OF RBT WILL BE PAID IN SEPRATE ITEM.									
151	9501200055	PROVIDING AND FIXING IN POSITION SUPPORT OF RBT (RAZOR BARBED TAPE) MADE OF 2.6 MM DIA AS PER IS: 4454, PART-1, GRADE-II HAVING MINIMUM GALVANIZING OF 230-250 GMS PER SQMM. FIXED ON ANGLE SUPPORT OF COMPOUND WALL WITH THE HELP OF GI U-NAILS / SPLIT PIN INCLUDING SCAFFOLDING ETC; COMPLETE AS DIRECTED BY ENGINEER IN CHARGE.	95.00	Running Meter	840	24	20160	0	20160		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
152	9501230076	Providing and fixing C.I. Manhole cover 0.60m x 0.45m size having weight not less than 35 kgs.	95.00	Number	4	1102	4408	0	4408		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
153	9500000008	Welfare Cess @ 1% of Estimated Cost	99.00	Each	1	85747.72	85747.72	0	85747.72		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
154	9500000010	GST@18%	99.00	Each	1	1543458.93	1543458.93	0	1543458.93		Mr. DINESHBHAI AMBALAL GURJAR UGVCL Head Office
Total					**55188.5**		**10203978.49**	**0**	**10203978.49**		

Amount in Words:- ONE CRORE TWO LAKH THREE THOUSAND NINE HUNDRED SEVENTY EIGHT RUPEES AND FOURTY NINE PAISA
Amount with Tax in Words:- ONE CRORE TWO LAKH THREE THOUSAND NINE HUNDRED SEVENTY EIGHT RUPEES AND FOURTY NINE PAISA

Approval Sequence

Item Key : 706502-576460					
Sr No.	**From Approver**	**To Approver**	**Action**	**Comment Date**	**Approver comment**
1	PATEL, NARENDRAKUMAR:DE|Technical|Palanpur Cir	PATEL, PRAKASHKUMAR:EE|Technical|Palanpur Cir	SUBMIT	14-NOV-2018 10:17:35 AM	
2	PATEL, PRAKASHKUMAR:EE|Technical|Palanpur Cir	RESONSE BY USER	RESPONSE -- FORWARD	14-NOV-2018 11:03:36 AM	CE(Projects) GETCO has granted approval for sparing land to UGVCL for construction of Sub division office building Kanodar at 66 K/v S/s Kanodar vide Letter No CE(project)/EE(Tr-3)/3/772 dtd:24/07/2018. Accordingly this office prepared estimate for construction of S/dn office building for Kanodar sdn having estimated cost Rs 88,40,175=43 incl 1 % well fare cess . Pl Accord Administrative approval & T.S. for above said Work. At present Kanodar S/dn office is sitting in hired building(commercial shops in complex) having too much less facility, Hence proposed building is essential for Kanodar S/Dn office for good atmosphere for working staff as well as for our valuable consumer at that office. Put up for approval Pl. Recomanded for approval. Kindly send it to Shri.P.J.Trivedi sir (Addl.Chief Engg-Civil) (Emp No: 6722) for further approval.
3	PATEL, PRAKASHKUMAR:EE|Technical|Palanpur Cir	BALEVA, CHANDUBHAI:AO|Accounts|Palanpur Cir	SEND	14-NOV-2018 11:03:38 AM	
4	BALEVA, CHANDUBHAI:AO|Accounts|Palanpur Cir	RESONSE BY USER	RESPONSE -- APPROVE	14-NOV-2018 11:06:25 AM	app
5	BALEVA, CHANDUBHAI:AO|Accounts|Palanpur Cir	GADHAVI, LALSINGH:SE|Technical|Palanpur Cir	SEND	14-NOV-2018 11:06:26 AM	
6	GADHAVI, LALSINGH:SE|Technical|Palanpur Cir	RESONSE BY USER	RESPONSE -- FORWARD	14-NOV-2018 11:17:38 AM	highly recommended for approval.
7	GADHAVI, LALSINGH:SE|Technical|Palanpur Cir	TRIVEDI, PRASHANT:ACE|Technical|UGVCL HO	SEND	14-NOV-2018 11:17:39 AM	
8	TRIVEDI, PRASHANT:ACE|Technical|UGVCL HO	RESONSE BY USER	RESPONSE -- FORWARD	16-NOV-2018 11:28:26 AM	for n.a. please.
9	TRIVEDI, PRASHANT:ACE|Technical|UGVCL HO	SHAKYA, MAHESHKUMAR:EE|Technical|UGVCL HO	SEND	16-NOV-2018 11:28:28 AM	
10	SHAKYA, MAHESHKUMAR:EE|Technical|UGVCL HO	RESONSE BY USER	RESPONSE -- FORWARD	17-NOV-2018 11:20:12 AM	Pl. check & process
11	SHAKYA, MAHESHKUMAR:EE|Technical|UGVCL HO	GURJAR, DINESHBHAI:DE|Technical|UGVCL HO	SEND	17-NOV-2018 11:20:13 AM	

Item Key : 706502-576460					
Sr No.	**From Approver**	**To Approver**	**Action**	**Comment Date**	**Approver comment**
12	GURJAR, DINESHBHAI:DE|Technical|UGVCL HO	RESONSE BY USER	RESPONSE -- FORWARD	15-JAN-2019 11:56:45 AM	Palanpur circle office put up estimate for Construction of Kanodar Sub Division Office Building at 66 KV S/S Kanodar. At present Kanodar sub division office functioning in hired building. CE(Projects) GETCO has granted approval for sparing land to UGVCL for construction of Sub division office building Kanodar at 66 K/v S/s Kanodar vide Letter No CE(project)/EE(Tr-3)/3/772 dtd:24/07/2018. In this regards, it is planned to make our owned building at 66kv substation kanodar campus & looking to available enough space our previously approved drawings of Sub dn office building is considered. It}s included construction of Adm. Block with compound wall of 208 running meter.As per soil investigation report quantities worked out in the aforesaid estimate and rates taken as per R & B SOR 2015-16. The amount of this estimate submitted by palanpur circle office is Rs. 88,40,175=43 with 1 % welfare cess, after scrutiny it}s comes out to Rs.86,96,513=43 with 1 % welfare cess and Rs.102,46,387=11 with 1% welfare cess and 18% GST. The estimate is submitted for administrative approval as per DOP (CL)-work clause no.1.1 and technical sanction as per DOP (CL)-work clause no.2.1/2.2.
13	GURJAR, DINESHBHAI:DE|Technical|UGVCL HO	SHAKYA, MAHESHKUMAR:EE|Technical|UGVCL HO	SEND	15-JAN-2019 11:56:47 AM	
14	SHAKYA, MAHESHKUMAR:EE|Technical|UGVCL HO	RESONSE BY USER	RESPONSE -- FORWARD	17-JAN-2019 01:37:42 PM	S.E. Palanpur circle office, submitted estimate for Construction of Kanodar Sub Division Office Building on land spared by CE(Projects) GETCO at 66 KV S/S Kanodar. At present Kanodar sub division office functioning in hired building. Estimate included construction of Adm. Block with compound wall of 208 running meter. In estimate quantities worked as per soil investigation report and rates taken as per R & B SOR 2015-16. The amount of this estimate submitted by palanpur circle office is Rs. 88,40,175=43 with 1 % welfare cess, after scrutiny it}s comes out to Rs. 86,60,519.56 with 1 % welfare cess and Rs. 1,02,03,978.49 with 1% welfare cess and 18% GST. The estimate is submitted for administrative approval as per

Item Key : 706502-576460					
Sr No.	**From Approver**	**To Approver**	**Action**	**Comment Date**	**Approver comment**
					DOP (CL)-work clause no.1.1 and technical sanction as per DOP (CL)-work clause no.2.1/2.2. Put up for approval pl.
15	SHAKYA, MAHESHKUMAR:EE|Technical|UGVCL HO	TRIVEDI, PRASHANT:ACE|Technical|UGVCL HO	SEND	17-JAN-2019 01:37:44 PM	
16	TRIVEDI, PRASHANT:ACE|Technical|UGVCL HO	RESONSE BY USER	RESPONSE -- FORWARD	18-JAN-2019 10:54:41 AM	Recommended as proposed for approval. It is further proposed to consider same from budgetary provision of year 2019-20. Execution of work will be done in year 2019-20.
17	TRIVEDI, PRASHANT:ACE|Technical|UGVCL HO	KOTHARI, RASHMIKANT:GM|Accounts|UGVCL HO	SEND	18-JAN-2019 10:54:42 AM	
18	KOTHARI, RASHMIKANT:GM|Accounts|UGVCL HO	DAMOR, AMRABHAI:COA|Accounts|UGVCL HO	DELEGATE	23-JAN-2019 05:44:07 PM	PL verify & process.
19	DAMOR, AMRABHAI:COA|Accounts|UGVCL HO	KOTHARI, RASHMIKANT:GM|Accounts|UGVCL HO	DELEGATE	04-FEB-2019 10:58:34 AM	As per DOP works (Committee level) 1.1 JMD/CE is competent authority to accord an administrative approval up to 5 Crore in concurrence with GM (F). Recommended for approval in e-urja subject to approval in hard copy.