




PURCHASE REQUISITION 315924


Description	Renovation of meter testing laboratory office & store building at Sabarmati campus	Requisition Type	----	Finally Approved Date	: 14-SEP-18
Requisition for Repeat PO	----	Approver Note	:	Preparer	: Mr. TAPAN KALPESHKUMAR BAROT
Tender Type	----	Current Approver	:	Final Approver	: Mr. ASHOKKUMAR KISHANLAL MANGAL
Creation Date	15-MAR-17				

Requisition Lines

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
1	9501200016	Dismantalling doors, windows, ventilators, etc. (Wood or steel shutters including chowkhars, Architraves, Holdfasts and other attachment etc. complete and stacking them within all lead and lift. 1. Not exceeding 3 Sq.M. in area	95.00	Each	22	118	2596	0	2596		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
2	9501200017	Dismantalling doors, windows, ventilators, etc. (Wood or steel shutters including chowkhars, Architraves, Holdfasts and other attachment etc. complete and stacking them within all lead and lift. 2. Exceeding 3 Sq.M. in area	95.00	Each	2	158	316	0	316		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
3	9501200007	Dismantalling tiles or stone floors laid in mortar including stacking of serviceable materials and disposal of underserviceable materials with all lead and lift.	95.00	Square Meter	53	30	1590	0	1590		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
4	9501200010	Dismantalling of sheet roofing including ridges, hips, valleys, gutters, etc. stacking of serviceable materials with all lead and lift (ii) A.C. Sheet roofing	95.00	Square Meter	210	34	7140	0	7140		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
5	9501200005	Demolition of brick work and stone masonry including stacking of serviceable materials and disposal of unserviceable	95.00	Cubic Meter	71	346	24566	0	24566		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE




Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		materials with all lead and lift (ii) In cement mortar									CIRCLE
6	9501200003	Demolition including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift 1. R.C.C. work	95.00	Cubic Meter	25	665	16625	0	16625		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
7	9501200012	Dismantling cement asbestos Hard board in ceiling or partition walls, wooden trellies work including frames, stacking of the serviceable materials and disposal of unserviceable materials and disposal of unserviceable materials with all lead and lift	95.00	Square Meter	140	30	4200	0	4200		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
8	9501200013	Dismantling wood work, wrought framed and fixed in frames trusses including stacking the materials with all leads and lift.	95.00	Cubic Meter	8	1106	8848	0	8848		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
9	9501200015	dismantling steel work including dismantling a stacking materials with all lead & lift.	95.00	KiloGram	5000	2.3	11500	0	11500		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
11	9501200026	Removing existing plasterwork including scaffolding & throwing the stuff to a lead of 500 M radius etc. complete as directed by E.I.C.	95.00	Square Meter	260	12.3	3198	0	3198		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
12	9501040002	Excavation for foundation upto 1.5 M. depth including sorting out and stacking of useful materials and disposing off excavated stuff up to 50M. lead.(b) Dense or hard soil	95.00	Cubic Meter	35	85.9	3006.5	0	3006.5		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
13	9501040007	Excavation for foundation for depth from 1.5 Mt to 3 Mt. including sorting out and stacking of useful materials and disposing	95.00	Cubic Meter	11	93.2	1025.2	0	1025.2		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE




Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		off the excavated stuff up to 50 Mt. lead.(b) Dense or hard soil									CIRCLE
14	9501050004	Providing and laying C.C. 1:4:8 and curing complete excl. cost of from work in : Foundation and plinth	95.00	Cubic Meter	23	2249	51727	0	51727		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
15	9501040026	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm. In depth consolidating EA deposited layer by ramming and watering.	95.00	Cubic Meter	46	79	3634	0	3634		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
16	9501040028	Filling in foundation and plinth with murrum or selected soil in layers of 20 cm. Thickness including watering ramming and consolidating etc. comp.	95.00	Cubic Meter	35	286	10010	0	10010		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
17	9501040027	Filling in plinth with sand under floors including watering ramming, consolidating and dressing etc. comp.	95.00	Cubic Meter	60	398	23880	0	23880		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
18	9501050127	Providing and laying ordinary M-200 and curing complete excluding the cost of form work and reinforcement for reinforced concrete work in :(a) Foundation footings, Base of columns and Mass concrete(Up to two floors)	95.00	Cubic Meter	6	3707.48	22244.88	0	22244.88		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
19	9501050120	Providing and laying M-200 and finishing smooth curing etc complete incl.the cost of form work but excluding the cost of reinforcement for R.C.C. work in coloumn having cross sectional area more than 0.08 sqm & up to 0.12sqm. up to floor two level.	95.00	Cubic Meter	3.5	6740.48	23591.68	0	23591.68		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
20	9501050107	Providing and laying M-200 and finishing	95.00	Cubic	4	5733.4	22933.	0	22933.92		Mr. TAPAN




Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		smooth curing etc complete incl.the cost of form work but excluding the cost of reinforcement for R.C.C. work in beam having cross sectional area more than 0.08 sqm & up to 0.12sqm. up to floor two level.		c Meter		8	92				KALPESHKUMAR BAROT SABARMATI CIRCLE
21	9501050100	Providing and laying M-200 and finishing smooth curing etc complete incl.the cost of form work but excluding the cost of reinforcement for R.C.c. work in Slabs having more than 10cm and up to 13 cm thickness up to two floor level.	95.00	Cubic Meter	30	5265.48	157964.4	0	157964.4		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
22	9501110003	Steel work welded in built up sections,framed work including cutting, histing, fixing in position and applying a priming coat of red lead paint :(A) In beams and joints channels angles, tees, flats with connecting cleats as in main and cross beams, hip and jack reffers, purlins connected to common raffers and the like.-	95.00	Quintal	1.32	5289	6981.48	0	6981.48		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
23	9501050020	Providing T M T. bar reinforcement for R.C.C. work including bending binding and placing in position complete up to floor two level.	95.00	KiloGram	9500	44.4	421800	0	421800		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
24	9501060005	Brick work using common Brunt clay building bricks having crushing strength not less than 35 Kg./Sqcm. In foundation and plinth in cement mortar 1:6: Conventional	95.00	Cubic Meter	14	2798	39172	0	39172		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
25	9501060029	Brick work using common Brunt clay building bricks having crushing strength not less than 35 Kg./Sqcm. In superstructure above plinth level up to two floor leveland plinth in cement mortar 1:6 (1cement : 6	95.00	Cubic Meter	44	2963	130372	0	130372		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE



Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		fine sand) (b) Conventional									
26	9501060047	(1) Half brick masonry in common burnt clay building bricks having crushing strength not less than 35 Kg./Sqcm. In cement mortar 1:4 (1 cement : 4 coarse sand) in foundation and plinth.(b) Conventional	95.00	Square Meter	135	418	56430	0	56430		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
27	9501170013	Providing 15 mm. Thick cement plaster in single coat on fair side Brick/concrete walls for interior plastering upto floor two level and finished even and smooth in :(I) Cement mortar 1:3 (1 cement : 3 sand) with a floating coat of neat cement slurry	95.00	Square Meter	635	173	109855	0	109855		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
28	9501170013	Providing 15 mm. Thick cement plaster in single coat on fair side Brick/concrete walls for interior plastering upto floor two level and finished even and smooth in :(I) Cement mortar 1:3 (1 cement : 3 sand) with a floating coat of neat cement slurry	95.00	Square Meter	200	156.9	31380	0	31380		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
29	9501170025	20 mm. Thick sand faced cement plaster on walls upto height 10 meters above ground level consisting of 12 mm. Thick backing coat of c.m. 1:3 (1 cement : 3 sand) and 8 mm. Thick finishing coat of c.m. 1:1 (1 cement : 1 sand) etc. complete.	95.00	Square Meter	445	189	84105	0	84105		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
30	9501170035	Providing cement vata (10 cm x 10 cm size) quarter round in cement mortar 1:1 including neat cement finishing watering etc. complete.	95.00	Running Meter	85	17.8	1513	0	1513		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
31	9501050021	Providing throating or plaster drip and molding to R.C.C. Chhaja.	95.00	Meter	100	25	2500	0	2500		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI




Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
											CIRCLE
34	9501220015	Providing & laying 20 to 25mm thick, both faces polished kotah stone with all edges machine cut up to 450mm width and of required length (only one piece to be used) of approved quality for cupboard shelves including fixing the same in masonry wall by cement mortar in three sides including curing etc. complete as directed by E.I.C .	95.00	Square Meter	125	888	111000	0	111000		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
35	9501140044	Providing & laying Granite flooring of approved quality in floor & dedo in (1:2) lime mortar bedding & setting the stone in cement slurry filling the joints with cement, curing, machine polishing etc., complete as directed by E.I.C. Rate is inclusive of cement cost for fixing of stone.	95.00	Square Meter	13	3259	42367	0	42367		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
36	9501220046	Labour charges for making moulding edge to Granite , incl. all tools tackels,materials & labour etc. complete as directed.	95.00	Running Meter	29	126	3654	0	3654		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
38	9501220041	Providing & fixing china mosaic tiles flooring as water proofing treatment including (a) Applying cement slurry of cement admixed with water proofing compound after cleaning the surface properly. (b) Cracks in slab shall be open in ' V ' groove & all loose materials shall be removed & crack filling shall be done with special & approved type of expanding crack fillet material . (c) Depressions in slab if any be filled up with C.C.(1:2:4) I.P.S.flooring. (d) P / L 20 mm thick	95.00	Square Meter	210	479	100590	0	100590		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE



Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		plaster layer in C.M. (1:4) with cement admixed with water proofing compound including rounding of junction of walls and slab by making cement vata. (e) Finishing the surface with china mosaic tiles (pieces) flooring incl.fixing the same in cement mortar (1:2) setting with ready made tile adhesive as recommended by manufacturer?s including fillings of joints mixed with pigmented white cement slurry of matching shade & finally finishing the surface with trowel with white cement slurry etc., complete (f) After finishing, the whole terrace shall be flooded with water to check the performance of work.									
39	9501140018	Providing and laying white glazed tiles 6 mm. Thick inflooring treads of steps and landings laid on a Bed of 12 mm. Thick cement mortar 1:3 (1 cement : 3 coarse sand) pointing in white ceand jointed with white cement slurry.	95.00	Square Meter	14	692	9688	0	9688		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
40	9501140021	Providing and laying white glazed tiles 6 mm. Thick in skirting risers of steps and dado on 10 mm. Thick cement plaster 1:3 (1 cement : 3 coarse sand) pointing in white ceand jointed with white cement slurry.	95.00	Square Meter	70	906	63420	0	63420		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
41	9501110019	Providing fitting & fixing fully glazed/ partly glazed double leaf anodised aluminium entrance door using extruded section fabricated by standard manufactures with framing 10.15cm x4.45cm rectangular section & door shutter made from 10.15	95.00	Square Meter	14	3190	44660	0	44660		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE




Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		cm x 4.45cm aluminium bottom section top & vertical section 6.35x3.80cm size using 5.5mm thick "Triveni" or HB4 plain glass with glazing deep rubber gasket with locking arrangement (Godrej type) with all fixtures & fastenings of anodised section with aluminium bedding floor spring mounted door closer with all labours & materials etc. Complete as per drawing and as directed by E.I.C.. (coloured powder coating to be done)									
42	9501110005	Providing & fixing in position collapsible steel shutters with vertical channels 20 x 10 x 2 mm. Braced with flat iron diagonals 20 x 5 mm. Size with top and bottom rails of T-Iron 40 x 40 x 6 mm. With 38 mm. Dia steel pulleys, complete with bolts, nuts, locking arrangements, stoppers, handles including applying a priming coat of Red lead paint	95.00	Square Meter	12	3934	47208	0	47208		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
43	9501110021	Providing and fixing aluminium anodised sliding windows having standard section using extruded section fabricated by standard. Manufacturers with 15/20 Microns silver colour anodising as per drawing windows shall be of 4 mm thick. Triveni 'HB4' smoke glass glazing rubber gasket and necessary hardware, handles cum locking arrangement etc. Complete Unit shall be fabricated from aluminium section conforming to HE9WB designated to IS?1285/1980 for its chemical and mechanical properties. Anodised shall be	95.00	Square Meter	16	2022	32352	0	32352		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE



Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		conforming to IS?1868/1968. All joints shall be mechanically joint having secured with specially design M.S. Zink plated heat arrangement. No welding process shall be allowed in the unit.(coloured powder coating to be done)									
44	9501220060	P & F alluminium anodized glass louvers type ventilator having std.section frame incl.powder coating approved shade & make etc.complete as directed by EIC	95.00	Square Meter	9	1386	12474	0	12474		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
45	9501100039	Providing & fixing M.S. grills of required pattern to wooden frames of windows etc. with M.S. flats at required spacing and frame all-round square or round bars with round headed bolts and nuts or by screws.(a) Plain grill	95.00	KiloGram	700	63.6	44520	0	44520		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
46	9501220056	Providing and fixing steel cupboard shutter of 18 gauge with steel frame and fixing the frame with brick masonry including locking arrangement with 3 coats of oil painting etc. comp.	95.00	Square Meter	59	2595	153105	0	153105		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
47	9501230037	Providing and fixing wash basin with single hole for pillar tap with C.I. Or M.S. brackers painted white including cutting holes and making good the same but excluding fittings : (A) Vitreous china (i) Flat back wash basin 500mm x 400mm size in approved colour.	95.00	Each	3	889	2667	0	2667		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
48	9501230055	Providing and fixing Pillar Tap, capstan head, screw down high pressure with screws, shanks and backnuts (A) 15 mm. Dia.	95.00	Each	3	354	1062	0	1062		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE




Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
49	9501230040	Providing and fixing C.P. brass waste for wash basin or sink(B) 40mm dia	95.00	Each	3	94.1	282.3	0	282.3		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
50	9501230057	Providing and fixing brass screw down stop (A) 15 mm. Dia.	95.00	Each	3	237	711	0	711		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
51	9501230045	Providing and fixing 600 mm. X 450 mm. Bevelled edge mirror of superior glass mounted on 6 mm. Thick A.C, sheet or plywood sheet and fixed to wooden plugs with C.P. brass screws and washers	95.00	Each	3	580	1740	0	1740		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
52	9501230027	Providing and fixing cast iron (spun) Nahni trap of the following nominal diaM of seld cleaning design with C.I.screwed down or highd grating including cost of cutting and making good the walls and floors 100 mm. Inlet and 50 mm. Outlet.	95.00	Each	6	359	2154	0	2154		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
53	9501240014	Providing and fixing S.W. Gully trap with C.I. Grating brick masonry chamber and water tight C.I. Cover with frame of 300 mm. X 300 size (inside) with standard weight (I) Square mouth trap (A) 150 mm. X 100 mm. Size p OR R type	95.00	Each	5	1227	6135	0	6135		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
54	9501230017	Providing and fixing to wall, ceiling and floor 6 Kg f/cm2 working pressure polythelene pipes of the following outside dia. Low density, complete with special flange compression type fittings wall clamps etc. including making good the wall, ceiling and floor.(A) 40 mm. 10 Kg/cm2	95.00	Meter	25	79	1975	0	1975		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE




Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
55	9501230020	Providing and fixing to wall, ceiling and floor 6 Kg f/cm2 working pressure polythelene pipes of the following outside dia. Low density, complete with special flange compression type fittings wall clamps etc. including making good the wall, ceiling and floor.(A) 110 mm. 10 Kg/cm2	95.00	Meter	55	318	17490	0	17490		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
56	9501240051	Providing B.B. Masonry inspection chamber (MANHOLE) of approved size including light type C.I. Cover with frame, necessary excavation bottom concreting of B.B.C.C. (1:4:8) 150mm. thick/ 225mm. thick B.B. Masonry in C.M.(1:6) 12mm thick cement plaster in C.M.(1:3) inside & to all exposed faces up to 300mm. below ground level, curing etc (B.B.MASONRY UPTO 1000mm. DEPTH.) c) 600X450mm. Clear size.	95.00	Number	2	2444	4888	0	4888		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
57	9501240001	Providing and laying (Two level or slopes) and jointing with stiff mixture or cement mortar in proportion 1:1, salt glazed stone ware pipes 100 mm dia. nominal intrnal diaM including testing of pipes and joints etc. complete.	95.00	Meter	8	183	1464	0	1464		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
58	9501240003	Providing and laying cement concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm. Nominal size) bending for stone- ware pipes of 100 mm dia.(112 mm Average bed thickness) internal diaMs with necessary form work and curring complete.	95.00	Meter	8	164	1312	0	1312		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
59	9501230089	Providing and fixing to wall, ceiling and	95.00	Runnin	20	84.9	1698	0	1698		Mr. TAPAN




Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		floor "U" PVC pipe of 15mm dia completewith special "U" PVC fitting wall clips etcincl making good the wall ceiling and floor. including making good the wall, ceiling and floor.		g Meter							KALPESHKUMAR BAROT SABARMATI CIRCLE
60	9501230060	Providing and fixing gun metal check or nonreturn fullway wheel valve(A) 15 mm. Dia.	95.00	Each	2	215	430	0	430		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
61	9501230051	Providing and fixing screw down bib taps of following size :(B) Brass chromium plated screw down bib tap.15 mm	95.00	Each	5	215	1075	0	1075		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
62	9501110015	Providing and fixing M.S.fan clamps type 1 of 16 mm. Dia. M.S. bar bent to shpe with hooked ends to R.C.C. slabs during laying painting the exposed portion of the loops all as per standard design complete.	95.00	Each	30	79.2	2376	0	2376		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
63	9501220008	Carrying out plinth treatment to post construction/existing structure by spraying chemical solution for termite control treatment including labour and material consistent with I.S.I specification.	95.00	Square Meter	222	66.6	14785.2	0	14785.2		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
64	9501220057	Cleaning the existing plastering / coloured surface with zero sand paper & providing & applying putty lappy finishing in 2 times for smoothening the surface including 1 coat of cement plaster etc., complete as directed by E.I.C.	95.00	Square Meter	840	47.4	39816	0	39816		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
65	9501180020	Distempering (two coats) with oil bound distemper of approved brand & manufacturer & of required shade on wall	95.00	Square Meter	840	48.3	40572	0	40572		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE




Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		surfaces to give an even shade, over & including a priming coat with a distemper primer of approved brand & manufacture after thoroughly brushing the surface free from mortar dropping & other foreign matter & also including preparing the surface even & sand papered smooth.									CIRCLE
66	9501180033	Providing & applying 2 coats of APEX or its equivalent AACRYLIC EXTERIOR paint on existing plastered surface or approved makes & shade including finishing & thinning as per manufacturers instruction. A gap of 6 hrs. should be given between 2 subsequent coats. The work should be carried out strictly as per manufacturers specifications and requirement etc., complete as directed by E.I.C.	95.00	Square Meter	445	65.6	29192	0	29192		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
67	9501190002	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint, brushing interior to give an even shade including cleaning the surface of all dirt, dust and othr foreign matter.	95.00	Square Meter	80	77	6160	0	6160		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
68	9501300001	Providing & fixing concealed point wiring with single PVC insulated flexible wire 2.5Sqmm for phase & neutral and 1.0sqmm for off wire 1100 volt grade copper stranded, (FR grade) ISI mark of approved quality; using 1.5 mm thick 1" dia sized ISI mark PVC pipe with shock proof ISI mark standard brand switch.The length of point wiring upto 5mtr in pair)Notes : Rates applicable per POINT i.e NOs.	95.00	Number	55	317	17435	0	17435		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE



Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
69	9501300035	Providing & fixing concealed point wiring with single PVC insulated flexible wire 1100 volt grade copper stranded, (FR grade) ISI mark of approved quality; using 1.5 mm thick 1" dia sized ISI mark PVC pipe with shock proof ISI mark standard brand switch.The length of point wiring upto 10mtrs in pair	95.00	Number	20	520	10400	0	10400		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
70	9501300036	Providing & fixing concealed point wiring with single PVC insulated flexible wire 1100 volt grade copper stranded, (FR grade) ISI mark of approved quality; using 1.5 mm thick 1" dia sized ISI mark PVC pipe with shock proof ISI mark standard brand switch.The length of point wiring upto 20mtrs in pair	95.00	Number	20	820	16400	0	16400		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
71	9501300002	Providing & fixing Two in One (2+3 Pin Plug Socket) 5Amp. 250 Volt ISI mark plug socket with switch on same switchboard provided for item no.1 including necessary wiring & adequate earthing wire as per specification & instructions of E.I. C. Laying of Phase wire, (2+3 plug socket) 2-in-1 plug socket on the board, with the switch)	95.00	Number	25	123	3075	0	3075		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
72	9501300003	Providing & fixing 15Amp. 250 Volt ISI mark plug socket with switch on same switchboard provided for item no.1 including necessary wiring & adequate earthing wire as per specification & instructions of E.I.C. Laying of Phase wire, (2+3 Plug socket, 2-in-1 plug socket on the board, with the switch)	95.00	Number	10	364	3640	0	3640		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE




Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
73	9501300037	Providing & fixing concealed wiring for WAN line (internal) with 4 pair ISI Computer cable CAT-6 grade with separate 1.5 mm 1/2" thick PVC pipe including relevant materials as per drawing & specification & direction with I/O Socket with box RJ-45 & labour, wire & Pipe. Length of service upto 10mtrs	95.00	Number	10	1374	13740	0	13740		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
74	9501300038	Providing & fixing concealed wiring for WAN line (internal) with 4 pair ISI Computer cable CAT-6 grade with separate 1.5 mm 1/2" thick PVC pipe including relevant materials as per drawing & specification & direction with I/O Socket with box RJ-45 & labour, wire & Pipe. Length of service upto 10 to 20mts	95.00	Number	5	2329	11645	0	11645		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
75	9501300005	Providing & fixing concealed wiring for Telephone line with Tele cable with separate PVC pipe fitting including relevant materials as per drawing & specification & direction of EIC. Note : providing socket in the switch board. The length of the wire up to 10mtr Rates are applicable per POINT.	95.00	Number	1	224	224	0	224		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
76	9501300039	Providing & fixing concealed wiring for Telephone line with Tele cable with separate PVC pipe fitting including relevant materials as per drawing & specification & direction of EIC. Note : providing socket in the switch board. The length of the wire up to 10 to 20 mtr Rates are applicable per POINT.	95.00	Number	1	368	368	0	368		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
77	9501300007	Providing & laying External wiring	95.00	Meter	100	101	10100	0	10100		Mr. TAPAN




Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		(concealed 1 ph wiring Upto 2 KW Loading) from main switch /intermediate joint (wire) to Room by using standard PVC pipe with separate ,mains/neutral complete as directed by E.I.C. The cable should be of 2.5 sqmm standared copper with earth wire total 3 wires FR grade.									KALPESHKUMAR BAROT SABARMATI CIRCLE
78	9501300077	Providing& Fixing of CFL 35W/23W with saddle ans mounting of any standard ISI mark as per instruction of EIC.	95.00	Number	22	265	5830	0	5830		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
79	9501300016	Providing & fixing 4 feetT-5 type complete tubelight (28 watts)	95.00	Number	39	443	17277	0	17277		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
80	9501300019	Providing & laying 3 phase line with 4.0sqmm wire fourline (3 phase+ 1 neutral) & 2.5 sqmm wire for earthing in concealed wire with 1.0sqmm pipe 1.5 mm thick from busbar to Distrubution MCB Board (3 core copper stranded wire 4.00 sqmm for three different phase, 1 core 2.5 sqmm copper stranded wire seprate for neutral and 1 core 1.0 sqmm copper stranded wire for earthing)	95.00	Meter	25	205	5125	0	5125		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
81	9501300031	Providing & fixing one door bell with plate as per instruction of E.I.C.	95.00	Number	2	189	378	0	378		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
82	9501300013	Providing of earthing with 1.3 mtr 3" dia CI pipe with Collars/ connection arrangement for making rigid connection to external G.I.	95.00	Number	1	2200	2200	0	2200		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI



Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		Flats. The Flat will be supplied by the company. The earthing will be done in a pit of 4.5 ft and making layers of charcoal, salt and sand till the ground level filling. Approximate 50 kg of charcoal and 50kg of salt will be utilised.									CIRCLE
83	9501300009	Labour charges for fixing of Fans & fixtures (Ceiling & wall Mounted)	95.00	Number	30	30	900	0	900		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
84	9501300015	Providing of ceiling fans : energy efficient 3 star and above of any standard ISI Mark like Crompton/ Philips/ Bajaj/Orient/Polar etc	95.00	Number	30	1550	46500	0	46500		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
85	9501300017	Providing & fixing hum free step dimmer for Fan.	95.00	Number	30	235	7050	0	7050		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
86	9501300078	Providing & Fixing heavy duty electric exhaust Fan of sweep size of 300mm of ISI approvedmake as directed.	95.00	Number	3	2000	6000	0	6000		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
87	9501300020	Mains service with 1.1KV grade FRP PVC insulated ISI marked Stranded flexible copper conductor wire 2core 2.5 sqmm	95.00	Meter	100	45	4500	0	4500		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
88	9501300021	Mains service with 1.1KV grade FRP PVC insulated ISI marked Stranded flexible copper conductor wire 2core 4 sqmm	95.00	Meter	100	65	6500	0	6500		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
89	9501300022	Mains service with 1.1KV grade FRP PVC insulated ISI marked Stranded flexible	95.00	Meter	100	120	12000	0	12000		Mr. TAPAN KALPESHKUMAR




Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		copper conductor wire 4core 4 sqmm									BAROT SABARMATI CIRCLE
90	9501300023	Providing & fixing 63A TPN MCB Hagger Make	95.00	Number	1	1300	1300	0	1300		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
91	9501300024	Providing & fixing 32A DP MCB Hagger Make	95.00	Number	2	450	900	0	900		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
92	9501300025	Providing & fixing 20 SP MCB Hagger Make	95.00	Number	2	200	400	0	400		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
93	9501300026	Providing & fixing 16 SP MCB Hagger Make	95.00	Number	2	200	400	0	400		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
94	9501300027	Providing & fixing 10 SP MCB Hagger Make	95.00	Number	6	200	1200	0	1200		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
95	9501300076	P/L CAT-6 computer mains of finolex OR equivalent ISI make etc complete as directed.	95.00	Running Meter	50	54.05	2702.5	0	2702.5		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
96	9501300074	P/F approved make 28 - way metal MCB distribution box having double door etc complete as directed	95.00	Each	1	3200	3200	0	3200		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
97	9501140045	P/L interlocking paver blocks of high density of 60mm thick M-35 grade	95.00	Square Meter	54	607	32778	0	32778		Mr. TAPAN KALPESHKUMAR



Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		grey/colour as per instruction for footpath etc as directed.Rate inclusive of excavation with compaction up to 30 cm and removal and carting of the samewith 25mm to 40mm sand bedding.The work of the paving blocks shall be executed in line & level. It should be laid in such a way so that cutting of paver block to be required.Paver block shall be completed and shall be relaid if necessary.									BAROT SABARMATI CIRCLE
98	9501100046	Providing and fixing 35 mm. Thick shutters for doors, windows and clearstory windows including indian teak wood frame 10x7cm incl black enamelled iron oxide fixtures & fastening incl priming coat and two coats of oil paint etc complete full pannelled door.	95.00	Square Meter	4	5530	22120	0	22120		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
99	9501220062	Labour charges for making moulding edge to kota stone , incl. all tools tackels,materials & labour etc. complete as directed.	95.00	Running Meter	20	94.5	1890	0	1890		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
100	9501140019	Providing and laying Ceramic Vetrified flooring tiles in flooring treads of steps and landings laid on a Bed of 12 mm. Thick cement mortar 1:3 (1 cement : 3 coarse sand) pointing in white ceand jointed with white cement slurry.	95.00	Square Meter	50	748	37400	0	37400		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
101	9501140040	Providing and fixing fully vitrified flooring tiles of 8 mm thick of approved brand, colour and size laid on average 25mm. thick bed of cement mortar 1 : 6 (1 cement : 6 coarse sand) with cement slurry mixed with pigments to match the	95.00	Square Meter	4	780	3120	0	3120		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE




Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		shade of the shade of between joints using ordinary cement.As/per sample approved by Engineer in charge.l) upto two floors									
102	9501180013	Removing dry or oil bound distemper by a ashing and scrapping and sand papering the wall surface smooth including necessary repairs to scratches complete.	95.00	Square Meter	150	7.1	1065	0	1065		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
103	9501050093	P.L. R.C.C. coping in cement concrete 1:1.5:3 with formwork,curing etc, butexcluding cost of reinforcement etc,	95.00	Cubic Meter	1.5	4108.48	6162.72	0	6162.72		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
104	9501050118	Providing and laying M-200 for reinforced concrete chajjahs not exceeding 10cm thickness incl finishing the exposed surfacewith cement mortar (1:3) to give a smooth surface centering and form workbut excluding the cost of reinforcement up to floor two level	95.00	Cubic Meter	1.5	5745.48	8618.22	0	8618.22		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
105	9501050115	Providing and laying M-200 and finishing smooth curing etc complete incl.the cost of form work but excluding the cost of reinforcement for R.C.C. for Lintel/Coping/staircase up to floor two level.	95.00	Cubic Meter	6	5613.48	33680.88	0	33680.88		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
106	9501220069	P&F FRP frame size 125x65mm size and 35mm thick FRP shutter with wood grain raised panel design finish shutter having extra reinforcement on sides and edges and in polish finish.The core of shutter is to be filled up with injected fire extinguishing grade polyurethane foam done in situ along with embedded wooden piece for stiffening and also for taking hinges and fixtures. The	95.00	Square Meter	8	4455	35640	0	35640		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE



Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		whole FRP frame and shutter is to be waterproof, weather proof, termite proof and resistance to mild acid/Alkali. Rates are to be inclusive of SS hinges with necessary screw and brass fixtures & fastening. Product should have 3 years performance guarantee and company have ISO 9001-2000 certificate.									
107	9501220014	Providing and fixing door shutter in single or double leaf of 20mm thick with shutter outer frame top bottom and style of size 54 X 24 X 1.80mm thick and locking rail area of size 100 X 24 X 1.80mm thick panels are made from PVC section 200 X 20 X 1mm thick including fixing & joints with providing 3 Nos. of 100 mm long hinges on EA flap of door including fixing with frame. The material is ISI approved ISI brand colour & tint as per drawing & instruction of E.I.C. (To be used for bath & W/C only. Measurements shall be paid for clear size of shutter only.)	95.00	Square Meter	1	0	0	0	0		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
108	9501230029	Providing and fixing wash down water closet (European type, W.C. Pan with integral 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1 (1 cement : 1 fine sand) (seat and cover to be measured and paid for separately) (A) Vitreous china pattern : in approved colour & make with connection for flushcocketc complete incl C.I. pipe connection up to man hole chamber for G.F & up to outside wall for other floors with	95.00	Each	2	3233.5	6467	0	6467		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE



Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		bends etc complete.									
109	9501230028	Providing and fixing water closet squatting pan (Indian type W.C.pan) size 580 mm. (A) Vitereous china (i) Long pattern in approved colour, with incl trap necessary C.I. piping with plug bends up to soil chamber for G.F & up to the sides of wall incl Porcelain foot rest etc complete in working condition & as directed by E.I. C.complete.	95.00	Each	1	871.7	871.7	0	871.7		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
110	9501230083	P/F white/coloured procelain flat back wall type URINALPAN HAVING SIZE 590X375X390 of approved quality& make incl waste coupling bend & necessary ouylet of 25mm dia G.I. pipe coonection incl brass stop cock ,pillar cock P.V.C. connection,spreader,& spreader pipes, brackets etc complete as directed by E.I.C	95.00	Number	2	2280	4560	0	4560		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
111	9501230069	Providing and fixing urinal approved quality connecting the urinal with integral longitudinal flush pipe (A) Squating plate pattern white earthen ware 550 mm. X 300 mm incl waste coupling bends & necessary outlets of 25mm dia G.I. pipe connection etc complete.	95.00	Each	1	975	975	0	975		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
112	9501230091	Providing and fixing to wall, ceiling and floor "U" PVC pipeof 25mm dia completewith special "U" PVC fitting wall clips etcincl making good the wall ceiling and floor. including making good the wall, ceiling and floor.	95.00	Running Meter	40	107	4280	0	4280		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
113	9501230062	Providing and fixing gun metal check or	95.00	Each	4	483	1932	0	1932		Mr. TAPAN



Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		nonreturn fullway wheel valve(C) 25 mm. Dia.									KALPESHKUMAR BAROT SABARMATI CIRCLE
114	9501230080	Providing & Fixing readymade P.V.C. water tight storage tank made from linear low density polyethylene & low density polyethylene LDPF product confirming to I.S: 10146?1982 with cover including providing & fixing one 20mm.dia. float valve ball?cock ,one 20mm.dia. G.I. Waste pipe with plug one 25mm.dia.G.I.Over flow pipe of length up to 0.30Mt. including making all connection for inlet/outlet supply with necessary fittings for outlet/ inlet etc., complete as directed by E.I.C. 1000 litre capacity	95.00	Litre	1000	4.6	4600	0	4600		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
115	9500000008	Welfare Cess @ 1% of Estimated Cost	99.00	Each	1	27792.44	27792.44	0	27792.44		Mr. TAPAN KALPESHKUMAR BAROT SABARMATI CIRCLE
116	9501100082	Providing & fixing approved quality vertical strip venation blind curtain incl powder coated runner channel etc.	95.00	Square Meter	9	495	4455	0	4455		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
117	9501050108	Providing and laying M-200 and finshing smooth curing etc complete incl.the cost of form work but excluding the cost of reinforcement for R.C.C. work in beam having cross sectional area more than 0.12 sqm & up to 0.18sqm. up to floor two level.	95.00	Cubmic Meter	21	5196.48	109126.08	0	109126.08		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
118	9501140042	Providing & laying 20 to 25mm. thick	95.00	Square	145	769	111505	0	111505		Mr.



Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)	Tax (INR)	Amount With Tax (INR)	Need By Date	Requestor & Its Org./ Buyer
		approved ROUGH KOTAH STONE 600X450mm. or approved size in flooring including fixing the same in C.M. (1:2) setting the stones in cement slurry & filling the joints with C.M. (1:1) by using water proofing compound, finishing surface, curing by filling ponds of water etc., complete as directed by E.I.C., Rate is inclusive of cement cost. (NOTE: THE CONTRACTOR SHALL HAVE TO GIVE THE TEST OF WATER PROOFNESS OF TERRACE FLOOR BY FILLING MINIMUM 150mm. DEEP WATER POOL FOR ATLEAST 3 DAYS TO CHECK UP ANY LEAKAGE.)		Meter							NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
119	9501140029	Providing and laying Kota stone slab 25 mm. Thick in resiers of steps. Dado and pillars laid on 10 mm. Thick cement mortar 1:3 (1 cement : 3 coarse sand) and jointed with grey cement slurry including rubbing and polising etc. complete.	95.00	Square Meter	10	888	8880	0	8880		Mr. NARENDRAKUMAR RAMESHCHANDRA PATEL Palanpur Circle
Total					23411.82		2807036.1	0	2807036.1		

Amount in Words:- TWENTY EIGHT LAKH SEVEN THOUSAND THIRTY SIX RUPEES AND TEN PAISA

Amount with Tax in Words:- TWENTY EIGHT LAKH SEVEN THOUSAND THIRTY SIX RUPEES AND TEN PAISA


Approval Sequence

Item Key : 618764-463959					
Sr No.	From Approver	To Approver	Action	Comment Date	Approver comment
1	BAROT, TAPAN:DE Technical UGVCL HO	SHAKYA, MAHESHKUMAR:EE Technical UGVCL HO	SUBMIT	18-AUG-2018 12:11:33 PM	
2	SHAKYA, MAHESHKUMAR:EE Technical UGVCL	RESONSE BY USER	RESPONSE -- FORWARD	18-AUG-2018	Pl. scrutinise & process



Item Key : 618764-463959

Sr No.	From Approver	To Approver	Action	Comment Date	Approver comment
	HO			01:09:16 PM	
3	SHAKYA, MAHESHKUMAR:EE Technical UGVCL HO	GURJAR, DINESHBHAI:DE Technical UGVCL HO	SEND	18-AUG-2018 01:09:19 PM	
4	GURJAR, DINESHBHAI:DE Technical UGVCL HO	RESONSE BY USER	RESPONSE -- FORWARD	20-AUG-2018 11:19:58 AM	As directed for needful action please.
5	GURJAR, DINESHBHAI:DE Technical UGVCL HO	PATEL, NARENDRAKUMAR:DE Technical Palanpur Cir	SEND	20-AUG-2018 11:20:11 AM	
6	PATEL, NARENDRAKUMAR:DE Technical Palanpur Cir	RESONSE BY USER	RESPONSE -- FORWARD	28-AUG-2018 06:06:32 PM	SE (Sabarmati) was submitted Estimate for Renovation of meter testing laboratory office & store building at Sabarmati campus including extension & renovation of existing M.T Lab/ store with extension of 2 span for MT lab office and new ladies & gents toilet facility and replacing existing AC sheets Roof by RCC slab roof , kota stone flooring etc and its Amount comes Rs31,91,656.62 with 1% welfare cess and After scrutiny of Estimate there are several changes in dimension which was not correct as per attached drawing and change in column footing calculation as well as Nos of w/d & ventilation and rate correction(as per Ahmedabad PWD SOR 15-16) Estimate Amount comes to Rs 27,74,931.23 with 1% of welfare cess. So, As per Clause no 1.3 of committee level }works, CE (OP) has empowered for administrative approval of said work. Its put up for further na pls.
7	PATEL, NARENDRAKUMAR:DE Technical Palanpur Cir	SHAKYA, MAHESHKUMAR:EE Technical UGVCL HO	SEND	28-AUG-2018 06:06:34 PM	
8	SHAKYA, MAHESHKUMAR:EE Technical UGVCL HO	RESONSE BY USER	RESPONSE -- FORWARD	31-AUG-2018 12:22:21 PM	At present meter testing laboratory store functioning in building with A.C. sheet roof & cement pointing on outer face of wall in Sabarmati campus. This building was constructed in year 1957, so it is require to renovate the building with providing RCC slab in place of AC sheet roof, raising the existing plinth level, shelves for storing materials, kotah stone flooring, cement plaster on outer face of wall, alluminium door windows, colour works & extending the two span for M.T. Lab office with ladies & gents toilet block. Accordingly this estimate for extension & renovation of existing M.T. Lab with separte facility of ladies,gents toilet & after scrutiny at R & C office, amount comes to Rs 2807036.10 with 1 % welfare cess but



Item Key : 618764-463959

Sr No.	From Approver	To Approver	Action	Comment Date	Approver comment
					without GST. This is submitted herewith for further approval of competent authority as per DOP, clause No. 1.3 & 2.1 committee level- works, empowers C.E.to accord necessary admn. approval & technical sanction for the estimate prepared up to Rs. 50.00 lacs., Put up for further approval pl.
9	SHAKYA, MAHESHKUMAR:EE Technical UGVCL HO	TRIVEDI, PRASHANT:ACE Technical UGVCL HO	SEND	31-AUG-2018 12:22:24 PM	
10	TRIVEDI, PRASHANT:ACE Technical UGVCL HO	RESONSE BY USER	RESPONSE -- FORWARD	04-SEP-2018 03:15:54 PM	Recommended for approval please. Hard copy also processed simultaneously- FTS-Civil-37.
11	TRIVEDI, PRASHANT:ACE Technical UGVCL HO	KOTHARI, RASHMIKANT:GM Accounts UGVCL HO	SEND	04-SEP-2018 03:15:56 PM	
12	KOTHARI, RASHMIKANT:GM Accounts UGVCL HO	DAMOR, AMRABHAI:COA Accounts UGVCL HO	DELEGATE	04-SEP-2018 04:17:43 PM	PL verify & process.
13	DAMOR, AMRABHAI:COA Accounts UGVCL HO	KOTHARI, RASHMIKANT:GM Accounts UGVCL HO	DELEGATE	07-SEP-2018 12:23:29 PM	The estimate is found high , however as per clarity given at sr No-40 we my approve. As per DOP works 1.3 JMD/CEhas full power to accord an administrative approval up to Rs 50 lakhs.The Power of JMD/CE is vested to MD Sir. Recommended for approval in e-urja subject to approval in hard copy.
14	KOTHARI, RASHMIKANT:GM Accounts UGVCL HO	RESONSE BY USER	RESPONSE -- APPROVE_AND_FORWARD	10-SEP-2018 03:08:43 PM	Recommended for approval in e-urja subject to approval in hard copy.
15	KOTHARI, RASHMIKANT:GM Accounts UGVCL HO	MANGAL, ASHOKKUMAR:	SEND	10-SEP-2018 03:08:46 PM	
16	MANGAL, ASHOKKUMAR:	RESONSE BY USER	RESPONSE -- APPROVE	14-SEP-2018 11:05:12 AM	ApprovE subject to approval in hard copy.
17	MANGAL, ASHOKKUMAR:	BAROT, TAPAN:DE Technical UGVCL HO	FYI: PO_REQ_APPROVED_JRAD	14-SEP-2018 11:05:15 AM	