



KADI KALOL ROAD - DIVISION OFFICE - KADI(N.G.)382 715

PR NO	387568
RFQ NO	54086

**ADVERTISED TENDER
054/2019**

To,
M/s _____

**NAME OF WORK:- Erection & Maintenance work of HT,LT & TC For various scheme under Bechraji
Sdn PART-G Kadi DO**

Estimate cost	Rs 500000.00
Earnest Money	Rs 5900/-
Security Deposit	5% of Tender Value
Relevant documents (By Registered Post A.D. or Speed Post only) submission date	On or before date 31.07.2019 Up to 18.00 Hrs
Date of opening of Tender fee, EMD cover and Technical Bid physical as well as online	Date: 01.08.2019 up to 12.00 Hrs
Type of Tender	Item Rate
Tender Fee	Rs 500+90 (GST)/-
Time Limit	12 Month

Earnest money deposit will be accept in cash or Demand Draft on any Schedule Bank at KADI. In favors of UTTAR GUJARAT VIJ COMPANY LIMITED, Cheque or Bank Guarantee will not be accepted.

NOTE:-Tender copy accepted only by R.P.A.D

Supdts.Accounts(Exp)
U.G.V.C.L. DO KADI

Executive Engineer
U.G.V.C.L., DO, KADI

**PR- 387568****SCHEDULE : B-1****RFQ- 54086**

**Name of work : Erection & Maintenance work of HT, LT & TC For various scheme under Bechraji Sdn
PART-G Kadi DO**

Memorandum showing items of Erection work with rates quantity & amount.

Sr. No.	Description of Work	Estimate Qty.	Unit	TENDER RATE in Figure	Total
1	2	3	4	5	7
1	HT TAPPING FROM THE EXISTING POLE INCLUDING FIXING OF CROSS ARMS, CLAMPS, ANTI-CLIMBING DEVICES, DANGER BOARD, INSULATORS ETC. COMPLETE AND PAINTING OF FABRICATED MATERIALS AND NUMBERING COMPLETE WITH COST OF PAINTS AS PER STANDARD SPECIFICATION BUT EXCLUDING ERECTION OF GUY SET AND EARTHING. APPROVED QUALITY PAINT SHALL BE SUPPLIED BY THE CONTRACTOR	20	NO	278	5560
2	ERECTION OF HT PSC POLES OF 10 Mtr X 270 KG INCLUDING EXCAVATION OF PIT AND REFILLING OF EARTH, FIXING OF CROSS ARMS, TOP FITTING CLAMPS ANTI-CLIMBING DEVICES, INSULATORS ETC, COMPLETE AND PAINTING OF FABRICATED MATERIALS USED ON THE POLES AND NUMBERING WITH COST OF PAINTS AS PER STANDARD SPECIFICATION BUT EXCLUDING ERECTION OF GUY SET AND EARTING. APPROVED QUALITY PAINT SHALL BE SUPPLIED BY THE CONTRACTOR.	45	NO	1815	81675
3	ERECTION OF HT/LT PSC POLES OF 8 Mtr X 200 KG INCLUDING EXCAVATION OF PIT AND REFILLING OF EARTH, FIXING OF CROSS ARMS, TOP FITTING CLAMPS ANTI-CLIMBING DEVICES, INSULATORS ETC, COMPLETE AND PAINTING OF FABRICATED MATERIALS USED ON THE POLES AND NUMBERING WITH COST OF PAINTS AS PER STANDARD SPECIFICATION BUT EXCLUDING ERECTION OF GUY SET AND EARTING. APPROVED QUALITY PAINT SHALL BE SUPPLIED BY THE CONTRACTOR	140	NO	675	94500
4	ERECTION OF STEEL POLES OF 8 TO 9 METERS INCLUDING EXCAVATION OF PIT AND REFILLING OF EARTH, FIXING OF CROSS ARMS, TOP FITTING CLAMPS ANTI-CLIMBING DEVICES, DANGERS BOARD, INSULATORS ETC. COMPLETE AND PAINTING OF STEEL POLE, FABRICATED MATERIALS USED ON THE POLE AND NUMBERING WITH COST OF PAINT AS PER STANDARD SPECIFICATION BUT EXCLUDING ERECTION OF GUY SET AND EARTHING. APPROVED QUALITY PAINT SHALL BE SUPPLIED BY THE CONTRACTOR.	12	NO	1120	13440



UGVCL
Uttar Gujarat Vij Company Ltd.

CIN – U40102GJ2003SGC042906


5	ERECTION OF STEEL POLE OF 11 to 13 METERS FOR RAILWAY CROSSING ON BG/MG/NG LINE FOR 0.400/11/22KV OVER HEAD LINES I.E. INCLUDING EXCAVATION OF PIT & REFILLING OF EARTH, FIXING CROSS ARMS, TOP FITTING CLAMPS, ANTI-CLIMBING DEVICES DANGERS BOARD, INSULATORS ETC. COMPLETE AND PAINTING OF STEEL POLES, FABRICATED MATERIALS USED ON THE POLES AND NUMBERING WITH COST OF PAINT AS PER STANDARD SPECIFICATION BUT EXCLUDING ERECTION OF GUY SETS AND EARTHING. APPROVED QUALITY PAINT SHALL BE SUPPLIED BY THE CONTRACTOR.	6	NO	1315	7890
6	ERECTION OF DOUBLE POLE STRUCTURE OF 10 METERS PSC POLE INCLUDING EXCAVATION OF PITS & REFILLING OF EARTH, FIXING OF CHANNELS, SUPPORTING ANGLES, CLAMPS, ANTI-CLIMBING DEVICES DANGERS BOARDS, INSULATORS ETC. COMPLETE & PAINTING OF POLES, FABRICATED MATERIALS USED ON THE POLES AND NUMBERING WITH COST OF PAINTS AS PER STANDARD SPECIFICATION BUT EXCLUDING ERECTION OF GUY SET AND EARTHING. APPROVED QUALITY PAINT SHALL BE SUPPLIED BY THE CONTRACTOR.	2	NO	4030	8060
7	ERECTION OF DOUBLE POLE STRUCTURE OF 8 Mtr X 200 KG PSC POLES INCLUDING EXCAVATION OF PITS AND REFILLING OF EARTH, FIXING OF CHANNELS SUPPORTING ANGLES, CLAMPS, ANTI-CLIMBING DEVICES, DANGER BOARDS, INSULATORS, DO FUSES ETC. COMPLETE AND PAINTING OF FABRICATED MATERIALS USED ON THE POLES AND NUMBERING WITH COST OF PAINT AS PER STANDARD SPECIFICATION BUT EXCLUDING OF ERECTION OF GUY SET AND EARTHING. APPROVED QUALITY PAINT SHALL BE SUPPLIED BY THE CONTRACTOR	4	NO	1650	6600
8	ERECTION OF DOUBLE POLE STRUCTURE WITH MOUNTING OF AB SWITCH, HG FUSES OF 8 Mtr X 200 KG PSC POLES INCLUDING EXCAVATION OF PITS AND REFILLING OF EARTH, FIXING OF CHANNELS SUPPORTING ANGLES, CLAMPS, ANTI-CLIMBING DEVICES, DANGER BOARDS, INSULATORS, DO FUSES ETC. COMPLETE AND PAINTING OF FABRICATED MATERIALS USED ON THE POLES AND NUMBERING WITH COST OF PAINT AS PER STANDARD SPECIFICATION BUT EXCLUDING OF ERECTION OF GUY SET AND EARTHING. APPROVED QUALITY PAINT SHALL BE SUPPLIED BY THE CONTRACTOR.	1	NO	1810	1810
9	ERECTION OF DOUBLE POLE STRUCTURE OF 8 TO 9 METERS STEEL POLES INCLUDING EXCAVATION OF PITS AND REFILLING OF EARTH, FIXING OF CHANNEL, SUPPORTING ANGLES, CLAMPS, ANTI-CLIMBING DEVICES, DANGERS BOARDS, INSULATORS, ETC. COMPLETE AND PAINTING OF POLES FABRICATED MATERIALS USED ON THE POLES AND NUMBERING WITH COST OF PAINT AS PER STANDARD SPECIFICATION BUT EXCLUDING ERECTION OF GUY SET AND EARTHING. APPROVED QUALITY PAINT SHALL BE SUPPLIED BY THE CONTRACTOR.	1	NO	2335	2335



UGVCL
Uttar Gujarat Vij Company Ltd.

CIN – U40102GJ2003SGC042906

10	ERECTION OF DOUBLE POLE STRUCTURE WITH MOUNTING OF AB SWITCH, HG FUSES 9 TO 11 METERS STEEL POLES INLUDING EXCAVATION OF PITS AND REFILLING OF EATH, FIXING OF CHANNEL, SUPPORTING ANGLES, CLAMPS, ANTI-CLIMBING DEVICES, DANGERS BOARDS, INSULATIORS, ETC. COMPLETE AND PAINTING OF POLES FABRICATED MATERIALS USED ON THE POLES AND NUMBERING WITH COST OF PAINT AS PER STANDARD SPECIFICIATION BUT EXCLUDING ERECTION OF GUY SET AND EARTHING.APPROVED QUOLITY PAINT SHALL BE SUPPLIED BY THE CONTRACTOR.	1	NO	2370	2370
11	ERECTION OF DOUBLE POLES STRUCTURES WITH MOUNTING OF AB SWITCH, HG FUSES, TRANSFORMERS, LIGHTENING ARRESTORS, DISTRIBUTION BOX ETC. OF 8 Mtr X 200 KG. PSC POLES INCLUDING EXCAVATION OF PITS AND REFILENG OF EARTH, CARTING OF TRANSFORMERS FROM STORES TO SITE, FIXING OF CHANNELS, SUPPORTING ANGLES, BRACINGS CROSS ARMS CLAMPS, ANTICLIMBING DEVICES, DANGER BOARDS, CONDUCTOR AND CABLES WIRING ETC. COMPLETE AND PAINTING OF FABRICATED MATERIALS USED ON THE POLES AND NUMBERING WITH COST OF PAINT AS PER STANDARD SPECIFICATION BUT EXCLUDING ERECTION OF GUY SETS AND EARTHING.APPROVED QUOLITY PAINT SHALL BE SUPPLIED BY THE CONTRACTOR.	6	NO	5360	32160
12	ERECTION OF DOUBLE POLES STRUCTURES WITH MOUNTING OF AB SWITCH, HG FUSES, TRANSFORMERS, LIGHTENING ARRESTORS, DISTRIBUTION BOX ETC. OF 10 Mtr X 270 KG. PSC POLES INCLUDING EXCAVATION OF PITS AND REFILENG OF EARTH, CARTING OF TRANSFORMERS FROM STORES TO SITE, FIXING OF CHANNELS, SUPPORTING ANGLES, BRACINGS CROSS ARMS CLAMPS, ANTICLIMBING DEVICES, DANGER BOARDS, CONDUCTOR AND CABLES WIRING ETC. COMPLETE AND PAINTING OF FABRICATED MATERIALS USED ON THE POLES AND NUMBERING WITH COST OF PAINT AS PER STANDARD SPECIFICATION BUT EXCLUDING ERECTION OF GUY SETS AND EARTHING.APPROVED QUOLITY PAINT SHALL BE SUPPLIED BY THE CONTRACTOR.	2	NO	7430	14860
13	ERECTION OF DOUBLE STRUCTURE WITH MOUNTING OF AB SWITCH, HG FUSES TRANSFORMERS, LIGHTENING ARRESTORS, DISTRIBUTION BOX 9 TO 11 METERS STEEL POLES INCLUDING EXCAVATIONS OF PITS & REFILENG OF EARTH CARTING OF TRANSFORMERS FROM STORE TO SITE, FIXING OF CHANNELS SUPPORTING ANGLES, BRACING, CORSS ARMS CLAMPS, ANTICLIMBING DEVICES, DANGERS BOARDS, CONDUCTOR AND CABLE WIRING ETC. COMPLETE AND PAINTING OF POLES FABRICATED MATERIALS USED ON THE POLES AND NUMBERING AS PER STANDARD SPECIFICIATION BUT EXCLUDING ERECTIONS OF GUY SETS AND EARTHING.APPROVED QUOLITY PAINT SHALL BE SUPPLIED BY THE CONTRACTOR.	1	NO	6160	6160
14	ERECTION OF GUY SET INCLUDING EXCAVATION OF PITS & REFILENG OF EARTH AS PER STANDARD SPECIFICATION WITH STAY CLAMPS, STAY WIRE ANCHOR ROD, TURN BUCKLE, EYEBOT, GUY INSULATORS, CEMENT CONCRETE BLOCK ETC, BUT EXCLUDING CONCRETING.APPROVED QUOLITY PAINT SHALL BE SUPPLIED BY THE CONTRACTOR.	50	NO	315	15750



UGVCL

Uttar Gujarat Vij Company Ltd.

CIN – U40102GJ2003SGC042906

15	CONCRETING OF POLES, GUYS, ETC. INCLUDING COST OF CEMENT SAND METAL (1:2:4) AND WATER ETC. AS PER STANDARD SPECIFICATION.	1.5	CMT	5900	8850
16	ERECTION OF COIL TYPE EARTHING INCLUDING COST OF COAL SALT ETC. BUT WITHOUT COST OF GI WIRE AS PER STANDARD SPECIFICATION	70	NO	350	24500
17	ERECTION OF GI PIPE/CI PLATE TYPE EARTHING INCLUDING COST OF COAL SALT ETC. BUT WITHOUT COST OF PIPE/GI LPLATE GI WIRE AS PER STANDARD SPECIFICATION	70	NO	350	24500
18	REPLACEMENT OF EXISTING CONDUCTOR BY ANY SIZE OF ACSR/AAA/DOG WITH PROVIDING DOUBLE PIN BINDING & EXI CONDUCTOR DISMENTLING INCLUDING.	4	KM	2730	10920
19	STRINGING OF 30MM2 ACSR/34MM2, 55MM2 AAA CONDUCTOR FOR 11/22KV & LT LINES INLCUDING FIXING OF INSULATORS, BINDING JUMPERING ETC.	12.5	ONE COND PER KM	1240	15500
20	STRINGING OF DOG. CONDUCTOR FOR 11/22KV & INLCUDING FIXING OF INSULATORS, BINDING JUMPERING ETC.	3	ONE COND PER KM	2730	8190
21	PROVIDING GUARDING TO HT LINE/LT LINEON ROAD / RAIL CORSSING	50	MTR	58	2900
22	LT LINE TAPPING SINGLE PHASE (WHERE ADDITIONAL NUT BOLTS & FABRICATIONS/U- CLAMPS FITTING IS REQUIRED.)	22	NO	31	682
23	LT LINE TAPPING THREE PHASES (WHERE ADDITIONAL NUT BOLTS & FABRICATIONS/U- CLAMPS FITTING IS REQUIRED.)	20	NO	67	1340
24	Dismantling of HT tapping	6	NO	139	834
25	Dismantling of PSC Pole HT/LT 8 mtr.& RSJ Pole 8 TO 11 Long with fabrication (HT) crediting at store and stacking of pole safe at road side	25	NO	465	11625
26	Dismantling of Steel Pole (150 x 150 x 13)/10 Meter PSC Long with fabrication crediting at store and stacking of pole safe at road side.	2	NO	935	1870
27	Dismantling of transformer centre (PSC Pole) with crediting of materials at store and safe stacking of pole at road side. Without t/c unload	5	NO	1870	9350
28	Dismantling of transformer centre (PSC Pole) with crediting of materials at store and safe stacking of pole at road side. with transformer	5	NO	2750	13750
29	DISMENTALING OF CONDUCTOR FROM LINE 34/55 MM2 and crediting to store. Conductore has to dismental from shackle to shackle pole, with minimum nos. of cut piece as instruction of Engineer incharge.	7	KM	620	4340
30	DISMENTALING OF CONDUCTOR FROM LINE DOG 100 MM2	3	KM	1365	4095
31	NAME AND NUMBERING OF POLE WITH MATERIAL	32	NO	18	576




UGVCL

Uttar Gujarat Vij Company Ltd.

CIN – U40102GJ2003SGC042906

32	CONSUMER NUMBERING ON SMC WITH MATERIAL	32	NO	18	576
33	REPLACEMENT OF SINGLE PHASE OLD SERVICE BY NEW SERVICE WITH TOOLS & TACKLES, FIXING FASTENERS.	12	NO	225	2700
34	REPLACEMENT OF SINGLE PHASE METER WITH PROPER FITTING	25	NO	29	725
35	REFIXING AND REPLACEMENT OF MMB WITH SMC	25	NO	49	1225
36	LABOR CHARGE FORR SERVICE CONNECTION BOX 1PHASE 8 WAY WITH FIXING OF BOX WITH REQUIRED SIZE OF POLE CLAMP AND HARDWARE ACCESSORIES	25	NO	157	3925
37	TREEMING OF TREE BRANCHES	25	NO	27	675
38	ERECTION OF SPECIAL TYPE EARTHING OF DISTRIBUTION TRANSFORMERS: Digging a pit for Transformer Earthing of size of (0.2 x 0.2 x 2.5) MTR in soil near transformer centre as directed by the staff/E-I-C, to prepare a homogeneous mixture with the Earthing chemical provided by the company with the stuff dug out of the pit and to make complete Earthing by using material provided by company like GI strip, Rigid PVC pipe, CI pipe, CC Eathing Chamber, Flexible copper wire, Lugs, Nut-bolts and Earthing Chemical Powder.	1	NO	660	660
39	Laying of overhead LT cable for road crossing HT line crossing & telephone line crossing etc	3	NO	165	495
40	Providing Three phase 4 wire service connection with pvc 4mm ² /10mm ² four core cable from terminal pole to metering point including fixing of meter with meter earthing complete work as per slandered specification but excluding cost of material	13	NO	325	4225
41	Additional cost for excavation of pit in Hard rock area for erection of pole/GUY etc as per standard specification over & above normal cost covered against excavation of pin under normal soil for erection of pole Guy, DP structure earthing with approval of Supdt Engg	13	NO	230	2990
42	PROVIDING OF 1-ph NEW CONNETIN WITH PVC 2.5 MM ² CABLE FROM TERMINAL POLE TO METERING POINT INCLUDING FIXING OF METER, MMB(SMC) SERVICE PIPE, GI WIRE NO-10, EGG INSULATOR REEL INSULATOR ETC. AS PER SPECIFICATION AND INSTRUCTION OF INCHARGE ENGINEER.	25	NO	245	6125
43	Painting of 8/9 MTR Girder Pole with all fabrication material by First coat of red oxide, Second coat of silver color and Bottom 1 MTR of each pole is painted with black color paint as per instruction of engineer in charge	5	NO	935	4675
44	Painting of only fabrication material fitted on PSC Pole by First coat red oxide & Second coat silver color and Bottom 1 MTR of each pole is painted with black color paint as per instruction of engineer in charge	4	NO	192	768




UGVCL

Uttar Gujarat Vij Company Ltd.

CIN – U40102GJ2003SGC042906

45	Painting of Double Pole structure Girder Pole with all fabrication material fitted on it by First coat of red oxide, Second coat of silver color and Bottom 1 MTR of each pole is painted with black color paint as per instruction of engineer in charge	5	NO	1815	9075
46	Painting of only fabrication material fitted on double pole structure PSC Pole by First coat of red oxide, Second coat of silver color and Bottom 1 MTR of each pole is painted with black color paint as per instruction of engineer in charge.	5	NO	825	4125
47	Painting of 11 MTR Girder Pole with all fabrication material by First coat of red oxide, Second coat of silver color and Bottom 1 MTR of each pole is painted with black color paint as per instruction of engineer in charge	5	NO	1045	5225
48	Painting of 13 MTR Girder Pole with all fabrication material by First coat of red oxide, Second coat of silver color and Bottom 1 MTR of each pole is painted with black color paint as per instruction of engineer in charge	5	NO	1210	6050
49	REJUMPERING WORK OF TAPPING DO AB SWITCHES BY APPROVING 1 COATS OF GRUSLABLE EPOXY COMPOUND AS PER SPECIFICATION RATE TO BE INCLUSIVE OF COST OF DROPER COMPONENT	50	NO	16	800
50	REBINDING & CLEANING OF 11 KV PIN/DISC INSULATOR	50	NO	9	450
51	REPLACEMENT OF 11 KV DISC INSULATOR WITH H/W AS PER SPECIFICATION	12	NO	44	528
52	PLUMBING/STRAIGHTENING OF PSC POLE	12	NO	88	1056
53	LBOUR CHARGES FOR FIXING OF V-X ARM & TOP FITTING IN PLACE OF EXISTING LT FITTING LIKE LT SHACKLE INSULATOR , D-CLAMP, LT SHACKLE BOLT ETC. ON EXISTING PSC/ RSJ POLE INCLUDING PAINTING OF NEW FABRECAATION ITEMS.	7	NO	110	770
54	REPAIRING OF EXISTING GUY SET or REPLACEMENT OF GUY SET COMPLETELY	25	NO	82	2050
55	REPLACEMENT OF 11 KV PIN INSULATOR & BINDING	26	NO	16	416
56	PROVIDING L.A ON D.P. WITH ERECTION NEWLY PLATE/COIL TYPE EARTHING COMPLETE WITH EXCVATION OF EARTH AS PER SPECIFICATION EXLUDING GI WIRE & EARTHING PLATE/COIL COAL & SALT PROVIDE BY CONTRACTORAS AS PER INSTRUCTION GIVEN BY E-I-C.	3	NO	486	1458
57	PROVIDING LINE SEPARATOR THREE PHASE EXLUDING SEPARATOR AS PER E-I-C.	112	NO	11	1232
	Total Rs. (A)				499991.00
	Bidders offer(+/-) in % (B)				



UGVCL Uttar Gujarat Viji Company Ltd.

CIN – U40102GJ2003SGC042906

Grand Total (C) = A +/- (A*B)				
Goods and service Tax D= C x GST % GST Rate: ____% SAC Code:				
Grand Total including GST E= C + D				
Final Offer in RS.=				
Final Offer RS. In words				

The Bidder shall quote Firm Price only. The price quoted will not be subject to any escalation till completion of work.



The Above prices are inclusive of all taxes, levies Duties etc. except Goods & Service Tax (GST). **GST will be paid extra as applicable from time to time on a given taxable goods and /or services**

**Executive Engineer
U.G.V.C.L. KADI**

Contractor's Name & Signature

GENERAL INSTRUCTION TO TENDERERS

1. Sealed Tenders are invited for the work of erection of HT/LT line & T/c. from the contractors/firms who have executed works of similar nature and magnitude successfully.
2. Demand Draft date should be on or in between “one month before from the last date of receiving of tender to last date of receiving of tender.



3. Tender documents are in two bids system i.e. “**Technical Bid**” and “**Price Bid**”. Bidder has to submit tender in one Envelop and in this two different covers should be put. One cover mentioning **Technical bid** on it & another cover mentioning **Commercial Bid** on it. If we receive envelop that do not have two separate sealed covers than those bids are liable to be rejected. Technical bid should be submitted with documents as under, failing which tender is liable for rejection.

4. Technical bid is to be submitted in a separate sealed envelope and subscribing the envelope as “**Technical Bid**”.

Technical bid should be submitted with documents as under, failing which tender May liable for rejection.


- i. **Solvency certificate issued from any Nationalized Bank amounting to sum equivalent of estimated cost (Minimum 5 Lacks)**
- ii. **Separate EPF code No. allotted by RPFC required**
- iii. **Copy of PAN card**
- iv. **Work Order Copies of Three Different financial years for erection of HT/LT line & T/C work from UGVCL/ any Distribution Company of Gujarat/GETCO/GSEC is required.**
- v. **Contractor will have to submit the certificate of Electrical contractor license**
- vi. **Tools-Tackles statement**
- vii. **Vendor Registration Certificate as Class A Or Class B (Class C will not be considered) as a contractor with UGVCL/any Discom of Gujarat/GETCO/GSEC required**
- viii. **GST Tax Registration Number**

The above documents should be submitted in form of attested true copies along with technical bid.

5. The sealed price bids comprising of Schedule-‘B’ should be submitted in separate sealed envelope subscribing the envelope as “**Price Bid**”.

6. **Both “Technical” and” Price” bid should be submitted in one common envelope subscribing the name of the work and tender opening date etc.**



7. The bidders shall submit their offer without any deviations in general terms and conditions of the contract or in Technical specification/items. Tenders of such deviations may also be rejected. Incomplete and conditional tenders shall not be considered.



8. The rates shall be quoted both in words and figures as per unit specified in schedule-‘B’ in case of any discrepancy between the rates quoted in words & figures, rate quoted in words will prevail.
9. Intending bidders should submit their tenders after studying all tenders documents carefully and visiting the site for satisfying themselves of actual site conditions, location and accessibility of site and nature, extent of the work involved etc. Submission of tenders implies that bidders have obtained all necessary information and other data required for executing the work.
10. “Price bid” of only qualifying bidders on the basis of Technical bid shall only be opened. Price of bidders, who are not qualified technically as per requirement of technical bid shall not be opened.
11. All the works shall be carried out as per company standard specifications & work quantity may be increase or decrease during actual work within order amount.
12. Tenders, which do not fulfill all or any of the conditions of the tender of incomplete in any respect may liable to rejection.
13. **Executive Engineer,UGVCL Kadi DO, reserves the right to accept or reject any or all tenders without assigning any reason thereof.**
14. Income Tax at prevailing rate will be deducted as per Income Tax Act.
15. **The rate shall be excluding of GST tax. GST will be applicable as per UGVCL rule.**
16. Any change in rate of GST Tax shall be entertained during contractual period of contract.



GENERAL TERMS AND CONDITION FOR ERECTION WORKS

1. Good quality paints & red oxide like Asian, Nerolac, burger etc. make shall only be applied for Numbering & Painting.
2. If numbering are not done as per Specifications standard due to negligence from your side in that Case rate of Rs. 25 /- per location will be deducted from the bill.
3. Painting to the fabrication materials carried out by Departmentally and the same amount as actual cost & expenditure towards processing and administrative charges on material weight base will be deducted from the contractor bill. In case if painting done to fabrication materials by contractor then it must as per standard



specification and good quality of work required. Most probably painting work to fabrication material done by departmentally

4. If Transformer is not carting & commissioning then Rs 1500/- per Transformer or actual cost for TC carting will be deducted in your bill.
5. Charges for mounting of AB Switches and distribution boxes are including in item i.e. Erection of T/c. If AB switch and dist.box is not provided by UGVCL in that case Rs.100/- for each items shall be deducted for the bill or it same are not provided by contractor on the part of his negligence in that case Rs.500/- for each item shall be deducted from the bill.
6. If earthing of Pole or DP structure is not found in a separate PIT as per standard than such earthing work shall not be considered as a executed earthing quality and such earthing shall be Executed by UGVCL through other agency and amount incured shall be deducted from the bill.
7. UGVCL does not accept any responsibility as Factory Act, Minimum Wages Act Workmen's Compensation Act, Insurance Rules etc .or any other act rules or regulations that have to be Observed by the contractor for carrying out the work.
8. The contract will be governed by the UGVCL as per works terms and conditions of the UGVCL.
9. The contractor will be faulty answerable and responsible for all the material issued to him for the work by the UGVCL any theft and loss or pilferage shall have to be borne by the contractor.
10. All Fabrication material for Erection of pole will be Provided by UGVCL from Kadi Divisional store ie Vcross Arm,Top fittings,side clamps,MS angle 9',4',2, MS chanel 9',Anchor rod,Turn buckle,U clamp etc
11. Loading Unloading of all materials from division store will be borne by contractor.
12. Material carting from Division store to site will be borne by contractor.
13. PSC/Girder pole carting at site within two kilometer range will be borne by contractor.
14. The contractor will be solely responsible for any accident/damage either to equipments or any Human being during the time of execution of work.
15. All other general terms and conditions as prevailing in the UGVCL shall be applicable to this work Contract.
16. The contractor must engage sufficient knowledgeable person round the clock, exclusively for Execution of work.
17. The contractor has to carry out all the works in accordance with revised and latest provision under I.E .Rule Act (Amended time to time) made there under and as per instruction of Engineer in charge.
18. Tools, Tackles, Manpower, Crane facilities etc. not be provided by the UGVCL.
19. The compliances of all Central/State Govt. Rules, safety and Insurance rules etc. and that of local Body is must conditions for the agency.
20. In case, it is not possible for the contractor to continue the work either due to heavy rains or other Reasonable causes, such facts should be immediately brought to notice of the Engineer In charge. If the reasons for stopping the work are genuine the Engineer In charge may ask the contractor to start the work again as per condition. The period of such stoppage will not be considered as a part of working days moreover the contractor cannot claim compensation for such stoppage. If contractor not carried out the work as per instruction & time limit given by E.I.C then work is completed by some other resource hiring by E.I.C & the Amount incured of work is deducted from contractor Bill.
21. As regard damages to the materials, equipments, contractor himself will be responsible. If there is any compensation to be paid in respect of "WORKMAN "Compensation Act or any other statutory Provisions, the same will be paid by contractor directly. If he thinks fit, he may take necessary Insurance covering at his cost.



UGVCL
Uttar Gujarat Vij Company Ltd.

CIN – U40102GJ2003SGC042906

22. Time limit extension will be given if material is not supplied in time and in any case of objection not cleared in time but if materials given in time and there is no any objection, then no time limit Extension will be granted and penalty will be imposed as per rules.
23. The erection work should be carried out according to the specification as per instructions and Programmed laid out by the Engineer in charge. Contractor has to ensure safe shifting and erection of all accessories/equipments as per standard norms.
24. All the works shall be carried out in accordance with latest rules under Electricity Act.2003(with Amendments). After completion of work execution required Tests are to be taken in presence of Engineer In charge.
25. The contractor should employ as a Supervisor with sufficient qualification and experience who could Supervise the execution of work throughout. He should always be present on the site at the time of Work.
26. No higher rate or revised rate will be applicable for the work, if work is held-up/ closed due to Whatever so reasons.
27. Penalty clause: in case, the work is not completed within the period stipulated in the sub work order, penalty shall be levied at 0.5 per week on the total sub work order subject to maximum 10 % of respective sub work order
28. If work will not be carried out within time limit of sub work order , work will be carried out by other agency at risk and cost of contractor and the amount will be deducted from respective Bill/SD. SDO is authority to decide the agency for non-completion of work.
29. Successful Bidder is bound to work under any S/Dn of Division Office Kadi in any scheme if require with the same rate, conditions & without any type of extra charges.
30. All types Nuts & bolts (Should be as per UGVCL sample and specification) will be supplied by UGVCL, if same is not available in any extreme case and if provided by contractor Rs.50/-(Fifty) per Kg shall be paid by UGVCL to contractor.
31. All legal complication of disputes is subject to KADI JURISDICTION ONLY.

Contractor's signature with seal.

Executive Engineer
U.G.V.C.L. KADI