



Uttar Gujarat Vij Company Ltd.

CIN – U40102GJ2003SGC042906

PR NO	392396
RFQ NO	55173

ADVERTISED TENDER

TO,
M/s _____

Name of Work Maintenance of HT,LT pole ,Painting of RSJ pole and fabrication work
under VISNAGAR -1 S/Dn.

Tender Notice No 102/2019

Estimate cost.	Rs. 300000
Earnest Money.	Rs. 3540.00
Security Deposit.	5% of order value
Relevant documents (By Registered Post A.D. or Speed Post only) submission date	On or before date 18.11.2019 Up to 18.00 Hrs
Date of opening of Tender fee, EMD cover and Technical Bid physical as well as online	Date: 19.11.2019 up to 12.00 Hrs
Type of tender	Item Rate.
Tender Fee	Rs. 590.00
Time Limit	1 Year

Earnest money deposit will be accepted in cash or by demand draft on any schedule bank at VISNAGAR in favor of UTTAR GUJARAT VIJ COMPANY LIMITED, cheques or Bank guarantee will not be accepted. The tender without Earnest Money deposit will not be accepted. The date of D.D of EMD should be within 10 days from the date of receipt of tender.

Tender received through RPAD will be accepted.

SUPDT.ACCTT.
UGVCL, DO, VISNAGAR.

EXECUTIVE ENGINEER
UGVCL, DO,VISNAGAR.

UTTAR GUJARAT VIJ COMPANY LIMITED, DIVISION OFFICE, VISNAGAR.

SCHEDULE.B- (I)

MEMORANDUM SHOWING ITEMS OF MAINTANCE WITH RATE QTY.& AMOUNT

Name of Work :- Maintance of HT/LT ploe ,Painting of pole and pole fabrication work under Visnagar-1 S/Dn

Sr. No	DETAILS OF WORKS.	QTY.	UNIT.	RATE IN Rs.	Net Amount.
1	Replacement of 11 kv pin insulator by new pin insulator/composite pin insulator. 9908000002	200	No	31	6200
2	Replacement of 11 kv Disc insulator by new Disc insulator/composite Disc insulator. 9908000003	200	NO	106	21200
3	Replacement of LT Shackle insulator by new one. 9907000016	200	No	21	4200
4	Re fixing of V cross arm in proper positions. 9912020008	100	NO	41	4100
5	Replacement of V cross arm by new One. 9902010001	100	NO	139	13900
6	Re fixing of Top fitting arm in proper positions. 9911000010	100	NO	27	2700
7	Replacement of Top fitting arm by new One. 9911000010	100	NO	34	3400
8	Straighting of tailed PSC Poles/RSJ Poles at pin point. 9911000001	100	NO	189	18900
9	Straighting of tailed PSC Poles/RSJ Poles at tension point. 9911000001	70	NO	207	14490
10	Re – Tightening loose guy set in all aspect. 9911000001	55	NO	104	5720
11	Re – jumpering oh HT/LT line foe Shackle pole. 9911000031	55	Per pole	59	3245
12	Erection of Supports pole PSC/RSJ for stay i.e stude pole. 9911000007	55	NO	418	22990
13	Pin binding of conductor with 11 kv pin insulator as per instruction of engineer. 9911000004	55	Per pole	12	660
14	Pin binding of conductor with LT Shackle insulator as per instruction of engineer. 9911000004	55	Per pole	9	495
15	Numbering of pole with paint by preparing background one colour and have lettering (height 3” and width 0.5”) as	55	No	28	1540

Division Office: M.N.College Road VISNAGAR-384 315 (North Gujarat)

Telephone: (02765) 232375,
Website: www.ugvcl.com

Fax: (02765) 232579

e-mail: do.vsnee@gebmail.com

ASSURING THE BEST SERVICES TO OUR VALUED CONSUMERS

E:\tender\TENDER\MSNCO 102 UPLOADED ON 06.11.2019\vsn do\maintance AUG 2019\92 maintance of HT, LT line TC ,Painting of pole and fabrication worksunder VISNAGAR -1 sub division. -.doc



Uttar Gujarat Vij Company Ltd.

CIN – U40102GJ2003SGC042906

	directed by engineer in charge (Colour to be used must have ISI mark colour to be provided by contractor).9908000016				
16	Painting/writing consumer no. on SMC/MMB with letter size height 40mm and width 8 mm for Urban area.9911000015	55	NO	7	385
17	Painting/writing consumer no. on SMC/MMB with letter size height 40mm and width 8 mm for RURAL area.9911000015	55	NO	13	715
18	Converting pin point to shackle point including dismounting and retesting etc including the cost of nuts and bolts.9908000003	10	location	1619	16190
19	Replacement of 1 ph meter box without meter (fastener are to be provided by contractor).9908000023	220	NO	50	11000
20	Replacement of 1 ph meter only (urban area) by another one.9908000022	250	NO	34	8500
21	Replacement of 1 ph meter only (Rural area) by another one.9908000022	200	NO	45	9000
22	Replacement of 1 ph service line by new PVC/Armored service line Without meter and meter box) by using GI wire no 10,Real insulator, two no of Egg insulators including labour of fitting of necessary accessories at consumer end as per specification including the cost of nuts and bolts.9908000016	20	NO	170	3400
23	Removal/Dismantling of existing HT/LT line (34 mm ² to 55 mm ² conductor) and crediting to store. Conductor has to Dismantle from shackle pole with minimum nos. of cut piece as instruction of engineer incharge. 9903000001	10	Per cond. per km	650	6500
24	Removal/Dismantling of existing HT/LT line (Above 55 mm ² size conductor) and crediting to store. Conductor has to Dismantle from shackle pole to shackle pole with minimum nos. of cut piece as instruction of engineer incharge. 9903000001	20	Per cond. per km	1450	29000
25	Re stringing of HT & LT line (34 mm ² to 55 mm ²) conductor/coated conductor with new pin binding.9901000002	20	Per wire per Span	69	1380
26	Re stringing of HT & LT line (Above 55 mm ² size conductor) conductor/coated conductor with new pin binding. 9901000002	20	Per wire per Span	71	1420
27	Re stringing of 11 KV Aerial bunch cable (all size) per span with labour of fitting of accessories.9906000004	20	Per wire per Span	208	4160

Division Office: M.N.College Road VISNAGAR-384 315 (North Gujarat)

Telephone: (02765) 232375,
Website: www.ugvcl.com

Fax: (02765) 232579

e-mail:do.vsnee@gebmail.com

ASSURING THE BEST SERVICES TO OUR VALUED CONSUMERS

E:\tender\TENDER\MSNCO 102 UPLOADED ON 06.11.2019\vsn do\maintance AUG 2019\92 maintance of HT, LT line TC ,Painting of pole and fabrication worksunder VISNAGAR -1 sub division. -.doc

CIN – U40102GJ2003SGC042906

28	Trimming of tree branches onstructing HT/LT line on one tree. 9911000009	500	Per tree	35	17500
29	Trimming of bigger size of tree branches/whole tree constructing HT/LT line. 9911000009	50	Per day per labour	315	15750
	Only Colour/painting work on existing/erected items,two coats of red oxide colour (Appored ISI Mark) and two coats of silver colour (approved ISI mark) ..red oxide & Colours are to be supplied by contractor				
A	Painting of steel/MS Fabricated Materials of PSC/RSJ pole of (HT line) .9911000060	10	Nos	76	760
B	Painting of steel/MS Fabricated Materials of PSC/RSJ pole – HT pole Extension (HT line) 9911000066	10	Nos	110	1100
C	Painting of steel/MS Fabricated Materials of PSC/RSJ pole of (LT line- 4 wire) 9911000065	20	Nos	56 (per wire 14 rs)	1120
D	Painting of all steel/MS Fabricated Materials on DP Stucture (without transformer) of PSC/RSJ pole of (Excluding RSJ pole) 9911000059	20	Nos	235	4700
E	Painting of all steel/MS Fabricated Materials on DP Stucture with transformer of PSC/RSJ pole of (Excluding RSJ pole) 9911000059	20	Nos	480	9600
F	Painting of steel/RSJ -100*116 of 9 to 13mtr (Excluding fabricated material) 9911000059	20	Nos	700	14000
G	Painting of steel/RSJ -100*116 of 11 to 13mtr (Excluding fabricated material) 9911000059	20	Nos	900	18000
			TOTAL....		297920

GST rate excluding

I/am we/are willing to carry out the work at _____% above /below _____ percent (Should be written in figures and words) of the estimated rates mentioned above. Amount of my/our tender works out as under

Signature of contractor With seal

Executive Engineer
U.G.V.C.L. Visnagar
Division

SPECIFICATIONS

For erection work of 11 KV Transmission lines.LT distribution lines and transformer sub-stations.

ERECTION OF HT AND LT LINES.:

(a) Site clearing and tree cutting which come in the way of line will be done by the contractor at his cost. Any claim for compensation in above respect will have to be borne by the contractor.

(b) Fixing : Pole position :The position of pole structures guys and earthings will be fixed by the department and shown to the contractor. He shall adhere to these locations in all circumstances unless. Directed by the department to make any change.

(c) Pole setting :

Where poles are set in good solid ground the depth of pit shall be 1/6 the height of the pole and for grounds of any other nature depth of the pit shall be decided by the department. The poles and guys must not be set at the edge of cut/at shore/ embankments where soil is liable to be washed or eroded out such setting should be avoided while back filling, the each must be packed tight and in no case must earth be dumped to greater depth than four inches without being rammed hard before the next layer is thrown in extra earth should be packed around the poles and rammed. The cost of damage done to the pole during the erection will be recovered from the contractor. No pole which is out of plumb or out of alignment shall be accepted. The contractor will keep the poles and other materials in his safe custody in erected and he is liable to compensate to the Company the full cost of same along with supervision charges, if the pole is broken during the erection or stolen from him custody. He should be able to render full account of the poles entrusted to him whenever the supervising officer demands to scrutinizes the same.

1. Erection of Complete Single Pole Structure.

Erection of single pole structure comprises of shifting of pole from the place in the village to the site of actual work in that village excavation of pit erection in position (with base place where required) of 26' to 33' PSC poles 60 lbs/Yds. 30' to 42' long rail or suitable size girder or any other suitable pole fitting up clamps and cross arms and fabricated materials etc. Complete as per drawing inclusive of numbering fixing of caution Company and anticlimbing device. All size of Bolts and Nuts required should be used by the contractor at his cost. All the fabricated materials such as cross arms clamps turn buckles etc. fitted on the PSC poles of RCC poles should be painted first coat with red lead paint and then two coats of aluminum paint. The tendered has to use all the paints at his cost and should got approved by the Engineerin- charge before use.-Do- same as item No.1 (a and also including painting of steel poles)

2. Special two poles structures.

Special two poles structures such as for HT line tapping Railway crossing any other HT, LT or telephone line crossing, terminal structure comprises of excavation of suitable pits and refilling of earth, erection in position of two numbers 26' to 33' PSC poles 60 lbs/Ybs 30' to 42' long rails or any other suitable poles fitting of clamps and cross arms. Cross bracing etc. as per drawing inclusive of mounting H.G.Fuses (or A B Switch or HT metering equipments etc. numbering, fixing of caution Board and anticlubming device. The D.P. must be properly aligned and must be special structure if included will be erected as per drawing supplied. A size of bolts and nuts required for fitting the fabrication should be used by the at his cost including painting as per item No.1.

3. Stringing of Conductors.

This includes stringing of standard and solid bare conductors with fitting has necessary HT/LT pin and strain insulators, binding on insulators, jumpering jointing, The jointing in HT line will be done by twisting sleeve joints as per standard practice, Care must be taken in handling the conductor must not be drawn over tough or rocky ground, where it is liable to be damaged Alluminium and ACSR conductors must be drawn on wooden or alluminium pulleys only the conductor or coil must not be dropped Westage and cutting should be avoided as far as possible, Not more than 5% scrap will be accepted in the material account drawing to the proper tension. The sag and spans will be maintained as per drawing and design. The cross arms and insulators must be so fixed that neither tills or bends in any position. The rate quoted should be per conductor route kilometer. The span and sag. However may vary according to sizes of poles available but these dimensions will be specified by the field Engineer before commencement of work.. The sagging should be uniform for all conductors and uneven sagging will not be allowed.

4. Stringing of Continue cuss Earth Wire.

Where required the stringing of G.I. Wire No. 1 or S.W.G. is to be carried out for continuous earth wire and sag should be kept appropriate as per the conductor and continuous earth wire should be fixed on cross arm by using "011" size bolts nuts and washers. The required bolts nuts and washers should be used by the contractor at his cost. All the fabricated cross arms sifted on the pole should be connected to the earth wire by G.I.Wire.

4.(a) Guarding.

The guarding will have to be provided between crossing of HT and LT lines below the entire railway crossing. At the crossing at the crossing to telephone or telegraphs line (Licensee's HT and LT lines are passing below Company's HT line) road crossing and such other places as indicated by the department. The work comprises of fixing of guard cross-arms, eye bolts guard cradle as per design. Binding cross arms must be used where the HT line crosses the road. A clearance of 20 ft. must be available for all road crossing. The poles for road crossing must be concreted. The work has to be carried out as per drawings specially prepared for the purpose Guarding for railways crossing is to be carried out as per instructions of the Engineer-in-charge.

5. Erection of Stay set.

The erection of stay comprises of excavation of pit of 2'x2'x4' depth burying stay rods anchor plate, fixing of turn buckle binding of GI Stay wire. The stay insulators must be inserted in the stay wire on all stays as per drawing. The wrapping of the Guy wire strands at both ends at the stay insulator must be even and must present neat appearance and good workmanship. No stay should be left loose but should be tight and straight to withstand any cyclone or stand storm. The item includes refilling of earth and painting paint should be used by the contractor at his cost. If the guys are not required to be concreted, a per-casted cement concrete block will be supplied by the department at his divisional store at visnagar which the contractor will have to transport at his cost to the site of work and will have to use for fixing the guy road rate includes transportation and using the same in place of cement concerting of the guy. If the block is damaged during transport the cost of same will be recovered from the contractor.

6. Cement concreting for rail of R.S.J. pole or stay rod should be carried out in preparation 1:3:6 i.e. one part of cement three part of washed river sand and six part of well burnt brick-bat of 1x 1FF" size metals. The mixture should be prepared on the GI sheets and should be free from the dust the river sand, cement and the metal or brickbat should be used by the contractor at his cost.

7. Concreting for muffing of poles or stay rods should be as per item No. 6 above and size of the boxing provided should be Dia. Of 1.5 feet X height 3 feet and 1.5 feet should remain below the ground level and 1.5 feet should remain above the ground level.

8. Earthing

A pit of 2'x2'x6' is to be dug about 3' away from the pole on which earthing is required to be carried out. The earthing pipe supplied should be erected in the pit and should be hammered in the ground as far as possible and G.I.Wire for earthing should be bolted with the pipe and should be connected with earth wire of the pole by means of bolt 10 kg. of common salt and coal-dust should be provided per earthing by the contractor at his cost. Bolts nuts and washers should be used by the contractor at his cost.

9. Erection of Pole Mounted Transformer Center.

This work includes erection of special two pole structure as per item No.2 and fixing of all fabricated materials for support of line, L.A.H.G. fuses. A.B. switches transformer L.T. Dist. Box etc. The work includes of transportation and hoisting of transformer fixing of H.G. fuses A.B. switch L. As Distribution Box bilding numbering and V.I.R. or P.V.C. wiring and prodding two earthings as per the specifications and the instructions of the Engineer-in-charge including painting.

(a) Up to and including 100 KVA

(b) –do- as above but transformer above 100 KVA capacities.

10. Painting of Transformer Structure.

All the fabricated materials used on the structure including the steel poles, also should be painted first with on coat of red lead and then with two coats of good quality of aluminum paints should be applied by the contractor at his cost. The paint should be got approved by the Engineer-in-charge before use.

(a) same as above vat for P.S.C. poles.

Signature of Contractor

Executive Engineer
Visnagar

: GENERAL INSTRUCTION TO TENDERERS ::

1.0 Tender are invited for the work of **Maintance of HT,LT ploe ,Painting of pole and pole fabrication work under Visnagar-1 S/Dn office under division office Visnagar** from the contractors/firms who have executed works of similar nature and magnitude successfully and who are registered under appropriate class.

2.0 Tender documents are in two bids system i.e. “**Technical Bid**” and “**Price Bid**”.

2.1 Bidder has to submit **Technical bid** One cover mentioning **Technical bid** on it & with name of works. Technical bid should be submitted with documents as under, failing which tender is liable for rejection.

- (i) Solvency certificate issued from any Nationalized Bank amounting to twice sum of estimated cost .
- (ii) Separate EPF code No. allotted by RPFC & Last Six month of current year EPF Challan paid copy is required.
- (iii) The Vender Registration certificate in appropriate class as contractor in UGVCL require. The vender registration fees paid challan /receipt attached by bidder will not be acceptable.
- (iv) Income Tax & GST:
 - a. Latest income tax clearance certificate for the year 2018-19 And/or 2017-18
 - b. Income tax at prevailing rate will be deducted as per income tax act
 - c. The rate shall be inclusive of PF and all other state/central government taxes, cess and levies .
 - d. The GST/Service at the prevailing rate should be paid as per the rules.
Contractor shall have to pay whatever applicable taxes prevailing at the time of placement Of order execution of work /Bill payment etc."Since the tender in respect of this LOA/AT was floated under Pre GST Regime, this OA/A/T is issued considering Pre GST (Old Tax Structure), the supplier has to provide the details of ITC claimed/available under GST for supply of items under this OA/A/T duly certified by a practicing chartered accountant. The content, manner and formal of submission of ITC details will be intimated to the supplier in due course of time, the 20% payment of supply along with GST after adjusting the quantum of ITC shall be made against SR Note and on receipt of details of ITC in the prescribed formal duly certified by a practicing Chartered Accountant
 - e. The L1 shall have to give under taking on his letter pad as under:
 - We ,the supplier/contractor of GUVNL/or subsidiary company hereby unconditionally agree to transfer the amount as determined as the benefit available to us in the form of higher input tax credit due to introduction of GST LAW.
 - We hereby unconditionally agree that GUVNL /or subsidiary company has the absolute Right to recover the net amount so determined from payments by GUVNL /or subsidiary Company by way of clause no.....of Statutory Variation and clause no.....of excise duty of our AT/WO/PO which has been agreed to and accepted by us & also as per the clause 171 of the GST law referring to Anti-Profiteering Law wherein the Govt has made it compulsory to transfer the benefits on account of higher ITC available due to introduction of GST to the consumers.
 - f. Regarding conditions of Tax, it will be binding to the contractor at relevant times.

- (v) Experience :-Contractor should produce evidence of having experience in executing similar nature & magnitude of jobs preferably photo copy of orders secured from UGVCL and satisfactory completion certificate from respective department.& Certificate as per requirement for E rection and **Maintance of HT,LT ploe ,Painting of pole and pole fabrication work under** by authorized officer of Distribution Company. Minimum 3 years Experience certificate require.
- (vi) Group Insurance A copy of the insurance policy of the insured laborer’s under W.C. Act.
- (vii) Details of equipments available with the tendered & Tools & tackle Certificate
- (viii) Electrical contractor license or wireman certificate with engineer registration is required.
- (ix) Turn over details year wise on CA Letterhead At least 2 years.
- (x) Copy of the **Maintance of HT,LT ploe ,Painting of pole and pole fabrication** work orders any Distribution Company is required.
- (xi) Contractor should produce GST NO. & PAN CARD Copy.
- (xii) Payment of Bills will be made through REAL TIME GROSS SETTLEMENT (RTGS) System while submission of bill prescribed RTGS form shall have to be submitted for each Bill by Contractor/Agency..
- (xiii) Govt. license to electrical contractor issued by Govt. of Gujarat is required.
- (xiv) Labour license certificate.

The above documents should be submitted in form of attested true copies along with technical bid. If any documents are not submitted by bidder than do not consider those bidder proposal & do not open price bid of those bidder.

2.2 “Technical” bid should be submitted in one common envelope super scribing the name of the work and tender opening date etc.

3.0 Technical bid shall be opened on date at **11.00** hrs. (If possible) in the presence of the bidders, who remains present at that time.

4.0 Earnest money deposit of **Rs. 3540.00** should be deposited in form of DD of Nationalized Bank in favor of UTTAR GUJARAT VIJ COMPANY LIMITED drawn on any scheduled Bank, payable at Visnagar. No any tender accepted without EMD . The date of D.D of EMD should be in between 10 days from the last date of receipt of tender.

5.0 Bidders should complete the tender documents in all respects and they are to be signed with Company’s seal on all pages.

6.0 The bidders shall submit their offer without any deviations in general terms and conditions of the contract or in Technical specification/items. Tenders of such departing, may also be rejected. Incomplete and conditional tenders shall not be considered. Any Tender found with overwriting /correction on the rate will not be accepted.

7.0 UTTAR GUJARAT VIJ COM.LTD. reserves the right to split up the work covered in the scope of this contract amongst more than one contractor.

8.0 Intending bidders should submit their tenders after studying all tenders documents carefully and visiting the site for satisfying themselves of actual site conditions, location and accessibility of site and nature, extent of the work involved etc.

UGVCL
Uttar Gujarat Vij Company Ltd.
CIN – U40102GJ2003SGC042906

23.0 If any work will not be executed by contractor fully / partly due to non providing of materials by UGVCL ,than the amount at appropriate rate will be deducted from the contractors bill , as the amount of non execution of works is already included in the rate of order.

24.0 Terms & condition & other relevant documents is required .

25.0 D.D. for EMD should be kept with “technical bid” only .

26.0 Tender without payment of tender fee will not be accepted.

27.0 Delay /late receipt of tender will be rejected.

28.0 Successful bidder should have to pay security Deposit should be paid through D.D of any Nationalized/ Schedule Bank in favor of Utter Gujarat Vij Company Ltd.” payable at VISNAGAR.

29.0 Penalty: - For delay in work / supply occurring on account of reasons other than force majeure as accepted by DGS&D the contractor will be liable to of penalty at a rate of 0.5% per week subject to maximum 10% of bill value. The condition of delay part of existence of force majeure condition will have to be given GST on penalty will have to be paid by contractor

Signature of Contractor
Name Seal, Details address
With phone/fax.

Executive Engineer
Visnagar.