

Visnagar Road - DIVISION OFFICE - Mehsana(N.G.)					
<table border="1"><tr><td>PR NO</td><td>416091</td></tr><tr><td>RFQ NO</td><td>58647</td></tr></table>		PR NO	416091	RFQ NO	58647
PR NO	416091				
RFQ NO	58647				
<u>ADVERTISED TENDER 048/2020</u>					
To, M/s _____ _____ _____					
NAME OF WORK: Maintance WORK of HT,LT & TC for JAGUDAN sdn For various scheme under Mehsana DO.					
Estimate cost	Rs 500000				
Earnest Money	Rs 5900/-				
Security Deposit	5% of Tender Value				
Relevant documents (By Registered Post A.D. or Speed Post only) submission date	On or before date 30.05.2020 Up to 18.00 Hrs				
Date of opening of Tender fee, EMD cover and Technical Bid physical as well as online	Date:02.06.2020 up to 12.00 Hrs				
Tender Fee	Rs 500 + 90 (GST) /-				
Time Limit	12 Month				
Earnest money deposit will be accept in cash or Demand Draft on any Schedule Bank at Mehsana. In favors of UTTAR GUJARAT VIJ COMPANY LIMITED, Cheque or Bank Guarantee will not be accepted.					
NOTE:-Tender copy accepted only by R.P.A.D					
Supdts.Accounts(Exp) U.G.V.C.L. DO Mehsana	Executive Engineer U.G.V.C.L., DO, Mehsana				

**PR- 416091****SCHEDULE : B****RFQ- 58647****Name of work : Maintance WORK of HT,LT & TC FOR JAGUDAN FOR VARIOUS SCHEME UNDER MSH D.O****Memorandum showing items of Erection work with rates quantity & amount.**

Sr. No.	Description of Work	Estimate Qty.	Unit	TENDER RATE in Figure	Total
1	2	3	4	5	7
1	REPLACEMENT OF 11 KV PIN INSULATOR BY NEW PIN INSULATOR/COMPOSITE PIN INSULATOR .Code No. 9908000002	240	No	31	7440.00
2	REPLACEMENT OF 11 KV DISC INSULATOR BY NEW DISC INSULATOR/COMPOSITE DISC INSULATOR.Code No. 9908000003	200	No	106	21200.00
3	REPLACEMENT OF LT SHACKLE INSULATOR BY NEW ONE Code No. 9907000016	200	No	21	4200.00
4	RE FIXING OF V CROSS ARM IN PROPER POSITION Code No. 9911000010	200	No	41	8200.00
5	REPLACEMENT OF V X ARM BY NEW ONE Code No. 9911000010	150	No	139	20850.00
6	RE FIXING OF TOP FITTING ARM IN PROPER POSITION Code No. 9911000010	150	No	27	4050.00
7	REPLACEMENT OF TOP FITTING BY NEW ONE Code No. 9911000010	200	No	34	6800.00
8	STRAIGHTING OF TILTED PSC/RSJ POLES AT PIN POINT Code No.9911000001	200	No	189	37800.00
9	STRAIGHTING OF TILTED PSC/RSJ POLES AT TENSION POINT Code No.9911000001	100	NO	207	20700.00
10	RE-TIGHTENING OF LOOSE GUY SET IN ALL ASPECTS Code No. 9911000001	100	NO	104	10400.00




UGVCL

Uttar Gujarat Vij Company Ltd.

CIN – U40102GJ2003SGC042906

11	RE-JUMPERING OF HT/LT LINE FOR SHACKLE POLE Code No. 9911000031,	100	NO	59	5900.00
12	ERECTION OF SUPPORT POLE (PSC/RSJ) FOR STAY (I.E STUD POLE) Code No. 9911000007	100	NO	418	41800.00
13	PIN BINDING OF CONDUCTOR WITH 11KV PIN INSULATOR AS PER INSTRUCTION OF ENGINEER INCHARGE Code No. 9911000004	100	No	12	1200.00
14	PIN BINDING OF CONDUCTOR WITH LT SHACKLE INSULATOR AS PER INSTRUCTION OF ENGINEER INCHARGE Code No. 9911000004	100	No	9	900.00
15	CONVERTING PIN POINT TO SHACKLE POINT INCLUDING DISMENTALING & RESTRINGING ETC INCLUDING THE COST OF NUTS & BOLTS Code No.9908000003	20	No	1619	32380.00
16	REMOVAL/DISMENTALING OF EXISTING HT/LT LINE (34MM2 TO 55MM2 CONDUCTOR) AND CREDITING TO STORE. CONDUCTOR HAS TO DISMENTAL FROM SHACKLE TO SHACKLE POLE, WITH MINIMUM NOS OF CUT PIECE AS INSTRUCTION OF E.I.C Code No.9903000001	130	No	650	84500.0
17	REMOVAL/DISMENTALING OF EXISTING HT/LT LINE (ABOVE 55MM2 SIZE CONDUCTOR) AND CREDITING TO STORE. CONDUCTOR HAS TO DISMENTAL FROM SHACKLE TO SHACKLE POLE, WITH MINIMUM NOS OF CUT PIECE AS INSTRUCTION OF E.I.C Code No.9903000001	10	No	1450	14500.00
18	RE-STRINGING OF HT & LT LINES (34 MM2 TO 55 MM2) CONDUCTOR/COATED CONDUCTOR WITH NEW PIN BINDING, JUMPER ETC Code No.9901000002	20	1 WIRE PER SPAN	69	1380.00
19	RE-STRINGING OF HT & LT LINES (ABOVE 55 MM2 SIZE CONDUCTOR) CONDUCTOR/COATED CONDUCTOR WITH NEW PIN BINDING, JUMPER ETC Code No. 9901000002	16	1 WIRE PER SPAN	71	1136.00
20	RE-STRINGING OF 11KV AERIAL BUNCH CABLE (ALL SIZE) PER SPAN WITH LABOUR OF FITTING OF ACCESSORIES Code No.9906000004	20	PER SPAN	208	4160.00
21	TRIMMING OF TREE BRANCHES OBSTRUCTING HT/LT LINE ON ONE TREE	500	No	35	17500.00



UGVCL

Uttar Gujarat Vij Company Ltd.

CIN – U40102GJ2003SGC042906

	Code No. 9911000009				
22	TRIMMING OF BIGGER SIZE OF TREE BRANCHES/WHOLE TREE OBSTRUCTING HT/LT LINE Code No. 9911000009	50	NO	315	15750.00
23	PAINTING OF STEEL/MS FABRICATED MATERIALS OF PSC/RSJ POLE (HT LINE) Code No. 9911000060	20	NO	76	1520.00
24	PAINTING OF STEEL/MS FABRICATED MATERIALS OF PSC/RSJ POLE-HT POLE EXTENSION (HT LINE) Code No. 9911000066	20	NO	110	2200.00
25	PAINTING OF STEEL/MS FABRICATED MATERIALS OF PSC/RSJ POLE (LT LINE-4 WIRE)...RS 14 PER WIRE Code No. 9911000065	20	NO	56	1120.00
26	PAINTING OF STEEL/MS FABRICATED MATERIALS ON DP STRUCTURE (WITHOUT TRANSFORMER) OF PSC/RSJ POLE (EXCLUDING RSJ POLE) Code No. 9911000059	20	NO	235	4700.00
27	PAINTING OF STEEL/MS FABRICATED MATERIALS ON DP STRUCTURE (WITH TRANSFORMER) OF PSC/RSJ POLE (EXCLUDING RSJ POLE) Code No. 9911000059	20	NO	480	9600.00
28	PAINTING OF STEEL/RSJ POLE-100X116 OF 9 TO 13 MTR (EXCLUDING FABRICATED MATERIALS) Code No. 9911000059	20	NO	700	14000.00
29	PAINTING OF STEEL/RSJ POLE-150X150 OF 11 TO 13 MTR (EXCLUDING FABRICATED MATERIALS) Code No. 9911000059	20	NO	900	18000.00
30	HT TAPPING FROM THE EXISTING POLE INCLUDING FIXING OF CROSS ARMS, CLAMPS, ANIT-CLIMBING DEVICES, DANGER BOARD, INSULATORS ETC. COMPLETE AND PAINTING OF FABRICATED MATERIALS AND NUMBERING OF POLE, COMPLETE WITHOUT COST OF NUTS & BOLTS, PAINTS AS PER STANDARD SPECIFICATION BUT EXCLUDING ERECTION OF GUY SET AND EARTHING. Code No.9901000001	5	NO	313	1565.00



UGVCL
Uttar Gujarat Vij Company Ltd.

CIN – U40102GJ2003SGC042906


31	ERECTION OF PSC POLES OF 8 Mtr X 200 KG INCLUDING EXCAVATION OF PIT AND REFILLING OF EARTH, FIXING OF CROSS ARMS, TOP FITTING CLAMPS ANTI-CLIMBING DEVICES, INSULATORS ETC, COMPLETE AND PAINTING OF FABRICATED MATERIALS USED ON THE POLES AND NUMBERING OF POLE, WITHOUT COST OF NUTS & BOLTS, PAINTS AS PER STANDARD SPECIFICATION BUT EXCLUDING ERECTION OF GUY SET AND EARTHING Code No.9902010001	20	NO	757	15140.00
32	ERECTION OF PSC POLES OF 10 MTR X 270 KG INCLUDING EXCAVATION OF PIT AND REFILLING OF EARTH, FIXING OF CROSS ARMS, TOP FITTING CLAMPS ANTI-CLIMBING DEVICES, INSULATORS ETC, COMPLETE AND PAINTING OF FABRICATED MATERIALS USED ON THE POLES AND NUMBERING OF POLE, WITHOUT COST OF NUTS & BOLTS, PAINTS AS PER STANDARD SPECIFICATION BUT EXCLUDING ERECTION OF GUY SET AND EARTHING Code No.9902010002	2	No	1815	3630.00
33	ERECTION OF STEEL POLES OF 9 TO 11 METERS INCLUDING EXCAVATION OF PIT AND REFILLING OF EARTH, FIXING OF CROSS ARMS, TOP FITTING CLAMPS ANTI-CLIMBING DEVICES, DANGER BOARD, INSULATORS ETC. COMPLETE AND PAINTING OF STEEL POLE, FABRICATED MATERIALS USED ON THE POLE AND NUMBERING OF POLE, WITHOUT COST OF NUTS & BOLTS, PAINTS AS PER STANDARD SPECIFICATION BUT EXCLUDING ERECTION OF GUY SET AND EARTHING Code No.9902010003	2	NO	1268	2536.00
34	ERECTION OF STEEL POLE OF 13 METERS FOR RAILWAY CROSSING ON BG/MG/NG LINE FOR 0.400/11/22KV OVER HEAD LINES I.E. INCLUDING EXCAVATION OF PIT & REFILLING OF EARTH, FIXING CROSS ARMS, TOP FITTING CLAMPS, ANTI-CLIMBING DEVICES DANGERS BOARD, INSULATIORS ETC. COMPLETE AND PAINTING OF STEEL POLES, FABRICATED MATERIALS USED ON THE POLES AND NUMBERING OF POLE, WITHOUT COST OF NUTS & BOLTS, PAINTS AS PER STANDARD SPECIFICATION BUT EXCLUDING ERECTION OF GUY SET AND EARTHING Code No.9902010005	1	No	1453	1453.00
35	ERECTION OF DOUBLEL POLES STRUCTURE OF 8 MTR X 200 KG PSC POLES INCLUDING EXCAVATION OF PITS & REFILENG OF EARTHING, FIXING OF CHANNELS, SUPPORTING ANGLES, CLAIMPS, ANTI-CLIMBING DEVICES DANGER BOARDS, INSULATIORS ETC. COMPLETE AND PAINTING OF FABRICATED MATERIALS USED ON THE POLES AND NUMBERING OF POLE, WITHOUT COST OF NUTS & BOLTS, PAINTS AS PER STANDARD SPECIFICATION BUT EXCLUDING	2	No	1720	3440.00



UGVCL
Uttar Gujarat Viji Company Ltd.

CIN – U40102GJ2003SGC042906

	ERECTION OF GUY SET AND EARTHING Code No.9902020001				
36	ERECTION OF DOUBLE POLE STRUCTURE WITH MOUNTING OF AB SWITCH, HG FUSES OF 8 MTR X 200 KG PSC POLES INCLUDING EXCAVATION OF PITS AND REFILING OF EARTH, FIXING OF CHANNELS SUPPORTING ANGLES, CLAMPS, ANTI-CLIMBING DEVICES, DANGER BOARDS, INSULATORS, DO FUSES ETC. COMPLETE AND PAINTING OF FABRICATED MATERIAL USED ON THE POLES AND NUMBERING OF POLE, WITHOUT COST OF NUTS & BOLTS, PAINTS AS PER STANDARD SPECIFICATION BUT EXCLUDING ERECTION OF GUY SET AND EARTHING Code No.9902020003	1	No	2067	2067.00
37	ERECTION OF DOUBLE POLES STRUCTURES WITH MOUNTING OF AB SWITCH, HG FUSES, TRANSFORMERS, LIGHTENING ARRESTORS, DISTRIBUTION BOX ETC. OF 8 MTR X 200 KG. PSC POLES INCLUDING EXCAVATION OF PITS AND REFILING OF EARTH, CARTING OF TRANSFORMERS FROM STORES TO SITE, FIXING OF CHANNELS, SUPPORTING ANGLES, BRACINGS CROSS ARMS CLAMPS, ANTICLIMBING DEVICES, DANGER BOARDS, CONDUCTOR AND CABLES WIRING ETC. COMPLETE AND PAINTING OF FABRICATED MATERIALS USED ON THE POLES AND NUMBERING OF POLE, WITHOUT COST OF NUTS & BOLTS, PAINTS AS PER STANDARD SPECIFICATION BUT EXCLUDING ERECTION OF GUY SET AND EARTHING Code No.9902030003	1	NO	5900	5900.00
38	ERECTION OF GUY SET INCLUDING EXCAVATION OF PITS & REFILING OF EARTH AS PER STANDARD SPECIFICATION WITH STAY CLAMPS, STAY WIRE ANCHOR ROD, TURN BUCKLE, EYEBOLT, GUY INSULATORS, CEMENT CONCRETE BLOCK ETC. BUT EXCLUDING CONCRETING, WITHOUT COST OF NUTS & BOLTS. Code No.9902040001	10	NO	364	3640.00
39	CONCRETING OF POLES, GUYS, ETC. INCLUDING COST OF CEMENT SAND METAL (1:2:4) AND WATER ETC. AS PER STANDARD SPECIFICATION. Code No.9905010001	1	CMT	5900	5900.00
40	ERECTION OF COIL TYPE/CI PLATE TYPE EARTHING INCLUDING COST OF COAL SALT ETC WITHOUT COST OF NUTS & BOLTS. BUT WITHOUT COST OF GI WIRE AS PER STANDARD SPECIFICATION (10KG SALT + 10KG COAL) Code No.9902040002	20	No	419	8380.00
41	ERECTION OF GI PIPE/CI PLATE TYPE EARTHING INCLUDING COST OF COAL SALT ETC WITHOUT COST OF NUTS & BOLTS. BUT WITHOUT COST OF PIPE/GI LPLATE GI WIRE AS PER STANDARD SPECIFICATION (20KG SALT + 20KG COAL) Code No.9902040003	5	No	491	2455.00
42	STRINGING OF 30MM2 ACSR/ 34MM2, 55MM2 AAAC CONDUCTOR FOR 11/22KV & LT LINES INLCUDING FIXING OF INSULATORS, BINDING JUMPERING	1	KM	1373	1373.00



UGVCL
Uttar Gujarat Viji Company Ltd.

CIN – U40102GJ2003SGC042906

	ETC. Code No.9903000001Code No.9903000001				
43	RE-STRINGING OF HT & LT LINES (34 MM2 TO 55 MM2) CONDUCTOR/COATED CONDUCTOR WITH NEW PIN BINDING, JUMPER ETC Code No.9911000008	10	KM	69	690.00
44	PROVIDING GUARDING TO HT LINE ON ROAD / RAIL CORSSING WITHOUT COST OF NUTS & BOLTS Code No.9906000002	50	MTR	58	2900.00
45	PROVIDING GUARDING TO LT LINE ON ROAD / RAIL CORSSING WITHOUT COST OF NUTS & BOLTS Code No.9906000001	50	MTR	58	2900.00
46	DISMENTALLING OF PSC POLE 8 MTR IN USABLE CONDITION WITH CREDITING OF FABRICATION AT STORE & STACKING OF POLE AT SAFE AND ON ROAD SIDE Code No.9907000017	10	NO	511	5110.00
47	DISMENTALLING OF PSC POLE 10 MTR IN USABLE CONDITION WITH CREDITING OF FABRICATION AT STORE & STACKING OF POLE AT SAFE AND ON ROAD SIDE Code No.9907000017	10	NO	1028	10280.00
48	DISMENTALLING OF HT TAPPING WITH CREDITING OF FABRICATION AT STORE Code No.9907000016	10	NO	157	1570.00
49	DISMENTALLING OF TRANSFORMER CENTRE (PSC POLE) WITH CREDITING OF FABRICATION & TRANSFORMER AT STORE & STACKING OF POLE AT SAFE AND ON ROAD SIDE (WITH TRANSFORMER), POLE & TRANSFORMER SHOULD BE IN CONDITION AS IT WAS Code No.9907000007	1	NO	3025	3025.00
50	DISMENTALLING OF TRANSFORMER CENTRE (PSC POLE) WITH CREDITING OF FABRICATION & TRANSFORMER AT STORE & STACKING OF POLE AT SAFE AND ON ROAD SIDE (WITHOUT TRANSFORMER) TRANSFORMER SHOULD BE IN CONDITION AS IT WAS Code No.9907000007	1	NO	2057	2057.00



UGVCL Uttar Gujarat Viji Company Ltd.

CIN – U40102GJ2003SGC042906

	Total Rs. (A)			Total	499897.00
	Bidders offer(+/-) in % (B)				
	Grand Total (C) = A +/- (A*B)				
	Goods and service Tax D= C x GST %				
	GST Rate: ____%				
	SAC Code:				
	Grand Total including GST E= C + D				
	Final Offer in RS.=				
	Final Offer RS. In words				



The Bidder shall quote Firm Price only. The price quoted will not be subject to any escalation till completion of work.

Nut & Bolt will be supplied by UGVCL Mehsana DO. If same are not available with UGVCL Mehsana Store & provided by contractor than it will be reimbursed after producing of bills. But rate of Nut-Bolt claimed should not be more than the last purchase rate of UGVCL Mehsana & at present it is Rs. (59.40+18 % GST) per Kg.

The Above prices are inclusive of all taxes, levies Duties etc. except Goods & Service Tax (GST). **GST will be paid extra as applicable from time to time on a given taxable goods and /or services**

Executive Engineer
U.G.V.C.L. Mehsana D.O


Contractor's Name & Signature





GENERAL INSTRUCTION TO TENDERERS

1. Sealed Tenders are invited for the work of erection of HT/LT line & T/c. from the contractors/firms who have executed works of similar nature and magnitude successfully.
2. Demand Draft date should be on or in between “one month before from the last date of receiving of tender to last date of receiving of tender.
3. Tender documents are in two bids system i.e. “**Technical Bid**” and “**Price Bid**”. Bidder has to submit tender in one Envelop and in this two different covers should be put. One cover mentioning **Technical bid** on it & another cover mentioning **Commercial Bid** on it. If we receive envelop that do not have two separate sealed covers than those bids are liable to be rejected. Technical bid should be submitted with documents as under, failing which tender is liable for rejection. Also **Price Bid” shall be submit in “ON LINE” only**
4. Technical bid is to be submitted in a separate sealed envelope and subscribing the envelope as “**Technical Bid**”.
Technical bid should be submitted with documents as under, failing which tender May liable for rejection.
 - i. **Solvency certificate issued from any Nationalized Bank 20% of estimated cost (Minimum 1 Lacks)**
 - ii. **Separate EPF code No. allotted by RPFC required.**
 - iii. **Copy of PAN card**
 - iv. **NO REQUIRED Work Order Copies of for erection of HT/LT line & T/C work from UGVCL/ any Distribution Company of Gujarat/GETCO/GSEC BUT IF CONTRACTER HAVE Work Order Copies of for erection of HT/LT line & T/C SO ATTECHED WITH TENDER COPY.**
 - v. **Contractor will have to submit the certificate of Electrical contractor license**
 - vi. **Tools-Tackles statement.**
 - vii. **Vendor Registration Certificate as Class D as a contractor with UGVCL/any Discom of Gujarat/GETCO/GSEC required**
 - viii. **GST Tax Registration Number**
 - ix. **Group Insurance copy of the insurance policy of the insured laborer’s under W.C. Act. will be submit After Receicing the Work Order.**

The above documents should be submitted in form of attested true copies along with technical bid.



5. The sealed price bids comprising of Schedule-‘B’ should be submitted in separate sealed envelope subscribing the envelope as **“Price Bid”**.
6. **Both “Technical” and” Price” bid should be submitted in one common envelope subscribing the name of the work and tender opening date etc.**
7. The bidders shall submit their offer without any deviations in general terms and conditions of the contract or in Technical specification/items. Tenders of such deviations may also be rejected. Incomplete and conditional tenders shall not be considered.
8. The rates shall be quoted both in words and figures as per unit specified in schedule-‘B’ in case of any discrepancy between the rates quoted in words & figures, rate quoted in words will prevail.
9. Intending bidders should submit their tenders after studying all tenders documents carefully and visiting the site for satisfying themselves of actual site conditions, location and accessibility of site and nature, extent of the work involved etc. Submission of tenders implies that bidders have obtained all necessary information and other data required for executing the work.
10. “Price bid” of only qualifying bidders on the basis of Technical bid shall only be opened. Price of bidders, who are not qualified technically as per requirement of technical bid shall not be opened.
11. All the works shall be carried out as per company standard specifications & work quantity may be increase or decrease during actual work within order amount.
12. Tenders, which do not fulfill all or any of the conditions of the tender of incomplete in any respect may liable to rejection.
13. **Executive Engineer, UGVCL Mehsana DO, reserves the right to accept or reject any or all tenders without assigning any reason thereof.**
14. Income Tax at prevailing rate will be deducted as per Income Tax Act.
15. **The rate in ” schedule B ” shall be excluding of GST tax. GST will be applicable as per UGVCL rule.**
16. Any change in rate of GST Tax shall be entertained during contractual period of contract





17. If Contractor take GST, So Mentione clearly in schedule B.

18. Contractor do Maintance work of line as per instruction of consurn SDO.

GENERAL TERMS AND CONDITION FOR ERECTION WORKS


1. Good quality paints & red oxide like Asian, Nerolac, burger etc. make shall only be applied for Numbering & Painting.
2. If numbering are not done as per Specifications standard due to negligence from your side in that Case rate of Rs. 25 /- per location will be deducted from the bill.
3. Painting to the fabrication materials carried out by Departmentally and the same amount as actual cost & expenditure towards processing and administrative charges on material weight base will be deducted from the contractor bill. In case if painting done to fabrication materials by contractor then it must as per standard specification and good quality of work required. Most probably painting work to fabrication material done by departmentally
4. If Transformer is not carting & commissioning then Rs 1500/- per Transformer or actual cost for TC carting will be deducted in your bill.
5. Charges for mounting of AB Switches and distribution boxes are including in item i.e. Erection of T/c. If AB switch and dist.box is not provided by UGVCL in that case Rs.100/- for each items shall be deducted for the bill or it same are not provided by contractor on the part of his negligence in that case Rs.500/- for each item shall be deducted from the bill.
6. If earthing of Pole or DP structure is not found in a separate PIT as per standard than such earthing work shall not be considered as a executed earthing quality and such earthing shall be Executed by UGVCL through other agency and amount incured shall be deducted from the bill.
7. UGVCL does not accept any responsibility as Factory Act, Minimum Wages Act Workmen's Compensation Act, Insurance Rules etc .or any other act rules or regulations that have to be Observed by the contractor for carrying out the work.
8. The contract will be governed by the UGVCL as per works terms and conditions of the UGVCL.
9. The contractor will be faulty answerable and responsible for all the material issued to him for the work by the UGVCL any theft and loss or pilferage shall have to be borne by the contractor.
10. All Fabrication material for Erection of pole will be Provided by UGVCL from Mehsana Divisional store ie Vcross Arm,Top fittings,side clamps,MS angle 9',4',2, MS chanel 9',Anchor rod,Turn buckle,U clamp etc
11. Loading Unloading of all materials from division store will be borne by contractor.
12. Material carting from Division store to site will be borne by contractor.
13. PSC/Girder pole carting at site within two kilometer range will be borne by contractor.
14. The contractor will be solely responsible for any accident/damage either to equipments or any Human being during the time of execution of work.
15. All other general terms and conditions as prevailing in the UGVCL shall be applicable to this work Contract.
16. The contractor must engage sufficient knowledgeable person round the clock, exclusively for Execution of work.
17. The contractor has to carry out all the works in accordance with revised and latest provision under I.E .Rule Act (Amended time to time) made there under and as per instruction of Engineer in charge.
18. Tools, Tackles, Manpower, Crane facilities etc. not be provided by the UGVCL.



19. The compliances of all Central/State Govt. Rules, safety and Insurance rules etc. and that of local Body is must conditions for the agency.
20. In case, it is not possible for the contractor to continue the work either due to heavy rains or other Reasonable causes, such facts should be immediately brought to notice of the Engineer In charge. If the reasons for stopping the work are genuine the Engineer In charge may ask the contractor to start the work again as per condition. The period of such stoppage will not be considered as a part of working days moreover the contractor cannot claim compensation for such stoppage. If contractor not carried out the work as per instruction & time limit given by E.I.C then work is completed by some other resource hiring by E.I.C & the Amount incurred of work is deducted from contractor Bill.
21. As regard damages to the materials, equipments, contractor himself will be responsible. If there is any compensation to be paid in respect of "WORKMAN "Compensation Act or any other statutory Provisions, the same will be paid by contractor directly. If he thinks fit, he may take necessary Insurance covering at his cost.
22. Time limit extension will be given if material is not supplied in time and in any case of objection not cleared in time but if materials given in time and there is no any objection, then no time limit Extension will be granted and penalty will be imposed as per rules.
23. The erection work should be carried out according to the specification as per instructions and Programmed laid out by the Engineer in charge. Contractor has to ensure safe shifting and erection of all accessories/equipments as per standard norms.
24. All the works shall be carried out in accordance with latest rules under Electricity Act.2003(with Amendments). After completion of work execution required Tests are to be taken in presence of Engineer In charge.
25. The contractor should employ as a Supervisor with sufficient qualification and experience who could Supervise the execution of work throughout. He should always be present on the site at the time of Work.
26. No higher rate or revised rate will be applicable for the work, if work is held-up/ closed due to Whatever so reasons.
27. Penalty clause: in case, the work is not completed within the period stipulated in the sub work order, penalty shall be levied at 0.5 per week on the total sub work order subject to maximum 10 % of respective sub work order.
28. **Penalty clause:-** If the bill for the work,after Reconciling inventory given to contractor and depositing back the surplus material to respective RSO/Divisional stores, is no submitted within three month from the work completion date as per work completion date,then penalty @ Rs.200 per week or part there of plus applicable GST subject to maximum of 10% of order value plus applicable GST will be deducted.
29. If work will not be carried out within time limit of sub work order , work will be carried out by other agency at risk and cost of contractor and the amount will be deducted from respective Bill/SD. SDO is authority to decide the agency for non completion of work.
30. Successful Bidder is bound to work under any S/Dn of Division Office Mehsana in any scheme if require with the same rate, conditions & without any type of extra charges.
31. All types Nuts & bolts (Should be as per UGVCL sample and specification) will be supplied by UGVCL, if same is not available in any extreme case and if provided by contractor(Rs.59.40/ + GST)per Kg shall be paid by UGVCL to contractor.
32. All legal complication of disputes is subject to Mehsana JURISDICTION ONLY.



Save Energy for Benefit of Self and Nation



UGVCL
Uttar Gujarat Viji Company Ltd.

CIN – U40102GJ2003SGC042906

33. AS PER INSTRUCTION OF EXECUTIVE ENGINEER, Contractor must go to other sub division under Mehsana D.O for Maintenance work.

Contractor's signature with seal.

Executive Engineer
U.G.V.C.L. Mehsana