



Visnagar Road - DIVISION OFFICE - Mehsana(N.G.)					
<table border="1"><tr><td>PR NO</td><td>421581</td></tr><tr><td>RFQ NO</td><td>59781</td></tr></table>		PR NO	421581	RFQ NO	59781
PR NO	421581				
RFQ NO	59781				
<b><u>ADVERTISED TENDER 071/2020</u></b>					
To, M/s _____ _____ _____					
NAME OF WORK: Erection & Dismantling work of HT/LT & TC For work Under Mehsana Rural SDn,Part-B under Mehsana D.O,UGVCL.					
Estimate cost	Rs 500000				
Earnest Money	Rs 5900/-				
Security Deposit	5% of Tender Value				
Relevant documents (By Registered Post A.D. or Speed Post only) submission date	On or before date 14.07.2020 Up to 18.00 Hrs				
Date of opening of Tender fee, EMD cover and Technical Bid physical as well as online	Date: 15.07.2020 up to 12.00 Hrs				
Type of Tender	Item Rate				
Tender Fee	Rs 500+ 90 (GST) /-				
Time Limit	24 Month				
Earnest money deposit will be accept in cash or Demand Draft on any Schedule Bank at Mehsana. In favors of UTTAR GUJARAT VIJ COMPANY LIMITED, Cheque or Bank Guarantee will not be accepted.					
NOTE:-Tender copy accepted only by R.P.A.D					
<b>Supdts.Accounts(Exp)</b> <b>U.G.V.C.L. DO Mehsana</b>	<b>Executive Engineer</b> <b>U.G.V.C.L., DO, Mehsana</b>				



### PR-421581SCHEDULE : B-1RFQ- 59781

**Name of work :** Erection & Dismantling work of HT/LT & TC For work Under Mehsana Rural SDn,Part-B under Mehsana D.O,UGVCL.

**Memorandum showing items of Erection work with rates quantity & amount.**

Sr. No.	Description of Work	Estimate Qty.	Unit	TENDER RATE in Figure	Total
1	2	3	4	5	7
1	<b>HT Tapping</b> from the Existing Pole including Fixing of Cross Arms, Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing <b>Code.990100001</b>	20	No	313	<b>6260.00</b>
2	Erectionof <b>PSC POLES of 10 Mtr X 270 KG</b> including Fixing of PIT and refilling of Earth, fixing of cross Arms, Top Fitting Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing <b>Code. 9902010002</b>	13	No	1815	<b>23595.00</b>
3	Erectionof <b>PSC POLES of 8 Mtr X 200 KG</b> including Fixing of PIT and refilling of Earth, fixing of cross Arms, Top Fitting Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing <b>Code.9902010001</b>	30	No	757	<b>22710.00</b>
4	Erectionof <b>Steel Poles of 9 Mtr to 11 Meters</b> including Fixing of PIT and refilling of Earth, fixing of cross Arms, Top Fitting Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing <b>Code.9902010003</b>	2	No	1268	<b>2536.00</b>
5	Erectionof <b>Steel Poles of 13 Meters</b> including Fixing of PIT and refilling of Earth, fixing of cross Arms, Top Fitting Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing <b>Code. 9902010005</b>	2	No	1453	<b>2906.00</b>
6	Erectionof <b>Double POLES structure of 8 Mtr X 200 KG PSC Pole</b> including Excavation of PIT and refilling of Earthing, fixing of Channels, Supporting Angles, Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing <b>Code. 9902020001</b>	2	No	1720	<b>3440.00</b>
7	Erectionof <b>Double POLES structure of 10 Mtr X 200 KG PSC Pole</b> including Excavation of PIT and refilling of Earthing, fixing of Channels, Supporting Angles, Clamps Anti-Climbing Devices, Danger board, Insulators, ETC.	1	No	4030	<b>4030.00</b>



**UGVCL**  
**Uttar Gujarat Vij Company Ltd.**

CIN – U40102GJ2003SGC042906

	Complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing <b>Code.9902020025</b>				
8	Erectionof <b>DOUBLE POLES structure of 9 Mtr To 11 Meter Steel Pole</b> including Excavation of PIT and refilling of Earth, fixing of Channels, Supporting Angles, Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. Complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing <b>Code. 9902020007</b>	2	No	2485	<b>4970.00</b>
9	ERECTION OF DOUBLE POLE STRUCTURE WITH MOUNTING OF FAB SWITCH, HG FUSES OF 8 MTRS 200 KG PSC POLES INCLUDING EXCAVATION OF PITS AND REFILLING OF EARTH, FIXING OF CHANNELS SUPPORTING ANGLES, CLAMPS, ANTI-CLIMBING DEVICES, DANGER BOARDS, INSULATORS, DO FUSES ETC. COMPLETE AND PAINTING OF FABRICATED MATERIALS USED ON THE POLES AND NUMBERING WITHOUT COST OF NUTS & BOLTS, PAINT AS PER STANDARD SPECIFICATION BUT EXCLUDING OF ERECTION OF GUY SET AND EARTHING. <b>9902020003</b>	1	NO	2067	<b>2067.00</b>
10	ERECTION OF DOUBLE POLE STRUCTURE WITH MOUNTING OF AB SWITCH, HG FUSES, 9 TO 11 METERS STEEL POLES INCLUDING EXCAVATION OF PITS AND REFILLING OF EARTH, FIXING OF CHANNEL, SUPPORTING ANGLES, CLAMPS, ANTI-CLIMBING DEVICES, DANGER BOARDS, INSULATORS, ETC. COMPLETE AND PAINTING OF FABRICATED MATERIALS USED ON THE POLES AND NUMBERING WITHOUT COST OF NUTS & BOLTS, PAINT AS PER STANDARD SPECIFICATION BUT EXCLUDING ERECTION OF GUY SET AND EARTHING. <b>9902020010</b>	1	NO	2712	<b>2712.00</b>
11	ERECTION OF DOUBLE POLE STRUCTURE WITH MOUNTING OF AB SWITCH, HG FUSES, 13 METERS STEEL POLES INCLUDING EXCAVATION OF PITS AND REFILLING OF EARTH, FIXING OF CHANNEL, SUPPORTING ANGLES, CLAMPS, ANTI-CLIMBING DEVICES, DANGER BOARDS, INSULATORS, ETC. COMPLETE AND PAINTING OF FABRICATED MATERIALS USED ON THE POLES AND NUMBERING WITHOUT COST OF NUTS & BOLTS, PAINT AS PER STANDARD SPECIFICATION BUT EXCLUDING ERECTION OF GUY SET AND EARTHING. <b>9902020010</b>	1	NO	3080	<b>3080.00</b>
12	ERECTION OF SINGLE POLE STRUCTURES WITH MOUNTING OF AB SWITCH, HG FUSES, TRANSFORMERS, LIGHTENING ARRESTORS, DISTRIBUTION BOX ETC. OF 8 METERS 200 KG AND PSC POLES INCLUDING EXCAVATION OF PITS AND REFILLING OF EARTH, CARTING OF TRANSFORMERS FROM STORES TO SITE, FIXING OF CHANNELS, SUPPORTING ANGLES, BRACINGS CROSS ARMS CLAMPS, ANTI-CLIMBING DEVICES DANGER BOARDS, CONDUCTOR AND CABLE WIRING ETC. COMPLETE AND PAINTING OF FABRICATED MATERIALS USED ON THE POLES AND NUMBERING WITHOUT COST OF NUTS & BOLTS PAINT AS PER STANDARD SPECIFICATION BUT EXCLUDING ERECTION OF GUY SETS AND EARTHING. <b>9902030003</b>	1	NO	2949	<b>2949.00</b>
13	Erectionof <b>DOUBLE POLE structures with mounting of AB Switch, HG Fuses, Transformers, Lightning Arrestors, Distribution BOX ETC. of 8 Mtr X 200 KG PSC Pole</b> including Excavation of PIT and refilling of Earth, carting of Transformers from Store to Site, Fixing of Channels, Supporting Angles, Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing. <b>Code. 9902030003</b>	13	No	5900	<b>76700.00</b>



# UGVCL

## Uttar Gujarat Vij Company Ltd.

CIN – U40102GJ2003SGC042906

14	Erectionof <b>DOUBLEPOLE structureswith mounting of AB Switch, HG Fuses, Transformers, Lightning Arrestors, Distribution BOX ETC. of 10 Mtr X 200 KG PSC Pole</b> including Excavation of PIT and refilling of Earth, carting of Transformers from Store to Site, Fixing of Channels, Supporting Angles, Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing. <b>Code. 9902030003</b>	1	No	7430	<b>7430.00</b>
15	Erectionof <b>DOUBLEPOLE structureswith mounting of AB Switch, HG Fuses, Transformers, Lightning Arrestors, Distribution BOX ETC. of 9 Mtr to 13 Meter STEEL Poles</b> including Excavation of PIT and refilling of Earth, carting of Transformers from Store to Site, Fixing of Channels, Supporting Angles, Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing. <b>Code. 9902030007</b>	1	No	6899	<b>6899.00</b>
16	Erectionof <b>GUY SET</b> including Excavation of PIT and refilling of Earth, AS PER STANDARD SPECIFICATION WITH STAY CLAMPS, STAY WIRE, ANCHOR ROAD,TURN BUCKLE, EYE BOLT, GUY INSULATORE, CC BLOCK ETC. <b>Code. 9902040001</b>	10	No	364	<b>3640.00</b>
17	CONCRETING OF POLES, GUYS, ETC. INCLUDING COST OF CEMENT SAND METAL (1:2:4) AND WATER ETC. AS PER STANDARD SPECIFICATION <b>Code. 9905010001</b>	1	CMT	5900	<b>5900.00</b>
18	Erectionof <b>COIL TYPE/ CI PLATE TYPE EARTHING</b> INCLUDING COST OF COAL SALT ETC. BUT WITHOUT COST OF GI WIRE AS PER STANDARD SPECIFICATION(10 KG SALT + 10 KG COAL) <b>Code. 9902040002</b>	20	No	419	<b>8380.00</b>
19	Erectionof <b>GI PIPE/CI PLATE TYPE EARTHING</b> INCLUDING COST OF COAL SALT ETC. BUT WITHOUT COST OF PIPE/GI LPLATE GI WIRE AS PER STANDARD SPECIFIATION (20 KG SALT + 20 KG COAL) <b>Code. 9902040003</b>	5	No	491	<b>2455.00</b>
20	ERECTION OF STEERT LIGHT FIXTURE COMPLETE WITHCLAMOS,BRASS NIPPLES,BRASS HOLDERS TACK WOOD BRUSH,REFLECTORS FUSE,WIRING ETC WITHOUTR COST OF NUTS ABS BOLTS AS PER STANDARD SPECIFICATIONBUT EXCLUDING COST OF MATERIALS. <b>9902040004</b>	2	NO	227	<b>454.00</b>
21	STRINGING OF 30MM2 ACSR/34MM2, 55MM2 AAA CONDUCTOR FOR 11/22KV & LT LINES INLUCDING FIXING OF INSULATORS, BINDING JUMPERING ETC. <b>Code.9903000001</b>	2	Km	1373	<b>2746.00</b>
22	RE-STRINGING OF HT & LT LINES (34 MM2 TO 55 MM2) CONDUCTOR/COATED CONDUCTOR WITH NEW PIN BINDING, JUMPER ETC Code No.9911000008	10	Per span	69	<b>690.00</b>
23	STRINGING OF DOG. CONDUCTOR FOR 11/22KV & INLUCDING FIXING OF INSULATORS, BINDING JUMPERING ETC <b>Code. 9903000002</b>	1	Km	3162	<b>3162.00</b>
24	RE-STRINGING OF HT & LT LINES (ABOVE 55 MM2 SIZE CONDUCTOR)	5	Per span	71	<b>355.00</b>



# UGVCL

## Uttar Gujarat Vij Company Ltd.

CIN – U40102GJ2003SGC042906

	CONDUCTOR/COATED CONDUCTOR WITH NEW PIN BINDING, JUMPER ETC Code No. 9911000008				
25	STRINGING OF GI WIRE 8 SWG INCLUDING BINDING JUMPERING ETC. (WITHOUT COST OF NUTS & BOLTS If Required) Code No.9903000003	2	ONE COND. PER KM	769	<b>1538.00</b>
26	STRINGING OF HT AB Cable including fitting of ALL Accessories. <b>Code 9903000001</b>	1	Km	28994	<b>28994.00</b>
27	RE-STRINGING OF 11KV AERIAL BUNCH CABLE (ALL SIZE) PER SPAN WITH LABOUR OF FITTING OF ACCESSORIES Code No.9903000001	5	PER SPAN	208	<b>1040.00</b>
28	STRINGING OF LT LINE ABC including fittings of all accessories-1 phase. <b>Code 9903000001</b>	5	Km	5883	<b>29415.00</b>
29	STRINGING OF LT LIINE ABC including Fitting os ALL accessories-3 Phase. <b>Code 9903000001</b>	2	Km	14707	<b>29414.00</b>
30	PROVIDING GUARDING TO HT LINE ON ROAD / RAIL CORSSING <b>Code. 9906000002</b>	100	Meter	58	<b>5800.00</b>
31	PROVIDING GUARDING TO LT LINE ON ROAD / RAIL CORSSING <b>Code. 9906000001</b>	100	Meter	58	<b>5800.00</b>
32	LT LINE TAPPING SINGLE PHASE (WHERE ADDITIONAL NUT BOLTS & FABRICATIONS/U- CLAMPS FITTING IS REQUIRED <b>Code.9901000002</b>	5	No	32	<b>160.00</b>
33	LT LINE TAPPING THREE PHASES (WHERE ADDITIONAL NUT BOLTS & FABRICATIONS/U- CLAMPS FITTING IS REQUIRED <b>Code.9901000003</b>	5	No	59	<b>295.00</b>
34	STRINGING/LAYING OF OVER HEAD LT CABLE FOR ROAD CROSSING, HT LINE CROSSING AND TELEPHONE LINE CROSSING ETC (PER SPAN) WITHOUT COST OF NUTS & BOLTS, JUSTI KHILLAS Code No.9911000017	5	PER SPAN	162	<b>810.00</b>
35	STRAIGHTING OF TILTED PSC/RSJ POLES AT PIN POINT Code No.9902010001	50	NO	189	<b>9450.00</b>
36	STRAIGHTING OF TILTED PSC/RSJ POLES AT TENSION POINT Code No.9902010001	10	NO	207	<b>2070.00</b>
37	Dismantling of 8 Mtr. PSC POLE inusable Conditionwithcrediting offabricationat STORE & STACKING OF POLE AT SAFE AND ON ROAD SIDE <b>Code.9907000017</b>	50	No	511	<b>25550.00</b>




# UGVCL

## Uttar Gujarat Vij Company Ltd.

CIN – U40102GJ2003SGC042906

38	Dismantling of 10 mtr psc pole/ 13 MTR. GIRDER SIZE 100X150 MM IN USABLE CONDITION WITH CREDITING OF FABRICATION AT STORE & STACKING OF POLE AT SAFE AND ON ROAD SIDE <b>Code. 9907000017</b>	10	No	1028	<b>10280.00</b>
39	Dismantling of H.T. Tapping. <b>Code9907000016</b>	10	No	156	<b>1560.00</b>
40	Dismantling of transformer centre (8MT PSC Pole) with crediting of fabrication materials & Transformer at store and safe stacking of pole at road side <b>with TransformerCode.9907000008</b>	2	No	3025	<b>6050.00</b>
41	Dismantling of transformer centre ( 8MT PSC Pole) with crediting of fabrication materials & Transformer at store and safe stacking of pole at road side. <b>Without TransformerCode.9907000008</b>	1	No	2057	<b>2057.00</b>
42	DISMANTLING OF 9,11 MTR. GIRDER SIZE 100X150 MM INCL. CRED. IN STORE. <b>Code.9907000005</b>	2	No	634	<b>1268.00</b>
43	DISMANTLING OF STEEL POLE 13 MTR WITH CREDITING OF FABRICATION AT STORE & STACKING OF POLE AT SAFE AND ON ROAD SIDE  Code No. 9907000006	2	NO	726	<b>142.00</b>
44	Dismantling of Double Pole structure with AB switch <b>Code.9907000019</b>	1	NO	860	<b>860.00</b>
45	DISMANTLING OF DP (MS GIRDER) 100X116 MM MTR. LONG. INCL. CREDITING IN STORE. <b>Code.9907000004</b>	1	NO	1242	<b>1242.00</b>
46	Dismantling of Double Pole structure with AB switch <b>Code.9907000019</b>	1	NO	1033	<b>1033.00</b>
47	DISMANTLING OF DP STRUCTURE WITH D.O. FUSE& AB SWITCH (RSJ POLE) WITH CREDITING OF FABRICATION AT STORE & STACKING OF POLE AT SAFE AND ON ROAD SIDE.  Code No.9907000004	1	NO	1356	<b>1356.00</b>
48	DISMANTLING OF TRANSFORMER CENTRE (10MT PSC POLE) WITH CREDITING OF FABRICATION & TRANSFORMER AT STORE & STACKING OF POLE AT SAFE AND ON ROAD SIDE (WITH TRANSFORMER), POLE & TRANSFORMER SHOULD BE IN CONDITION AS IT WAS  Code No.9907000007	5	NO	3025	<b>15125.00</b>
49	DISMANTLING OF TRANSFORMER CENTRE (PSC POLE) WITH CREDITING OF FABRICATION & TRANSFORMER AT STORE & STACKING OF POLE AT SAFE AND ON ROAD SIDE (WITHOUT TRANSFORMER) TRANSFORMER SHOULD BE IN CONDITION AS IT WAS	5	NO	2057	<b>10285.00</b>




# UGVCL

## Uttar Gujarat Vij Company Ltd.

CIN – U40102GJ2003SGC042906

	Code No.9907000007				
50	DISMANTLING OF STAY SET. Code.9907000014	5	KM	182	<b>910.00</b>
51	DISMANTLING OF STREET LIGHT FIXTURE ON POLE WITH CLAMPS WITH CREDITING OF DISMANTLE MATERIAL AT STORE. Code No.9907000020	2	NO	113	<b>226.00</b>
52	DISMANTLING OF CONDUCTOR FROM LINE 34/55 MM2. Code.9907000009	5	KM	650	<b>3250.00</b>
53	REMOVAL/DISMANTLING OF EXISTING HT/LT LINE (ABOVE 55MM2 SIZE CONDUCTOR) AND CREDITING TO STORE. CONDUCTOR HAS TO DISMANTLE FROM SHACKLE TO SHACKLE POLE, WITH MINIMUM NOS OF CUT PIECE AS INSTRUCTION OF E.I.C Code No.9907000009	2	PER COND. PER KM	1450	<b>2900.00</b>
54	Dismantling of guardning of HT/LT line. Code. 9906000002	50	NO	29	<b>1450.00</b>
55	DISMANTLING OF GUARDING OF LT LINE ON ROAD /RAIL/TELEPHONE CROSSING WITH CREDITING OF DISMANTLE MATERIAL AT STORE. Code No.9907000021	50	MTR	29	<b>1450.00</b>
56	ERECTION OF SUPPORT POLE (PSC/RSJ) FOR STAY (I.E STUD POLE) Code No.9902010001	5	NO	418	<b>2090.00</b>
57	TRIMMING OF TREE BRANCHES OBSTRUCTING HT/LT LINE ON ONE TREE Code No.9911000009	200	Per Tree	35	<b>7000.00</b>
58	TRIMMING OF BIGGER SIZE OF TREE BRANCHES/WHOLE TREE OBSTRUCTING HT/LT LINE Code No.9911000009	200	Per Day Per Labour	315	<b>63000.00</b>
59	PAINTING OF STEEL/MS FABRICATED MATERIALS OF PSC/RSJ POLE (HT LINE) Code No.9911000059	10	NO	76	<b>760.00</b>
60	PAINTING OF STEEL/MS FABRICATED MATERIALS OF PSC/RSJ POLE-HT POLE	5	NO	110	<b>550.00</b>



**UGVCL**  
**Uttar Gujarat Viji Company Ltd.**

CIN – U40102GJ2003SGC042906

	EXTENSION (HT LINE) Code No.9911000059				
61	PAINTING OF STEEL/MS FABRICATED MATERIALS OF PSC/RSJ POLE (LT LINE-4 WIRE)...RS 14 PER WIRE Code No.9911000059	15	NO	56	<b>840.00</b>
62	PAINTING OF STEEL/MS FABRICATED MATERIALS ON DP STRUCTURE (WITHOUT TRANSFORMER) OF PSC/RSJ POLE (EXCLUDING RSJ POLE) Code No.9911000059	10	NO	235	<b>2350.00</b>
63	PAINTING OF STEEL/MS FABRICATED MATERIALS ON DP STRUCTURE (WITH TRANSFORMER) OF PSC/RSJ POLE (EXCLUDING RSJ POLE) Code No.9911000059	10	NO	480	<b>4800.00</b>
64	PAINTING OF STEEL/RSJ POLE-100X116 OF 9 TO 13 MTR (EXCLUDING FABRICATED MATERIALS) Code No.9911000059	10	NO	700	<b>7000.00</b>
65	PAINTING OF STEEL/RSJ POLE-150X150 OF 11 TO 13 MTR (EXCLUDING FABRICATED MATERIALS) Code No.9911000059	9	NO	900	<b>8100.00</b>
	<b>Total Rs. (A)</b>			<b>Total</b>	<b>499646.00</b>
	<b>Bidders offer(+/-) in % (B)</b>				
	<b>Grand Total (C) = A +/- (A*B)</b>				
	<b>Goods and service Tax D= C x GST %</b> <b>GST Rate: ____%</b> <b>SAC Code:</b>				
	<b>Grand Total including GST E= C + D</b>				
	<b>Final Offer in RS.=</b>				





Save Energy for Benefit of Self and Nation



**UGVCL**  
**Uttar Gujarat Vij Company Ltd.**

CIN – U40102GJ2003SGC042906

	<b>Final Offer RS. In words</b>				
--	---------------------------------	--	--	--	--



The Bidder shall quote Firm Price only. The price quoted will not be subject to any escalation till completion of work.

Nut & Bolt will be supplied by UGVCL Mehsana DO. If same are not available with UGVCL Mehsana Store & provided by contractor than it will be reimbursed after producing of bills. But rate of Nut-Bolt claimed should not be more than the last purchase rate of UGVCL Mehsana & at present it is Rs. (59.40+18 % GST) per Kg.

The Above prices are inclusive of all taxes, levies Duties etc. except Goods & Service Tax (GST). **GST will be paid extra as applicable from time to time on a given taxable goods and /or services**

**Executive Engineer**  
**U.G.V.C.L. Mehsana D.O**

**Contractor's Name & Signature**




### **GENERAL INSTRUCTION TO TENDERERS**

1. Sealed Tenders are invited for the work of erection of HT/LT line & T/c. from the contractors/firms who have executed works of similar nature and magnitude successfully.
  2. Demand Draft date should be on or in between “one month before from the last date of receiving of tender to last date of receiving of tender.
  3. Tender documents are in two bids system i.e. “**Technical Bid**” and “**Price Bid**”. Bidder has to submit tender in one Envelop and in this two different covers should be put. One cover mentioning **Technical bid** on it & another cover mentioning **Commercial Bid** on it. If we receive envelop that do not have two separate sealed covers than those bids are liable to be rejected. Technical bid should be submitted with documents as under, failing which tender is liable for rejection. Also **Price Bid” shall be submit in “ON LINE” only**
  4. Technical bid is to be submitted in a separate sealed envelope and subscribing the envelope as “**Technical Bid**”.  
Technical bid should be submitted with documents as under, failing which tender May liable for rejection.
    - i. **Solvency certificate issued from any Nationalized Bank 20% of estimated cost (Minimum 1 Lacks)**
    - ii. **Separate EPF code No. allotted by RPFC required.**
    - iii. **Copy of PAN card**
    - iv. **NO ANY EXPERIENCE Work Order Copies Required but if contractor have Work Order Copies so attech Three Different financial years for erection of HT/LT line & T/C work from UGVCL/ any Distribution Company of Gujarat/GETCO/GSECL.**
    - v. **Contractor will have to submit the certificate of Electrical contractor license**
    - vi. **Tools-Tackles statement.**
    - vii. **Vendor Registration Certificate as ClassDTYPE as a contractor with UGVCL/any Discom of Gujarat/GETCO/GSEC required.**
    - viii. **GST Tax Registration Number**
    - ix. **Group Insurance copy of the insurance policy of the insured laborer’s under W.C. Act.will be submit After Receicing the Work Order.**
- The above documents should be submitted in form of attested true copies along with technical bid.
5. The sealed price bids comprising of Schedule-‘B’ should be submitted in separate sealed envelope subscribing the envelope as “**Price Bid**”.





6. **Both “Technical” and” Price” bid should be submitted in one common envelope subscribing the name of the work and tender opening date etc.**
7. The bidders shall submit their offer without any deviations in general terms and conditions of the contract or in Technical specification/items. Tenders of such deviations may also be rejected. Incomplete and conditional tenders shall not be considered.
8. The rates shall be quoted both in words and figures as per unit specified in schedule-‘B’ in case of any discrepancy between the rates quoted in words & figures, rate quoted in words will prevail.
9. Intending bidders should submit their tenders after studying all tenders documents carefully and visiting the site for satisfying themselves of actual site conditions, location and accessibility of site and nature, extent of the work involved etc. Submission of tenders implies that bidders have obtained all necessary information and other data required for executing the work.
10. “Price bid” of only qualifying bidders on the basis of Technical bid shall only be opened. Price of bidders, who are not qualified technically as per requirement of technical bid shall not be opened.
11. All the works shall be carried out as per company standard specifications & work quantity may be increase or decrease during actual work within order amount.
12. Tenders, which do not fulfill all or any of the conditions of the tender of incomplete in any respect may liable to rejection.
13. **Executive Engineer,UGVCL Mehsana DO, reserves the right to accept or reject any or all tenders without assigning any reason thereof.**
14. Income Tax at prevailing rate will be deducted as per Income Tax Act.
15. **The rate shall be excluding of GST tax. GST will be applicable as per UGVCL rule.**
16. Any change in rate of GST Tax shall be entertained during contractual period of contract



**GENERAL TERMS AND CONDITION FOR ERECTION WORKS**

1. Good quality paints & red oxide like Asian, Nerolac, burger etc. make shall only be applied for Numbering & Painting.
2. If numbering are not done as per Specifications standard due to negligence from your side in that Case rate of Rs. 25 /- per location will be deducted from the bill.
3. Painting to the fabrication materials carried out by Departmentally and the same amount as actual cost & expenditure towards processing and administrative charges on material weight base will be deducted from the contractor bill. In case if painting done to fabrication materials by contractor then it must as per standard specification and good quality of work required. Most probably painting work to fabrication material done by departmentally
4. If Transformer is not carting & commissioning then Rs 1500/- per Transformer or actual cost for TC carting will be deducted in your bill.
5. Charges for mounting of AB Switches and distribution boxes are including in item i.e. Erection of T/c. If AB switch and dist.box is not provided by UGVCL in that case Rs.100/- for each items shall be deducted for the bill or it same are not provided by contractor on the part of his negligence in that case Rs.500/- for each item shall be deducted from the bill.
6. If earthing of Pole or DP structure is not found in a separate PIT as per standard than such earthing work shall not be considered as a executed earthing quality and such earthing shall be Executed by UGVCL through other agency and amount incured shall be deducted from the bill.
7. UGVCL does not accept any responsibility as Factory Act, Minimum Wages Act Workmen's Compensation Act, Insurance Rules etc .or any other act rules or regulations that have to be Observed by the contractor for carrying out the work.
8. The contract will be governed by the UGVCL as per works terms and conditions of the UGVCL.
9. The contractor will be faulty answerable and responsible for all the material issued to him for the work by the UGVCL any theft and loss or pilferage shall have to be borne by the contractor.
10. All Fabrication material for Erection of pole will be Provided by UGVCL from Mehsana Divisional store ie Vcross Arm,Top fittings,side clamps,MS angle 9',4',2, MS chanel 9',Anchor rod,Turn buckle,U clamp etc
11. Loading Unloading of all materials from division store will be borne by contractor.
12. Material carting from Division store to site will be borne by contractor.
13. PSC/Girder pole carting at site within two kilometer range will be borne by contractor.
14. The contractor will be solely responsible for any accident/damage either to equipments or any Human being during the time of execution of work.
15. All other general terms and conditions as prevailing in the UGVCL shall be applicable to this work Contract.
16. The contractor must engage sufficient knowledgeable person round the clock, exclusively for Execution of work.
17. The contractor has to carry out all the works in accordance with revised and latest provision under I.E .Rule Act (Amended time to time) made there under and as per instruction of Engineer in charge.
18. Tools, Tackles, Manpower, Crane facilities etc. not be provided by the UGVCL.
19. The compliances of all Central/State Govt. Rules, safety and Insurance rules etc. and that of local Body is must conditions for the agency.
20. In case, it is not possible for the contractor to continue the work either due to heavy rains or other Reasonable causes, such facts should be immediately brought to notice of the Engineer In charge. If the reasons for stopping the work are genuine the Engineer In charge may ask the contractor to start the work again as per condition.



The period of such stoppage will not be considered as a part of working days moreover the contractor cannot claim compensation for such stoppage. If contractor not carried out the work as per instruction & time limit given by E.I.C then work is completed by some other resource hiring by E.I.C & the Amount incurred of work is deducted from contractor Bill.

21. As regard damages to the materials, equipments, contractor himself will be responsible. If there is any compensation to be paid in respect of "WORKMAN "Compensation Act or any other statutory Provisions, the same will be paid by contractor directly. If he thinks fit, he may take necessary Insurance covering at his cost.
22. Time limit extension will be given if material is not supplied in time and in any case of objection not cleared in time but if materials given in time and there is no any objection, then no time limit Extension will be granted and penalty will be imposed as per rules.
23. The erection work should be carried out according to the specification as per instructions and Programmed laid out by the Engineer in charge. Contractor has to ensure safe shifting and erection of all accessories/equipments as per standard norms.
24. All the works shall be carried out in accordance with latest rules under Electricity Act.2003(with Amendments). After completion of work execution required Tests are to be taken in presence of Engineer In charge.
25. The contractor should employ as a Supervisor with sufficient qualification and experience who could Supervise the execution of work throughout. He should always be present on the site at the time of Work.
26. No higher rate or revised rate will be applicable for the work, if work is held-up/ closed due to Whatever so reasons.
27. Penalty clause: in case, the work is not completed within the period stipulated in the sub work order, penalty shall be levied at 0.5 per week on the total sub work order subject to maximum 10 % of respective sub work order
28. **Penalty clause:-** If the bill for the work,after Reconciling inventory given to contractor and depositing back the surplus material to respective RSO/Divisional stores, is no submitted within three month from the work completion date as per work completion date,then penalty @ Rs.200 per week or part there of plus applicable GST subject to maximum of 10% of order value plus applicable GST will be deducted.
29. If work will not be carried out within time limit of sub work order , work will be carried out by other agency at risk and cost of contractor and the amount will be deducted from respective Bill/SD. SDO is authority to decide the agency for non completion of work.
30. Successful Bidder is bound to work under any S/Dn of Division Office Mehsana in any scheme if require with the same rate, conditions & without any type of extra charges.
31. All types Nuts & bolts (Should be as per UGVCL sample and specification) will be supplied by UGVCL, if same is not available in any extreme case and if provided by contractor( Rs.59.40/ + GST)per Kg shall be paid by UGVCL to contractor.
32. All legal complication of disputes is subject to Mehsana JURISDICTION ONLY.
33. **AS PER INSTRUCTION OF EXECUATIVE ENGINEER, Contractor must go to other sub division under Mehsana D.O for Erection work.**
34. **After Complete TENDER Process, When Mehsana D.O has Required work pertain Tender then & then after Work order Issue.**

Executive Engineer

Contractor's signature with seal.U.G.V.C.L. Mehsana D.O