



PR.NO :- 422969 / RFQ.NO:- 60074
Tender Notice No MSN CO : 085/2020

Executive Engineer, UGVCL, Kadi DO invites On-line e- Tender for work of Erection, Dismantling & Maintenance work of HT/LT lines & T/C for Kadi-1 Sdn under Kadi DO. Tender Papers & Specifications may be down loaded from Web site <https://ugvcl.nprocure.com> (To view, download and on-line submission) and UGVCL web site www.ugvcl.com (To view & download only). Last date of on line submission is _____, upto 15 hrs. Tender fee may be paid along with submission of tender and its receipt to be kept in the cover containing EMD, for respective tender. “All the relevant documents of tenders to be submitted physically” will be received only by Registered Post A.D. or Speed Post addressed to Executive Engineer, UTTAR GUJARAT VIJ COMPANY LTD., DIVISION OFFICE, Kadi. “NO COURIER SERVICE OR HAND DELIVERY” will be allowed.



KADI KALOL ROAD - DIVISION OFFICE - KADI(N.G.)382 715

PR NO	422969
RFQ NO	60074

ADVERTISED TENDER

To,
M/s

NAME OF WORK: Erection, Dismantling & Maintenance work of HT/LT lines & T/C for Kadi-1 Sdn under Kadi DO.

Estimate cost	Rs 1999999.00
Earnest Money	Rs 20000/-
Security Deposit	5% of Tender Value
Online Preliminary, Technical & Price bid i.e. On line (e-tendering) tender/offer submission last date (This is mandatory)	Date: 17.08.2020 Up to 18.00 Hrs
Relevant documents (By Registered Post A.D. or Speed Post only) submission date	On or before date 19.08.2020 Up to 18.00 Hrs
Date of opening of Tender fee, EMD cover and Technical Bid physical as well as online	Date: 20.08.2020 up to 12.00 Hrs
Date of On line Opening of Price Bid (Tentative, if possible)	Date: 20.08.2020 up to 16.00 Hrs
Type of Tender	Item Rate
Tender Fee	Rs 1000+180 (GST) /-
Time Limit	12 Month

Earnest money deposit will be accept in only Demand Draft on any Schedule Bank at KADI. In favors of UTTAR GUJARAT VIJ COMPANY LIMITED, Cheque, cash or Bank Guarantee will not be accepted.

NOTE:-Tender copy accepted only by R.P.A.D or Speed Post only.

Supdts.Accounts(Exp)
U.G.V.C.L. DO KADI


Executive Engineer
U.G.V.C.L., DO, KADI

**PR- 422969****SCHEDULE : B-1****RFQ-60074**

Name of work : Erection, Dismantling & Maintenance work of HT/LT lines & T/C for Kadi-1 Sdn under Kadi DO.

Memorandum showing items of Erection work with rates quantity & amount.

Sr. No.	Description of Work	Estimate Qty.	Unit	TENDER RATE in Figure	Total
1	2	3	4	5	7
1	HT Tapping from the Existing Pole including Fixing of Cross Arms, Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing Code.9901000001	120	No	313	37560.00
2	Erection of PSC POLES of 8 Mtr X 200 KG including Fixing of PIT and refilling of Earth, fixing of cross Arms, Top Fitting Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing . 9902010001	200	No	757	151400.00
3	Erection of PSC POLES of 10 Mtr X 270 KG including Fixing of PIT and refilling of Earth, fixing of cross Arms, Top Fitting Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing . 9902010002	100	No	1815	181500.00
4	Erection of Steel Poles of 9 Mtr to 11 Meters including Fixing of PIT and refilling of Earth, fixing of cross Arms, Top Fitting Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing . 9902010003	40	No	1268	50720.00
5	Erection of Steel Poles of 13 Meters including Fixing of PIT and refilling of Earth, fixing of cross Arms, Top Fitting Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing Code. 9902010005	40	No	1453	58120.00
6	Erection of Double POLES structure of 8 Mtr X 200 KG PSC Pole including Excavation of PIT and refilling of Earthing, fixing of Channels, Supporting Angles, Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing Code. 9902020003	20	No	1720	34400.00
7	Erection of Double POLES structure of 10 Mtr X 200 KG PSC Pole including Excavation of PIT and refilling of Earthing, fixing of Channels, Supporting Angles, Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. Complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set	10	No	4030	40300.00



	and Earthing Code. 9902020025				
8	Erection of Double POLES structure of 9 Mtr To 11 Meter Steel Pole including Excavation of PIT and refilling of Earth, fixing of Channels, Supporting Angles, Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. Complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing Code. 9902020010	10	No	2485	24850.00
9	Erection of Double POLES structure with mounting of AB Switch, HG Fuses of 8 Mtr X 200 KG PSC Pole including Excavation of PIT and refilling of Earth, fixing of Channels, Supporting Angles, Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing Code. 9902020003	10	No	2067	20670.00
10	Erection of Double POLES structure with mounting of AB Switch, HG Fuses of 9 Mtr TO 11 Meter Steel Poles including Excavation of PIT and refilling of Earth, fixing of Channels, Supporting Angles, Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing . 9902020010	10	No	2712	27120.00
11	Erection of Double POLES structure with mounting of AB Switch, HG Fuses of 13 Meter Steel Poles including Excavation of PIT and refilling of Earth, fixing of Channels, Supporting Angles, Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing Code. 9902010005	10	No	3080	30800.00
12	Erection of SINGLE POLE structure with mounting of AB Switch, HG Fuses, Transformers, Lightning Arrestors, Distribution BOX ETC. of 8 Mtr X 200 KG PSC Pole including Excavation of PIT and refilling of Earth, carting of Transformers from Store to Site, Fixing of Channels, Supporting Angles, Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing. Code. 9902030003	20	No	2949	58980.00
13	Erection of DOUBLE POLE structures with mounting of AB Switch, HG Fuses, Transformers, Lightning Arrestors, Distribution BOX ETC. of 8 Mtr X 200 KG PSC Pole including Excavation of PIT and refilling of Earth, carting of Transformers from Store to Site, Fixing of Channels, Supporting Angles, Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing.	20	No	5900	118000.00
14	Erection of DOUBLE POLE structures with mounting of AB Switch, HG Fuses, Transformers, Lightning Arrestors, Distribution BOX ETC. of 10 Mtr X 200 KG PSC Pole including Excavation of PIT and refilling of Earth, carting of Transformers from Store to Site, Fixing of Channels, Supporting Angles, Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole,	10	No	7430	74300.00




UGVCL

Uttar Gujarat Vij Company Ltd.

CIN – U40102GJ2003SGC042906

	complete As per standard specification but excluding erection of GUY set and Earthing. Code. 9902030003				
15	Erection of DOUBLE POLE structures with mounting of AB Switch, HG Fuses, Transformers, Lightening Arrestors, Distribution BOX ETC. of 9 Mtr to 11 Meter STEEL Poles including Excavation of PIT and refilling of Earth, carting of Transformers from Store to Site, Fixing of Channels, Supporting Angles, Clamps Anti-Climbing Devices, Danger board, Insulators, ETC. complete and Painting of Fabricated materials and numbering of pole, complete As per standard specification but excluding erection of GUY set and Earthing. Code. 9902030007	10	No	6899	68990.00
16	Erection of GUY SET including Excavation of PIT and refilling of Earth, AS PER STANDARD SPECIFICATION WITH STAY CLAMPS, STAY WIRE, ANCHOR ROAD, TURN BUCKLE, EYE BOLT, GUY INSULATORE, CC BLOCK ETC. 9902040001	300	No	364	109200.00
17	CONCRETING OF POLES, GUYS, ETC. INCLUDING COST OF CEMENT SAND METAL (1:2:4) AND WATER ETC. AS PER STANDARD SPECIFICATION	40	CMT	5900	236000.00
18	Erection of COIL TYPE/ CI PLATE TYPE EARTHING INCLUDING COST OF COAL SALT ETC. BUT WITHOUT COST OF GI WIRE AS PER STANDARD SPECIFICATION Code. 9902040002	400	No	419	167600.00
19	STRINGING OF 30MM ² ACSR/34MM ² , 55MM ² AAA CONDUCTOR FOR 11/22KV & LT LINES INLCUDING FIXING OF INSULATORS, BINDING JUMPERING ETC. Code. 9903000001	40	Km	1373	54920.00
20	STRINGING OF DOG. CONDUCTOR FOR 11/22KV & INLCUDING FIXING OF INSULATORS, BINDING JUMPERING ETC Code. 9903000001	4	Km	3162	12648.00
21	PROVIDING OF 1-ph NEW CONNETIN WITH PVC 2.5 MM ² CABLE FROM TERMINAL POLE TO METERING POINT INCLUDING FIXING OF METER, MMB(SMC) SERVICE PIPE, GI WIRE NO-10,EGG INSULATOR REEL INSULATOR WITH METEREARTHING COMPLETE WORK AS PER STANDARD SPECIFICATION ETC. Code. 9912020008	20	No	258	5160.00
22	Providing Three phase 4 wire service connection with PVC 4mm ² /10mm ² four core cable from terminal pole to metering point including fixing of meter with meter earthing complete work as per slandered specification but excluding cost of material Code. 9912020008	20	No	355	7100.00
23	PROVIDING GUARDING TO HT LINE/LT LINEON ROAD / RAIL CORSSING	100	Meter	58	5800.00
24	LT LINE TAPPING SINGLE PHASE (WHERE ADDITIONAL NUT BOLTS & FABRICATIONS/U- CLAMPS FITTING IS REQUIRED Code. 9901000002	200	No	32	6400.00
25	LT LINE TAPPING THREE PHASES (WHERE ADDITIONAL NUT BOLTS & FABRICATIONS/U- CLAMPS FITTING IS REQUIRED Code. 9901000002	100	No	59	5900.00
26	Stringing / Laying of overhead LT cable for road crossing HT line crossing & telephone line crossing ETC. Code. 9906000001	38	No	162	6156.00




UGVCL

Uttar Gujarat Vij Company Ltd.

CIN – U40102GJ2003SGC042906

27	Dismantling of 8 Mtr. PSC POLE in usable Condition with crediting of fabrication at STORE & STACKING OF POLE AT SAFE AND ON ROAD SIDE	60	No	511	30660.00
28	Dismantling of 10 mtr psc pole/ 13 MTR. GIRDER SIZE 100X150 MM IN USABLE CONDITION WITH CREDITING OF FABRICATION AT STORE & STACKING OF POLE AT SAFE AND ON ROAD SIDE Code. 9907000017	40	No	1028	41120.00
29	Dismantling of transformer centre (PSC Pole) with crediting of fabrication materials & Transformer at store and safe stacking of pole at road side with Transformer Code. 9907000007	10	No	3025	30250.00
30	Dismantling of transformer centre (PSC Pole) with crediting of fabrication materials & Transformer at store and safe stacking of pole at road side. Without Transformer Code. 9907000007	10	No	2057	20570.00
31	CARTING OF PSC POLE AT DESTINATION (PER POLE) MORE THAN 4 KM & UP TO WORK DESTINATION Code. 9914020002	80	LS	246	19680.00
32	Replacement of 11 KV PIN INSULATOR by new pin insulator /Composite Pin Insulator with Binding Code. 9908000002	1000	No	31	31000.00
33	Replacement of 11 KV DISC INSULATOR WITH H/W by new Disc Insulator / Composite Disc insulator As per Specification. Code. 9908000003	200	No	106	21200.00
34	Replacement of LT Shackle insulator By New One. Code. 9908000008	100	No	21	2100.00
35	Re Fixing OF V cross arm in proper positions. Code. 9911000010	100	No	41	4100.00
36	Replacement of V cross arm By New One. Code. 9911000010	100	No	139	13900.00
37	Re Fixing of Top fitting arm in proper positions Code. 9911000010	100	No	27	2700.00
38	Replacement of Top Fitting Bye New One Code. 9908000002	100	No	34	3400.00
39	Straighting of tilted PSC Poles/ RSJ Poles at Pin Point Code. 9911000002	100	No	189	18900.00
40	Straighting of tilted PSC Poles/ RSJ Poles at tension Point Code 9911000002	100	No	207	20700.00
41	Re-Tightening of loose GUY set in all aspects. Code. 9911000007	60	No	104	6240.00
42	Re-Jumpering work of HT/LT LINE for SHACKLE POLE, TAPPING DO AB SWITCHES AS PER SPECIFICATION Code. 9911000031	100	No	59	5900.00
43	Erection Of Support pole (PSC/RSJ) for stay (i.e. stud Pole). 9911000002	100	No	418	41800.00
44	PIN BINDING OF CONDUCTORE & CLEANING OF 11 KV PIN INSULATOR AS PER INSTRUCTION OF ENGINEER INCHARGE Code. 9911000004	100	No	12	1200.00
45	PIN BINDING OF CONDUCTORE & CLEANING OF LT SHACKLE INSULATOR AS PER INSTRUCTION OF ENGINEER INCHARGE Code. 9911000004	101	No	9	909.00
46	Numbering of pole with paint by preparing back ground of one colour & have lettering (Height 3" and width 0.5") as directed by engineer incharge.	30	No	28	840.00





UGVCL

Uttar Gujarat Vij Company Ltd.

CIN – U40102GJ2003SGC042906

	(Colour to be used must have ISI mark, colour to be provided by contractor)				
47	Converting Pin Point to Shackle point including dismantling & restringing etc including the cost of Nuts & Bolts Code. 9908000118	4	No	1619	6476.00
48	REPLACEMENT OF SINGLE PHASE MMB WITH PROPER FITTING.	20	No	50	1000.00
49	REPLACEMENT OF SINGLE PHASE METER WITH PROPER FITTING. (Urban Area) Code. 9908000023	10	No	34	340.00
50	REPLACEMENT OF SINGLE PHASE METER WITH PROPER FITTING. (Rural Area) Code. 9908000023	700	No	45	31500.00
51	REPLACEMENT OF SINGLE PHASE OLD SERVICE BY NEW SERVICE By using GI wire no 10., Real insulators, two nos Egg insulators including labor of fitting of necessary accessories at consumer end as per specification. Including the cost of Nuts & bolts. Code. 9908000016	100	No	170	17000.00
52	Removal / Dismantling of Existing HT/LT line conductor from line 34/55 MM2 and crediting to store. Conductor has to dismantle from shackle to shackle pole, with minimum nos. of cut piece as instruction of Engineer incharge. Code. 9907000009	8	Per Cond Per KM	650	5200.00
53	Removal / Dismantling of Existing HT/LT line conductor from line DOG 100 MM2 (Above 55MM2 size conductor) and crediting to store. Conductor has to dismantle from shackle to shackle pole, with minimum nos. of cut piece as instruction of Engineer in charge. Code. 9907000009	8	Per Cond Pe KM	1450	11600.00
54	Re-stringing of HT & LT line (34 mm2 to 55mm2) conductor/coated conductor with new pin binding (SPAN-35 MTR) Code. 9911000008	2	1 Wire per span	69	138.00
55	Re-stringing of HT & LT line (Above 55mm2 size conductor) conductor /coated conductor with new pin binding (SPAN-40 MTR) 9911000008	2	1 Wire per span	71	142.00
56	Trimming of TREE BRANCHES on strutting HT/LT line on one tree size more than 5 inch.	289	Per tree	35	10115.00
57	Trimming of bigger size of tree branches/whole tree on strutting HT/LT line Code. 9911000009	15	Per Day per labour	315	4725.00
	Total Rs. (A)			Total	1999999.0
	Bidders offer(+/-) in % (B)				
	Grand Total (C) = A +/- (A*B)				
	Goods and service Tax D= C x GST % GST Rate: ____% SAC Code:				
	Grand Total including GST E= C + D				



	Final Offer in RS.=				
	Final Offer RS. In words				

The Bidder shall quote Firm Price only. The price quoted will not be subject to any escalation till completion of work.

Nut & Bolt will be supplied by UGVCL KADI DO. If same are not available with UGVCL Kadi Store & provided by contractor than it will be reimbursed after producing of bills. But rate of Nut-Bolt claimed should not be more than the last purchase rate of UGVCL Kadi & at present it is Rs. (63+18 % GST) per Kg.

The Above prices are inclusive of all taxes, levies Duties etc. except Goods & Service Tax (GST). **GST will be paid extra as applicable from time to time on a given taxable goods and /or services.**

Executive Engineer
U.G.V.C.L. KADI DO

Contractor's Name & Signature

GENERAL INSTRUCTION TO TENDERERS

1. Sealed Tenders are invited for the work of erection, dismantling and maintenance work of HT/LT line & T/c. from the contractors / firms who have executed works of similar nature and magnitude successfully.
2. Demand Draft date should be on or in between “one month before from the last date of receiving of tender to last date of receiving of tender.
3. Tender documents are in two bids system i.e. “**Technical Bid**” and “**Price Bid**”. Bidder has to submit tender in one Envelop and in this two different covers should be put. One cover mentioning **Technical bid** on it & another cover mentioning **Commercial Bid** on it. If we receive envelop that do not have two separate sealed covers than those bids are liable to be rejected. Technical bid should be submitted with documents as under, failing which tender is liable for rejection. Also **Price Bid” shall be submit in “ON LINE” only**
4. Technical bid is to be submitted in a separate sealed envelope and subscribing the envelope as “**Technical Bid**”.
Technical bid should be submitted with documents as under, failing which tender May liable for rejection.
 - i. **Solvency certificate issued from any Nationalized Bank amounting to sum equivalent of estimated cost (Minimum 10 Lacks)**



- ii. Separate EPF code No. allotted by RPFC required EPF paid Challan copy of last six month.
- iii. Copy of PAN card.
- iv. Work Order Copies of Three Different financial year's whose total amount Rs.40 lakh. For erection of HT/LT line & T/C work from only UGVCL/any DISCOM subsidiary of GUVNL (PGVCL/MGVCL/DGVCL) is required. Attach year wise separate sheet with work order or experience certificate and summary of order wise amount list.
- v. Contractor will have to submit the certificate of Electrical contractor license.
- vi. Tools-Tackles statement.
- vii. Vendor Registration Certificate of UGVCL as Minimum Class A (Class-B, C & D will not be considered), as a contractor with UGVCL required.
- viii. GST Tax Registration Number.
- ix. Group Insurance copy of the insurance policy of the insured laborer's under W.C. Act.
- x. Turn over details year wise on CA Letterhead At least 3 financial years

The above documents should be submitted in form of attested true copies along with technical bid.

5. The sealed price bids comprising of Schedule-'B' should be submitted in separate sealed envelope subscribing the envelope as **"Price Bid"**.
6. **Both "Technical" and" Price" bid should be submitted in one common envelope subscribing the name of the work and tender opening date etc.**
7. The bidders shall submit their offer without any deviations in general terms and conditions of the contract or in Technical specification/items. Tenders of such deviations may also be rejected. Incomplete and conditional tenders shall not be considered.
8. The rates shall be quoted both in words and figures as per unit specified in schedule-'B' in case of any discrepancy between the rates quoted in words & figures, rate quoted in words will prevail.
9. It is mandatory for all bidders to submit their tenders documents by both forms of online (e-tendering in n code) and physically in scheduled time. If tender is submitted in any one form, i.e. either by on line OR physically, the bid shall not be considered. Bidders shall submit price **Bid On-line (n code) only and not in Physical form.**
10. Bidders are requested to submit price-bid in on line (**e-tendering n code form**) only and not to submit the price bid in physical form. This is mandatory. If price bid is submitted in physical form, same will not be opened and only **on-line (n code) submitted price bid will be considered for evaluation.**
11. Intending bidders should submit their tenders after studying all tenders documents carefully and visiting the site for satisfying themselves of actual site conditions, location and accessibility of site and



nature, extent of the work involved etc. Submission of tenders implies that bidders have obtained all necessary information and other data required for executing the work.


12. Documents mentioned as per tender terms and condition shall be submitted in the technical bid. In case of non-submission of mandatory document or attachment of wrong document, bid will be rejected out rightly at UGVCL, Kadi DO discretion.
12. “Price bid” of only qualifying bidders on the basis of Technical bid shall only be opened. Price of bidders, who are not qualified technically as per requirement of technical bid shall not be opened.
13. All the works shall be carried out as per company standard specifications & work quantity may be increase or decrease during actual work within order amount.
14. Tenders, which do not fulfill all or any of the conditions of the tender of incomplete in any respect may liable to rejection.
15. **Executive Engineer, UGVCL Kadi DO, reserves the right to accept or reject any or all tenders without assigning any reason thereof.**
16. Income Tax at prevailing rate will be deducted as per Income Tax Act.
17. **The rate shall be excluding of GST tax. GST will be applicable as per UGVCL rule.**
18. Any change in rate of GST Tax shall be entertained during contractual period of contract.
19. Bidders should be in touch with the above websites for information regarding revision/corrigendum/Amendment in tender till due date of online submission and there after No separate information shall be sending this regards.

GENERAL TERMS AND CONDITION FOR ERECTION WORKS

1. Good quality paints & red oxide like Asian, Nerolac, burger etc. make shall only be applied for Numbering & Painting.
2. If numbering are not done as per Specifications standard due to negligence from your side in that Case rate of Rs. 25 /- per location will be deducted from the bill.
3. Painting to the fabrication materials carried out by Departmentally and the same amount as actual cost & expenditure towards processing and administrative charges on material weight base will be deducted from the contractor bill. In case if painting done to fabrication materials by contractor then it must as per standard specification and good quality of work required. Most probably painting work to fabrication material done by departmentally
4. If Transformer is not carting & commissioning then Rs 1500/- per Transformer or actual cost for TC carting will be deducted in your bill.




5. Charges for mounting of AB Switches and distribution boxes are including in item i.e. Erection of T/c. If AB switch and dist.box is not provided by UGVCL in that case Rs.100/- for each items shall be deducted for the bill or it same are not provided by contractor on the part of his negligence in that case Rs.500/- for each item shall be deducted from the bill.
6. If earthing of Pole or DP structure is not found in a separate PIT as per standard than such earthing work shall not be considered as a executed earthing quality and such earthing shall be executed by UGVCL through other agency and amount incurred shall be deducted from the bill.
7. UGVCL does not accept any responsibility as Factory Act, Minimum Wages Act Workmen's Compensation Act, Insurance Rules etc .or any other act rules or regulations that have to be Observed by the contractor for carrying out the work.
8. The contract will be governed by the UGVCL as per works terms and conditions of the UGVCL.
9. The contractor will be faulty answerable and responsible for all the material issued to him for the work by the UGVCL any theft and loss or pilferage shall have to be borne by the contractor.
10. All Fabrication material for Erection of pole will be Provided by UGVCL from Kadi Divisional store i.e. V cross Arm, Top fittings, side clamps, MS angle 9',4',2, MS channel 9',Anchor rod, Turn buckle, U clamp etc
11. Loading Unloading of all materials from division store will be borne by contractor.
12. Material carting from Division store to site will be borne by contractor.
13. PSC/Girder pole carting at site within two kilometer range will be borne by contractor.
14. The contractor will be solely responsible for any accident/damage either to equipments or any Human being during the time of execution of work.
15. All other general terms and conditions as prevailing in the UGVCL shall be applicable to this work Contract.
16. The contractor must engage sufficient knowledgeable person round the clock, exclusively for Execution of work.
17. The contractor has to carry out all the works in accordance with revised and latest provision under I.E .Rule Act (Amended time to time) made there under and as per instruction of Engineer in charge.
18. Tools, Tackles, Manpower, Crane facilities etc. not be provided by the UGVCL.
19. The compliances of all Central/State Govt. Rules, safety and Insurance rules etc. and that of local Body is must conditions for the agency.
20. In case, it is not possible for the contractor to continue the work either due to heavy rains or other Reasonable causes, such facts should be immediately brought to notice of the Engineer In charge. If the reasons for stopping the work are genuine the Engineer In charge may ask the contractor to start the work again as per condition. The period of such stoppage will not be considered as a part of working days moreover the contractor cannot claim compensation for such stoppage. If contractor not carried out the work as per instruction & time limit given by E.I.C then work is completed by some other resource hiring by E.I.C & the Amount incurred of work is deducted from contractor Bill.



21. As regard damages to the materials, equipment's, contractor himself will be responsible. If there is any compensation to be paid in respect of "WORKMAN "Compensation Act or any other statutory Provisions, the same will be paid by contractor directly. If he thinks fit, he may take necessary Insurance covering at his cost.
22. Time limit extension will be given if material is not supplied in time and in any case of objection not cleared in time but if materials given in time and there is no any objection, then no time limit Extension will be granted and penalty will be imposed as per rules.
23. The erection work should be carried out according to the specification as per instructions and Programmed laid out by the Engineer in charge. Contractor has to ensure safe shifting and erection of all accessories/equipment's as per standard norms.
24. All the works shall be carried out in accordance with latest rules under Electricity Act.2003(with Amendments). After completion of work execution required Tests are to be taken in presence of Engineer In charge.
25. The contractor should employ as a Supervisor with sufficient qualification and experience who could Supervise the execution of work throughout. He should always be present on the site at the time of Work.
26. No higher rate or revised rate will be applicable for the work, if work is held-up/ closed due to Whatever so reasons.
27. **Penalty clause: in case, the work is not completed within the period stipulated in the sub work order, penalty shall be levied at 0.5 per week on the total sub work order subject to maximum 10 % of respective sub work order.**
28. If work will not be carried out within time limit of sub work order, work will be carried out by other agency at risk and cost of contractor and the amount will be deducted from respective Bill/SD. SDO is authority to decide the agency for non-completion of work.
29. Successful Bidder is bound to work under any S/Dn of Division Office Kadi in any scheme if require with the same rate, conditions & without any type of extra charges.
30. All types Nuts & bolts (Should be as per UGVCL sample and specification) will be supplied by UGVCL, if same is not available in any extreme case and if provided by contractor Rs.63/-(Sixty three) +18 %GST per Kg shall be paid by UGVCL to contractor.
31. In tree cutting Rate for cut the branches whose thickness is greater than 3" inch. For Tree cutting Manpower issued as per instruction of in charge Engineer.
32. **If the bill for the work, after reconciling inventory given to contractor and depositing back the surplus material to respective Division Store, is not submitted within three month from the work completion date per work completion due, then penalty @200 per week or part thereof plus applicable GST subject to maximum of 10% of order value plus applicable GST will be deducted.**
33. All legal complication of disputes is subject to KADI JURISDICTION ONLY.



Save Energy for Benefit of Self and Nation



UGVCL
Uttar Gujarat Vij Company Ltd.

CIN – U40102GJ2003SGC042906

Contractor's signature with seal.

Executive Engineer
U.G.V.C.L. KADI DO.