UTTAR GUJARAT VIJ COMPANY LIMITED CIRCLE OFFICE - MEHSANA SCHEDULE - B

Name of work: Rubble, Sand filling, Yellow Earth at Sami Sub Division Office Building at 66 KV S/S Sami.

Sr.No.	Description	Qty.	Unit	Rate	Amount
1	Providing and filling rubbles including hand packing and filling interstices with quarry spalls behind abutments and between returns as directed. (upto 10 ton)		CMT	997.09	37889.42
2	Filling in foundation & plinth with murrum or selected soil in layers of 20cm. Thickness including watering, ramming and consolidating etc. complete.	480.00	CMT.	238.69	114571.20
3	Filling in plinth with sand under floors including watering, ramming, consolidating and dressing etc. complete.		CMT.	398.20	8362.20
Α	Estimated Cost				160822.82
В	Add 1% wellfare cess on A				1%
С	Total including Wellfare cess C = A + B				
D	GST Rate SAC Code9954			18%	
Е	Total Amount with 1% welfare cess and 18% GST [E]				
F	Bidder's Offer (+ / -) in %[F]				
G	Grand Total $G = [E +/- (E*F)]$				
	Final Offer (in Rs.)				
_	Final Offer (Rs. In Words)				

We have read and clearly understood the terms, conditions, Schedule 'B' and Technical specifications put up by UGVCL on WEB site.

I/We hereby accept all the conditions and specifications of this tender document, and accordingly, I/We am/are willing to carry out the work at quated rate as above.

SIGNATURE OF CONTRACTOR (With rubber stamp/seal of the company)

Superintending Engineer Circle Office, Mehsana