

SCHEDULE-B

	SCHEDULE-B					
WORK:	Renovation-colour work of ADM office building, compound wall at Mehsana Ind & Highway sdn office building under Mehsana Division.					
Item No.	Description	Qty.	Unit	Rate	Amount	
1	Removing dry or Oil bound distemper by washing and scrapping and sand papering the wall surface smooth including necessary repairs to scratches complete	2400.00	SMT	6.89	16536.00	
2	Removing and scraping of old deteriorated plaster of any thickness fromm wall / R.C.C member including stacking of serviceable material and disposal of unserviceable from site of work with all lead and lift		SMT	11.92	715.20	
3	Half brick masonary in common burnt clay building bricks having crushing strength not less than 35 Kg./Sq.cm. in cement mortar 1:4 (1cement :4 coarse sand) in super structure above plinth level up to floor two level. (B) CONVENTIONAL BRICKS	8.00	SMT	420.30	3362.40	
4	Providing 20mm. Thick double coat mala cement plaster on interior brick / concrate work for plastering comprising of base coat of 12mm thick cement plaster in (i) Cement mortar 1:4 (1 cement :4 coarse sand)in rough finishing and 8mm thick top coat of cement mortar 1:2 (1 cement :2 coarse sand) finished with trovel incl. scafolding, curing etc complete.		SMT	170.22	1702.20	
5	20mm. Thick sand faced cement plaster (Tipani with Gutka) on walls up to height 10 meters above ground level consisting of 12mm. Thick backing coat of C.M. 1:3 (1 cement: 3 sand) and 8 mm. thick finishing coat of C.M. 1:1 (1 Cement: 1 sand) etc Complete.		SMT	189.23	21761.45	
6	Wall painting two coats with weather proof acralic emulsion APEX type paint of approved brand & manufacture and of required shade on exterior wall surface to give an even shade over and including a primery coat with alkaly resistance primer of approved brand after throughly brushing surface to remove all dirt and remains of loose powdered materials etc comp. for all height.(R.A)	4550.00	SMT	65.60	101680.00	
7	Applying One coat of Birla Or Asian acrylic lapi (putty) & two coats of primer approved brand and manufacture on new wall surface to give an even shade including throughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth	650.00	SMT	23.71	15411.50	
8	Distempering (Two coats) with oil bound distemper of approved brand and manufacture and of required shade on wall rurface to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thouroughly brushing the surface free from mortar dropping and other foreign matter and also including preparing the surface even and sand papered smooth.	2400.00	SMT	45.88	110112.00	
9	Scraping oil paint from steel and other metal surface and making the surface even (with Hand Scraping.)	200.00	SMT	31.00	6200.00	
10	Painting two coats (including priming coat) on previously painted steel and other metal surface with enamel paint, brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter.(No repit Colour/Shad)		SMT	95.23	19046.00	
11	Providing & fixing CERA make wash basin with single hole for pillar tap with C.I. or M.S. brackets painted white including cutting holes & making good the same but excluding fittings. Vitreous China Flat back of size 550mm. X 400mm. Colour as directed by EIC	1.00	Each	947.28	947.28	
12	Providing & fixing pillar tap capstan head, screw down high pressure with screws, shanks and back nuts. 15MM DIA.	4.00	Each	355.93	1423.72	
13	Providing & Fixing Screw down bib taps of following size (B) Brass chromium plated screw down bib tap of 15MM. Dia.	4.00	Each	215.72	862.88	
14	Providing & fixing C.P. brass waste for wash basin or sink (B) 40mm. Dia.	7.00	Each	103.20	722.40	
15	Providing & fixing brass screw down stop tap (A) 15mm. Dia.	8.00	Each	237.29	1898.32	

Item No.	Description	Qty.	Unit	Rate	Amount
16	Providing & Fixing white / coloured porcelain flat back wall type URINAL PAN of CERA make having size 590 * 375 *390 mm of approved quality & make including waste coupling bends & necessary outlet of 25mm.dia. G.I. Pipe connections including providing brass stop cock (pillar cock type), PVC connection, spreader & spreader pipes, brackets etc., completed as directed by E.I.C.	2.00	Each	2280.00	4560.00
17	Providing & fixing PVC SWR Nahani trap IS 14735 for drain - 100 mm diameter with jali of the following nominal diameter of self cleansing design with C.I. screw down or hinged grating including cost of cutting & making good the walls and floor (100mm. Inlet and 50mm. Outlet)	2.00	Each	438.99	877.98
18	Providing & Fixing S.W. Gully trap with C.I. grating brick masonary chamber & water tight C.I. cover with frame of 300mm X 300mm.size inside with standard weight. (i) Square mouth trap (B) 150mm. X 100mm. size P or R type.	2.00	Each	1215.89	2431.78
19	Providing, Laying and jointing in true line & level 15mm dia. U-PVC pipe (SCH-40) line including fittings of make as approved by EIC. Pipe shall be fixed on the wall with the help of clamp at every two meter C/C OR shall be concealed as directed including necessary fittings etc including testing of pipe and joints and fixing the same with adhesive solvent including cost of all materials and labour etc complete.	20.00	Rmt	84.87	1697.40
20	Providing, Laying and jointing in true line & level 25mm dia. U-PVC pipe (SCH-40) line including fittings of make as approved by EIC. Pipe shall be fixed on the wall with the help of clamp at every two meter C/C OR shall be concealed as directed including necessary fittings etc including testing of pipe and joints and fixing the same with adhesive solvent including cost of all materials and labour etc complete.	40.00	Rmt	107.29	4291.60
21	Providing, Erecting & Fixing ready made double coated sintex P.V.C. (ISI) or equivalent ISI water storage tank of required capacity each with cover including providing & fixing one 20mm.dia. float valve ball-cock, one 20mm dia. G.I. Waste pipe with plug, one 25mm dia. G.I. over flow pipe of length up to 0.30mt. including making all connection for inlet/outlet supply with necessary fittings etc. complete on terrace. (A) 1000 Liter capacity	2000 00	Lit.	4.61	9220.00
22	Providing cement vata (10cm X 10cm. Size) quarter round in cement mortar 1:1 including neat cement finishing, watering etc Complete.	80.00	RMT	17.58	1406.40
23	Helper	10.00	Days	199.90	1999.00
24 25	Carpenter 1st class Polishing with french polish on previously polished wood and wood based surface to give an even surface including cleaning, the surface of all dirt, dust and sand papered smooth and including a coat of wood filler.		Each SMT	294.00 52.27	1470.00 3136.20
26	Applying general insecticide pest control treatment to floors, cupboards etc including labour material etc. complete. Using Heptachloride 20 EC. As Per 6113_pests Consentration Weight 0.50 percent is recommended one litre chemical emulsion dillute with 39 liter of water will give. Total dillute concrentration will be 40 litre inclusive of one litre chemical emulsion application 0.5 Litre chemical / Sqm of surface is recommended as per I.S	330.00	SMT	67.78	22367.40
27	Providing & laying POLISHED KOTAH STONE slab 25mm . Thick in risers of steps dado and pillars laid on 10mm. thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry including rubbing & polishing etc Complete.		SMT.	677.05	1692.63
28	P/F powder quoted GI sheet of Jindal or equivalent make having width of 1050mm (effective 1000mm) of 0.6mm thick of required clour blue/or white with instakllation as per directied by EIC complete etc. The rates are excluding cost of Purlins, Rafters and trusses etc.	80.00	SMT	600.00	48000.00
29	Steel work welded in built up sections, framed work including cutting, histing, fixing in position and applying a priming coat of red lead paint :-(A) In beams and joints channels angles, tees, flats with connecting cleats as in main and cross beems, hip and jack reffers, purlins connected to common raffers and the like.		Quintel	6021.76	19269.63

Item	Description	Qty.	Unit	Rate	Amount	
No.						
30	Providing and fixing 12.5 Litres high level CI. flushing cistern with A pair of C.I. or Mild steel brackets, womplete with fittings such as syplionic arrangement, 15mm nominal size brass ball valve with polythene float, lever G.I. China (60 cm.) and pull union and couplings for connections with inlet, outlet and overflow pipes etc. including cutting holes in walls and making good the same (overflow pipe to be measured and paid fo separately)	2.00	Each	1033.69	2067.38	
31	Providing and Fixing capsule door closed to the Door as directed by EIC	0.00	Each	100.00	0.00	
32	Providing & laying broken china mosaic tiles flooring for terrace using 12 mm to 20 mm broken pieces of glazed tiles to be laid over cement mortar 1:3 to plain or slope and to be tempered to bring mortar crème out upto surface using white cement including rounding off the junctions and extending them upto 15 cm along the wall including water pond test and clearing with water and oxalic acid etc complete as directed.		SMT.	470.72	47072.00	
Α	Total Estimated Amount Rs					
В	Bidder's Offer (+ / -) in % [B]					
С	Grand Total C = A +/- (A*B)					
D	Add 1% Welfare Cess on C					
E	Total including Welfare Cess E = C + D					
	GST Rate9954					
F	Goods & Service Tax F = E X GST% i.e. 18 % as applicable on the date of tender in amount Rs.					
G	Grand total including GST & Welfare Cess G = E+F					
	Final Offer (in Rs.)					
	Final Offer (In Words)					
We have read and clearly understood the terms, conditions, Schedule 'B' and technical specifications put up by UGVCL on website. I/We hereby accept all the conditions and specifications of this tender document, and accordingly, I/We am/are willing to carry out the wo						
	ature of Contractor Superintending Engin					
	(With rubber stamp/seal of the company)		na			